



UNIVERSITY OF TORONTO




3 1761 01499191 3





Digitized by the Internet Archive
in 2007 with funding from
Microsoft Corporation



84

1909

No. 11.

THE ENGLISH PEASANTRY
AND THE
ENCLOSURE OF COMMON FIELDS

Studies in Economics and Political Science

Edited by H. J. MACKINDER, M.A., Director of the
London School of Economics

No. 14.

THE ENGLISH PEASANTRY
AND THE
ENCLOSURE OF COMMON FIELDS


Illustrations in Facsimile and Original

Printed by H. J. Johnson, 21, Abchurch Lane, London, E.C. 4

London, 1881

No. 4

THE ENGLISH PEASANTRY
AND THE
ENCLOSURE OF COMMON FIELDS





OPEN FIELDS AT EPWORTH, ISLE OF AXHOLME.

THE ENGLISH PEASANTRY AND THE ENCLOSURE OF COMMON FIELDS

BY

GILBERT SLATER, M.A., D.Sc.

WITH AN INTRODUCTION BY THE RIGHT HONOURABLE
THE EARL OF CARRINGTON, K.G., G.C.M.G., Etc.

President of the Board of Agriculture

93/5
28/11

LONDON

ARCHIBALD CONSTABLE & CO. LTD.

1907

BRADBURY, AGNEW, & CO. LD., PRINTERS,
LONDON AND TONBRIDGE.

AUTHOR'S PREFACE.

THE investigations embodied in this book were begun in 1894, on the suggestion of Mr. Graham Wallas, and at the request of Mr. J. A. Spender. They were continued in subsequent years, in conjunction with the London School of Economics, and the results were summarised in a thesis entitled "The Enclosure of Common Fields in England in the Eighteenth and Nineteenth Centuries," which was submitted to the University of London in 1904, and approved as a thesis for the degree of Doctor of Science in Economics. That thesis consisted in the first place of a series of maps, partially reproduced in this volume through the kind assistance of the Royal Geographical Society; and in the second place of manuscript matter which has been revised for publication in the form of this volume and under the present title. The original maps are in the custody of the London School of Economics, and can be seen by those who desire to examine them. They include a series of county maps, on which parishes in which common fields have been enclosed by Act of Parliament are coloured and marked according to the date of enclosure, and maps illustrating the process of Parliamentary enclosure, and the working of the common field system. Those who are interested in the enclosure history of any particular county may also be recommended to consult the Victoria County History.

It is my pleasant duty here to gratefully acknowledge my obligations to the two gentlemen above mentioned for the original impulse to study the process of the destruction and decay of English village communities; to the London School of Economics; and in particular to its first Director, Mr. W. A. S. Hewins, its present Director, Mr. H. J. Mackinder, and Mr. Hubert Hall,

for assistance, encouragement, and advice ; to many labourers, farmers, clergymen, and other rural residents, for information and personal kindness ; to the Royal Geographical Society for defraying the cost of the production of the blocks of the illustrative maps herewith published ; and to Earl Carrington, the President of the Board of Agriculture, for reading the book in proof, and recommending it to those who are willing to study rural history because they desire to improve rural conditions of life.

In writing this book I have deemed it a matter of conscience to preserve the attitude of mind of the student of history, pure and simple. I have felt, and feel, that historical investigation can only be rightly carried on when all motives except the simple desire to know the truth are excluded from the investigator's mind. Yet the investigation undertaken having been thus far completed, and its results placed on record, I cannot refrain from attempting to read out of them some lessons for the present and the future.

My conclusions have been in large measure expressed for me by Lord Carrington's Introduction. The policy of the legislature and of the Central Government, expressed in the Enclosure Acts of the eighteenth and nineteenth centuries, though it claimed, and on the whole rightly claimed, that it effected an immediate and great increase in the country's output of agricultural produce, and an improvement in the breeds of sheep and cattle, was nevertheless essentially a policy directed towards the enhancement of agricultural rents, the building up of large and compact landed estates, the establishment of capitalist farming, the uprooting of peasant proprietors and of small holdings together with the communal use of land, and the multiplication of the class of landless agricultural labourers. There is need in the twentieth century for a new agricultural policy. As I read the economic signs of the time, industrial conditions are beginning to favour a great agricultural revival in the British Isles. A wise programme of rural reform is necessary both in order that the possible agricultural prosperity may be secured, and in order that the nation may

reap in full its possible fruits of physical and moral well-being for the people.

In all times the fading memories and traditions of the past have contributed to form in men's minds the ideals of a possible better future state of society which are the inspiration of progress. The memories and traditions of the English village community, together with its visible relics in the form of commons, commonable meadows, and (rarely) common fields, have had their influence on the formation of the ideals of the Labour and Democratic movement of our country from the time of Cobbett onwards. Through historical research the past may become more definitely suggestive.

The suggestions borne into my mind for the agricultural policy of the twentieth century may be summed up in the phrase, British agriculture must be democratised. By this I mean that the principle of collective ownership of the soil must be established or re-established; that agricultural co-operation must be revived in new forms suitable to modern conditions; that the ancient right of independent access to the soil for every tiller of it must be restored; that a career of industrial advance in agriculture must be made possible for the competent worker. On one important side of the life of the old English village community I have not touched at all in this book, viz., its social and recreative side. In this respect also the losses of the past will probably be recovered spontaneously if the nation aims in its agricultural policy at the three essentials of wholesome, hopeful, human work, as opposed to dehumanised toil, Freedom, Training and Mutual Aid.

GILBERT SLATER.

January 10th, 1907. ^

CONTENTS.

CHAP.	PAGE
I. ENCLOSURE IN GENERAL	1.
II. THE MERCIAN TYPE OF VILLAGE COMMUNITY	8
III. THE WESSEX TYPE OF VILLAGE COMMUNITY	19
IV. EXTENT OF EXISTING COMMON FIELDS	36.
V. THE ISLE OF AXHOLME	52
VI. SOME RECENT ENCLOSURES	63
VII. AGRICULTURE IN OPEN FIELD PARISHES A HUNDRED YEARS AGO	73.
VIII. NORFOLK AGRICULTURE	78
IX. 13 GEO. III. C. 81	87
X. ENCLOSURE AND DEPOPULATION	91.
XI. ENCLOSURE AND THE POOR	117
XII. THREE ACRES AND A COW	129
XIII. STATISTICAL SUMMARY OF ENCLOSURE BY ACT OF PARLIAMENT	140
XIV. ENCLOSURE OF COMMON FIELDS WITHOUT PARLIA- MENTARY SANCTION	148.
XV. RUN-RIG AND COMMON FIELD	164
XVI. COMMON FIELDS IN NEW ENGLAND	183
XVII. THE PROGRESS OF ENCLOSURE WITHOUT PARLIA- MENTARY SANCTION	187
XVIII. THE RESULTS OF ENCLOSURE	261.

APPENDIX A. STATISTICAL SUMMARY OF ACTS ENCLOSING WASTE	267
APPENDIX B. PRIVATE ACTS ENCLOSING COMMON FIELDS	268
APPENDIX C. LELAND'S ITINERARY	314
APPENDIX D. GENERAL ACTS AFFECTING ENCLOSURE	322
APPENDIX E. A NORFOLK OPEN FIELD PARISH	331
INDEX	333

ILLUSTRATIONS.



	PAGE
VIEW OF OPEN FIELD IN EPWORTH, AXHOLME	<i>Frontispiece.</i>

MAPS :—

LAXTON, WEST FIELD, AND PART OF MILL FIELD	<i>To face</i>	8
STRATTON MEADOW	,,	25
ENCLOSURE OF COMMON FIELDS BY ACT OF PARLIAMENT	,,	73
LELAND'S ITINERARY	,,	161
EAST MIDLANDS. SECTION I.		196
EAST MIDLANDS. SECTION II.		197
HAMPSHIRE, SURREY, AND SUSSEX	,,	233
PART OF BRAUNTON GREAT FIELD	,,	250

INTRODUCTION.

THE ENGLISH PEASANTRY AND THE ENCLOSURE OF COMMON FIELDS.

THE enclosure of common fields, and the passing away of the English Village Community to make room for the agricultural organisation prevailing to-day, is a subject not merely of historical interest, but one which touches very closely some of the most vital national problems of the twentieth century.

During the past five generations mechanical, industrial, and commercial progress, with the consequent creation of great towns and cities, has so occupied the national activities, and has made us to such an extent a nation of town-dwellers, that there has been a tendency to overlook rural life and rural industries. But in recent years social reformers have come to see that the solution of many of the problems of the town is to be found in the country, and increasing attention is being paid to the causes of the rural exodus and the best means by which it can be arrested. No industry can be in a healthy condition which does not provide an opportunity for the small man to improve his position ; and consequently such questions as the provision of allotments and small holdings, agricultural co-operation, the preservation of the independence of spirit of the agricultural labourer, and the securing for him the prospect of a continually advancing career on the land are recognised as matters of urgent national importance.

In this book Dr. Slater shows that the movement for the enclosure of arable open and common fields has been a movement for the sweeping away of small holdings and small properties ; that the " Village Community " which any Enclosure Act of this character abolished was essentially an organisation for agricultural co-operation. He shows that at least in certain parts of the country even in comparatively recent times enclosure has produced rural depopulation, and has converted the villager from " a peasant with a mediæval status to an agricultural labourer entirely dependent on a weekly wage." He further makes us doubt whether these little village revolutions, while they temporarily stimulated agricultural progress by facilitating improved stock-breeding and the economy of labour, did not also to a certain extent destroy the opportunities of future progress by separating farmer from labourer by a gulf difficult to cross, and thus cutting off the supply of new recruits to the farming class.

At the same time, whatever reasons there may be for regretting the enclosure of our Common Fields, and for wishing that the interests of the humbler tillers of the soil had been more sedulously guarded on enclosure, in the main the process was inevitable. Common field Agriculture was a survival of customs and institutions which had grown up when each village lived its life to a great extent in isolation. It was necessary that the villager should almost forget that he was a Little Pedlingtonian to realise that he was an Englishman. Village patriotism had to die down temporarily to make way for national patriotism ; and when the spirit died out of the Village Community its form could not be preserved.

Now and in the future there is need that local patriotism, pride in the local community, and willingness to serve it, whether it be village or city, should be kindled again to its old vigour.

With the revival of the spirit will come a revival of some of the old forms of village common life, and a creation of new forms in place of those which will remain among the forgotten facts of the past. The Village Community is a hope of the future as well as a memory of the past, and therefore those who are interested in the movement for reviving British Agriculture on democratic lines and for improving the social and economic conditions of our villages have reason to welcome Dr. Slater's attempt to describe existing and recent survivals of the English Village Community, and to ascertain the circumstances, causes, and consequences of its gradual extinction.

CARRINGTON.

28th November, 1906.

THE ENGLISH PEASANTRY AND THE ENCLOSURE OF COMMON FIELDS.

CHAPTER I.

ENCLOSURE IN GENERAL.

THE internal history of our villages is a more obscure, but not less important a part of English history, than the internal history of our towns. It is, indeed, more fundamental. A town is ordinarily by origin an overgrown village, which never loses the marks of its origin. And it was by agricultural and social changes in the villages that the way was prepared for the great industrial revolution, or more properly, evolution, which is the underlying fact of the history of English towns, especially during the last two centuries.

The central fact in the history of any English village since the Middle Ages, is expressed in the word "enclosure." Primarily "enclosure" means surrounding a piece of land with hedges, ditches, or other barriers to the free passage of men and animals. Agriculturally, enclosure of arable land in the midst of unenclosed arable land is a preliminary step to its conversion into pasture, the hedge is erected to keep animals in; enclosure of land in the midst of open common pasture is a preliminary step to tillage, the hedge keeps animals out. But in

holding of, say, twenty acres of arable land would consist of about thirty separate strips of land of from half an acre to an acre each, scattered over all the three or four arable fields, but approximately equally divided between each field, so that each year the occupier would have, for example, about five acres under wheat, five under barley, five under pulse, and five fallow, provided that were the customary course of husbandry. Right through the year the fallow land would be used as common pasture, and the land under crops would become commonable after the crops were carried.

Along the streams flowing into the river Ivel would be the open commonable meadows. These would be divided into a number of plots, half-acres, quarter-acres, or even smaller, marked by pegs driven in the ground, or stones; and a certain number of these plots were assigned to each holding, in proportion to the amount of arable land. During the spring, while the cattle were on the common pasture, the meadow would be let grow for hay; when the time for hay harvest came, each peasant cut his own plots, and the meadow became commonable during the rest of the summer. Some of the peasant occupiers would be small freeholders, some probably copyholders, others legally annual tenants. All would meet together on certain occasions to settle questions of common interest.

We might say, though the expression must not be too rigidly interpreted, that under the common field system the parish, township, or hamlet formed one farm, occupied and cultivated by a group of partners holding varying numbers of shares. It may well be imagined what a village cataclysm took place when an Act for the enclosure of the parish was passed, and commissioners descended upon the village, valued every property and every common right, and carved out the whole parish into rectangles, instituting the modern system of separate exclusive ownership and individual cultivation. We shall see that ordinarily the holdings on enclosure became fewer and larger, that very many of the peasants were in consequence driven from the village, or became landless, pauperised agricultural labourers. We shall see also that the traditions of the common field system where

they have perished as distinct memories, have survived in the form of aspirations for agricultural reform. In fact, the great rural question for the twentieth century to determine, is whether there were not beneath the inconvenient and uneconomical methods of the common field system, a vital principle essential to true rural prosperity, which has to be re-discovered and re-established in forms suitable to the present environment.

It is not intended in this book to go into the vexed question of the origin of the common field system, or of the English village community. It will be noticed that the researches upon which this book is based do not as a rule go further back than Leland's Itinerary in 1536 and following years. From such materials only hypotheses can be obtained, which require to be tested by all the evidence from earlier records. A hypothesis, however, has a certain value as a mental thread by which the facts can be connected and more clearly conceived.

Judging entirely from eighteenth and nineteenth century evidence, one is in the first place driven to accept most unhesitatingly the prevailing theory that the English common field system was based on co-aration. But one is tempted to very summarily dismiss the theory of Roman origin. Rather one is inclined to say that as long as a considerable portion of the villagers of the parish were accustomed to yoke their oxen or harness their horses to a common plough, the system was a living one, capable of growth and modification according to the ideas of the people who worked it. It became, as it were, fossilised and dead, incapable of other than decaying change, when each occupier cultivated his own set of strips of land by his own plough or his own spade. One is therefore inclined to suppose that the introduction of each new element in the population of a village—Saxon, Angle, Dane, and in a less degree, Norman—profoundly modified earlier customs, and that in each part of Britain a local type of village community resulted from the blending of different racial traditions.

This hypothesis is directly suggested by the evidence of recent survivals. The most familiar type of village community is characteristic of the Midlands; I have termed it the Mercian

type. It is most easily conceived as a compound of the pure Keltic system, known in the Highlands and Ireland as Run-rig or Rundale, and the North German system traditional among the Angles, in which the two elements in equal strength are very perfectly blended together. In the South of England we find a different type, here termed the Wessex type, in which the influence of Keltic tradition is more strongly seen. The village community in Norfolk and the adjoining part of Suffolk shows some remarkable special features, traces of which are found in adjoining counties, but which appear to be easily accounted for as the result of the later intrusion of Scandinavian traditions. Further, throughout the West of England, from Cumberland to Devon and Cornwall, we find evidence that the primitive type of village community approximated very closely to the Keltic Run-rig.

Enclosure of the common fields, meadows and pastures, of any particular village may have taken place in the following ways :—

(1) By Act of Parliament, viz., (a) by a private Act, (b) under the authority of the General Enclosure Acts of 1830 and 1836, (c) by the Enclosure Commissioners and their successors, the Board of Agriculture, under the General Enclosure Act of 1845 and its amending Acts.

(2) By common agreement of all the collective owners.

(3) By the purchase on the part of one owner of all conflicting rights.

(4) By special licence of the Tudor monarchs.

(5) By various forms of force and fraud.

Commonable waste may have been enclosed in any of the above ways, and also under the Statutes of Merton and Winchester (1235 and 1285), which give Lords of the Manor the right of enclosing commons provided proof is given that the tenants of the manor are left sufficient pasture.

Enquiry into the history of Enclosure naturally begins with an examination of the Enclosure Acts.

The first fact elicited by this examination is that there is a

perfect *legal* similarity between Acts for enclosing commonable waste, which may be termed *Acts for extending cultivation*, and Acts such as that for Henlow, for enclosing all the open and common arable and other lands of a parish or parishes, which may be termed *Acts for extinguishing village communities*. About one-third of the Enclosure Acts belong to the former variety, about two-thirds to the latter. As from the economic and social points of view, the two classes of Enclosure Acts are as widely different as they are legally similar, no statistical summaries of the Acts can have much value until the two classes are sorted out. To do this involved a separate examination of all the Acts accessible.

Appendix A contains a statistical summary of the Acts for enclosing commonable waste passed between 1727 and 1845; Appendix B contains a list of Acts for enclosing common arable fields with or without other commonable lands passed between 1727 and 1900.

CHAPTER II.

THE MERCIAN TYPE OF VILLAGE COMMUNITY.

LAXTON, AN OPEN FIELD PARISH.

PERHAPS the best surviving example of an open field parish is that of Laxton, or Lexington, in Nottinghamshire, about ten miles from Newark and Southwell. It lies remote from railways and high roads, and is only to be reached by bye roads. From whatever quarter one approaches the village, one enters the parish through a gate. The village is in the centre of the parish, and is surrounded by enclosed fields. Other enclosures are to be found on the most remote parts of the parish, in some cases representing, apparently, old woodland which has been converted into tillage or pasture; in other cases portions of the arable fields. But nearly half the area of the parish remains in the form of two great arable fields, and two smaller ones which are treated as two parts of the third field. The different holdings, whether small freeholds or farms rented from the Lord of the Manor, who owns nearly all the parish, consist, in part, of strips of land scattered all over these fields, in a manner which can best be understood by reference to the map. Within these arable fields cultivation is not carried on according to the discretion of the individual farmer, but by strict rules of great antiquity. In each of the fields a three year course is rigidly adhered to.

First year, wheat.

Second year, spring corn (*i.e.* barley, oats, peas, beans, vetches, tares, &c.).

Third year, fallow.

If, therefore, Laxton be visited early in June, the following description of the appearance of the parish will be found correct. The traveller passes through the boundary gate. He finds his road leads him through the "Spring corn" field, which lies

LAXTON

WEST FIELD AND PART OF MILL FIELD

-  Common Pasture
-  Farm N°1
-  " N°2

Approximate Scale $\frac{1}{5000}$

100 50 0 100 200 300 400 Yards



open on either side of the road. A phrase which is continually used by old farmers when attempting to describe common fields will probably occur to him in this field: "It is like allotments." But it is like an allotment field with many differences.

All the great field is divided up into oblong patches, each patch growing its own crop, but with no more division or boundary between one crop and the next than a mere furrow.

If, then, the traveller looks again at a strip of land growing, say, beans, he will find that this strip consists of one, two, or more ridges, locally termed "lands." A "land" in Laxton has a pretty uniform width of $5\frac{1}{2}$ yards, and a normal length of one furlong; but by the necessity of the case the length varies considerably. Owing to this variation in length the various strips of land which make up the different holdings in the common fields, when their area is expressed in acres, roods, or poles, seem to have no common measure.

Because the soil of Laxton is a heavy clay it is customary to plough each "land" every year in the same manner, beginning at the edges, and turning the sod towards the centre of the "land." Hence each "land" forms a long narrow ridge, heaped up in the middle, and the lie of the "lands" or ridges was at some unknown date so well contrived for the proper drainage of the land, that it is probable that if the whole of a field were let to a single farmer, he would still plough so as to maintain the old ridges.

The same ridges are to be found on the other two fields, one of which is a stretch of waving wheat; while the third, or fallow field, is being leisurely ploughed, a number of sheep getting a difficult living from the thistles and other weeds in the still unploughed portions, and on the "sicks," i.e. certain grassy parts of the field which are defined by boundary marks, and are never allowed to be ploughed. In one extreme corner of the parish is Laxton Heath, a somewhat swampy common covered with coarse grass. Here, too, sheep are grazed in common, according to a "stint" somewhat recently determined upon. Before the stint was agreed to, every commoner had the right of turning out as many sheep as he could feed in winter, the result

being that the common was overstocked, and the sheep nearly starved. The stint regulates the number of sheep each commoner may graze upon the common according to the number he can feed on his other land in the parish. It was not adopted without opposition on the part of those whose privileges it restricted.

This brings us to the question, Who are the commoners? There are two sorts of claim by which a man may be entitled to common rights, and to a voice in such deliberations as those by which a stint is agreed to. One is by a holding in the common open fields, the other is by the occupation of a "toft-head." A "toft" is not very easy to define. One may say that it either is, or represents, an ancient house or cottage in the village; but that immediately suggests the question, How ancient? It is well known in the village which cottages are "tofts" and which are not. Those which are, command a rent about £2 a year higher in consequence. It is to be noted that if the house or cottage which is the visible sign of "toft-head" be pulled down, and a new one erected on the same spot, the new house has the same rights attached to it. One is naturally led to the hypothesis that up to a certain date¹ all cottages erected

¹ The following extract from a sixteenth century writer throws some light upon this point:

"Another disorder of oppression
aduerte this wone wiche is mucche odyous,
A lord geauyn to private affection
lettinge the pooareman an olde rotten howse,
which hathe (to the same) profyttes commodious
its Cloase, and Common, with Lande in the feelde
but noate well heere howe the pooareman is peeelde.

"The howse shall hee haue and A gardeyne plott,
but stonde he must to the reperation:
Close, Comon or Londe fallithe none to his lott;
that beste might helpe to his sustentation.
the whoale Rente payethe hee for his habitation,
as though hee dyd thappertenauncis possesse
Such soare oppression neadethe speadye redresse."

"The Pleasaunt Poesye of Princelie Practise" (1548)

WILLIAM FORREST, Chapter III., 21 & 22
E.E.T.S. Extra Series, XXXII.

We have here the practice of divorcing the cottage from its common right described as a novelty. The Act of 31 Elizabeth, c. 7, by prohibiting the letting

in Laxton carried common rights, but that after that date no new common rights could be created. There are, therefore, two classes of commoners: the farmers who hold land in the common fields, and the labourers who occupy the privileged cottages. A farmer may possess a number of common rights in respect of (1) his farmhouse, if it be a "toft," (2) his arable holding, and (3) any toft cottages he may own or rent and sub-let to labourers, retaining their common rights. The labourer has but one common right. Each common right entitles the holder to one vote, and to one share in the division of the money revenues drawn from the commonable lands, besides the right of feeding an indefinite number of sheep on the fallow field, and the regulated number on the common. The money revenue that comes from the commonable fields is obtained as follows: The grass lands ("sicks") in the two common fields which are under crops cannot be grazed upon conveniently, because any animals would be liable to stray into the crops. They are, therefore, mown for hay, and the right to mow them is sold by auction to one of the commoners, and the price realised is divided. Recently this has worked out at about 14s. per common right. Each commoner also has the right of pasturing animals upon the two fields that are under crops, directly the harvest has been carried.

The exercise of this right, which appears to be most keenly valued, as it is found to persist in many parishes after all other traces of the common field system have died away, obviously opens the door to quarrels. It is not to be expected that all farmers should finish carrying their crops on the same day; and the position of the man who is behind all his neighbours, and so is standing between the commoners and their right of pasture, is not an enviable one. But a constitutional system of government exists for the purpose of dealing with these and other difficulties. A "Foreman of the Fields" and a "Field Jury" are elected: of cottages without 4 acres of land, in effect prohibited the letting of a cottage without a common right, as the 4 acres *would* not be the highly valued Close, and *could* not, unless the rights of other villagers were infringed, be waste or common pasture. Four acres in the common arable field was implied, and this of course carried a right of common.

the field jury settles all disputes between individuals, while the duties of the foreman include that of issuing notices to declare when the fields are open for pasturing; on which day all the gates, by which, as I have previously mentioned, the parish is entered, must be closed, while all the gates of the farmyards are thrown open, and a varied crowd of animals winds along the drifts and spreads over the fields.

It will be noticed that the commonable lands of Laxton include only arable fields and common pasture. The commonable meadows which the parish once had, have been partitioned and enclosed at a date beyond the recollection of the oldest inhabitant. The neighbouring parish of Eakring still has commonable meadows. In this respect Eakring is a more perfect example of the open field parish than Laxton, though its common arable fields have been much more encroached upon; and have, in fact, been reduced to scattered fragments, so that the rector was unable to tell me whether there were five, six, or more of them. The villagers, however, say simply "Three: the wheat field, the bean field, and the fallow field." The commonable meadows are, like the common fields, held in scattered strips intermingled; and are commonable after hay harvest. The rule in Eakring is that if one man only has any hay left on the meadows, the other commoners can turn in their cattle and relieve him of it; but if he can get a neighbour to leave but one haycock also, he is protected.

The constitution of Eakring differs somewhat from that of Laxton. There are regularly four toft meetings every year, presided over by the steward of the lord of the manor, at which all questions relating to the commonable lands are settled. Further, all toft holders have an equal right to feed an indefinite number of sheep on the fallow field, and the other fields when available, but the exercise of the right is regulated by a species of auction. The number of sheep that can be pastured with advantage is agreed upon, and since the total number of sheep which the assembled toft holders desire to put on is sure to exceed that number, a price to be charged per sheep is by degrees fixed by mutual bargaining, till the numbers of sheep

for which their owners are willing to pay is reduced to the number that the pasture can bear. The cottager and toft holder, therefore, who though not holding an acre of land in the parish, has yet enterprise enough to bid for the right of keeping a flock of sixty sheep on the common fields, is therefore heartily welcomed by that section of the toft holders who have no desire to bid against him, because he forces up the value of their rights.

A RECENT ENCLOSURE—CASTOR AND AILESWORTH.

Up till 1898 an even better example of an open-field parish could be seen in Northamptonshire. In that year was completed the enclosure of Castor and Ailesworth, two hamlets forming part of the parish of Castor, situated three miles from Peterborough on the road to Northampton. In 1892, when application was made to the Board of Agriculture, which now represents the Enclosure Commissioners of the General Enclosure Act of 1845, there were in the two hamlets, out of a total area of 4976 acres, 2,425 acres of common arable fields, 815 acres of common pastures and meadows, and 370 acres of commonable waste, and only about 1300 acres enclosed. In Laxton the commonable land is less than half the area of the parish. The greater amount of old enclosure in Laxton has had its effect on the distribution of the population. There are some, though very few, outlying farmhouses. In Castor and Ailesworth all the habitations and buildings, except a watermill and a railway station, are clustered together in the two hamlets, which form one continuous village. At present very nearly all the land of Laxton and Eakring is in the ownership of the respective lords of the two manors; in Castor and Ailesworth the Ecclesiastical Commissioners are the largest landowners; but nearly as much land is the property of Earl Fitzwilliam, and there are besides a number of small landowners. Before enclosure all these properties were intermixed all over the area of the two hamlets, the two chief properties coming very frequently in alternate strips.

Though the area of commonable land in Castor was so much greater than in Laxton, those customs of village communal life which we have described had retained much less vigour; and to the decay of the power of harmonious self-government the recent enclosure was mainly attributable. The customary method of cultivation in Castor and Ailesworth was a three-field system, but a different three-field system to that described above. The succession of crops was:—First year, wheat; second year, barley; third year, a “fallow crop,” or as locally pronounced, “follow crop.” Each year in the spring the farmers and toft-holders of Castor, and similarly of Ailesworth, would meet to decide the crop to be sown on the fallow field. One farmer, who held the position—though not the title—of “Foreman of the Fields,” kept a “stint book,” a list of all the villagers owning common rights, and the number of rights belonging to each. The number of votes that could be cast by each villager depended upon the number of his common rights. The fallow crop might be pulse or turnips or other roots or anything else that seemed advisable; but it was essential to the *farmers’* interests that they should agree upon some crop. For a tradition existed in the village that unless the farmers were agreed as to the crop to be sown on the fallow field, that field could be treated as though it really were fallow. It could be pastured on all the year by all the toft-holders, and any crop which any farmer might sow would be at the mercy of his neighbours’ cattle and sheep. I could not find that this had ever happened. On the other hand, the farmers being agreed about the crop, they could also determine the date when the fallow field should become commonable.¹ The wheat-field and barley-field became commonable after harvest; the meadows and pastures were commonable between August 12th and February 14th.

The reason why the medieval three-field system was retained in Laxton, but was altered in Castor to an improved three-field system, is to be found in the nature of the soil. That of Laxton

¹ This is good law. By 43 Geo. III. c. 81 these agreements could be made by “a three-fourths majority in number and value.” See Chapter IX.

is a heavy clay, growing wheat of noted quality; that of the Northamptonshire parish is lighter, in parts very shallow and stony. Another result of the difference of soil was a different system of ploughing. The Castor method was that technically known as "Gathering and Splitting," viz., alternately to plough each strip from the margin inwards, turning the sod inwards, and the reverse way, turning the sod outwards, so that the general level of the field was not broken into a series of ridges. In Castor, as in Laxton, no grassy "balk" divided one man's "land" from his neighbour's, the furrow only had to serve as boundary, and sometimes the boundary was bitterly disputed. Before the enclosure there was one spot in the common fields where two neighbours kept a plough each continually, and as fast as one ploughed certain furrows into his land, the other ploughed them back into his.

Another difficulty occasionally arose when high winds prevailed at harvest time. The great extent of the open fields, and the slightness of any opposition to the sweep of the wind, at such times allowed the corn to be blown from one man's land, and scattered over his neighbours'. Indeed it recently happened that one year when peas had been chosen as the fallow crop, that a storm carried the whole crop to the hedge bordering the field, and so mixed together in inextricable confusion the produce belonging to thirty or forty different farmers.

Another source of dispute was one that has been a prolific cause of trouble in common fields for centuries. Where the extremities of a series of adjoining "lands" abut on a land belonging to another series at a right angle, the land so abutted on is termed a "head-land," and the occupiers of the lands that abut on it have the right of turning their ploughs on the headland, and taking the plough from one strip to another along it. The occupier of the headland therefore has to defer ploughing it till all his neighbours have finished, and often chafes at the delay. Recently a farmer in the unenclosed parish of Elmstone Hardwick, near Cheltenham, in Gloucestershire, attempted to find a remedy for this inconvenience. He ploughed his headland at the time that suited his convenience, and then sued his neigh-

bours for trespass when they turned their ploughs in his land. Needless to say he lost more by his action than by the trespass.

In Castor quarrelsome farmers were wise enough to avoid the law courts. Instead, they wrote appealing against their neighbours to their respective landlords, but the landowners were unable to restore harmony. The death of a farmer who had won the highest respect of his neighbours, and who had continually used his great influence to allay ill-feeling and promote harmony, brought on a state of tension that gradually became unbearable; and the appointment by the Ecclesiastical Commissioners of a new agent, who could not understand and had no patience with the peculiarities of common-field farming, led to steps being taken for enclosure.

The first step necessary was to obtain the agreement of the great majority of the people interested. The agent in question, assisted energetically by the leading farmer in Ailesworth, succeeded in doing this without much difficulty. In 1892, application was made for an order to the Board of Agriculture, whose inspector reported warmly commending the project. The simple statement of the farmers with regard to their farms, *e.g.*, "I hold 175 acres in 192 separate parcels," would convince him that a change was necessary. The figures for holdings are not given by the enclosure award, but a summary of the facts with regard to some of the smaller properties gives the following:—

The glebe consisted of—

					A.	R.	P.
16	scattered strips of land in	Wood Field,	area		10	1	16
5	"	"	Nether Field,	"	3	1	12
7	"	"	Normangate Field,	"	4	0	2
33	"	"	Mill Field,	"	20	2	28
34	"	"	Thorn Field,	"	24	2	29
50	"	"	Milton Field,	"	37	0	37
18	"	"	four meadows,	"	10	1	20
2	Lammas closes,			"	7	2	24

making a total of 165 outlying parcels of land, scattered far and wide over a parish of five thousand acres in extent, and yet

THE MERCIAN TYPE OF VILLAGE COMMUNITY. 17

amounting, with some small closes near the village, only to 118 acres in area. Further—

		A.		R.		P.			
Proprietor	A	owned	17	3	19	in	32	parcels	
„	B	„	3	0	16	„	6	„	
„	C	„	80	1	5	„	164	„	
„	D	„	9	0	18	„	8	„	
„	E	„	2	0	2	„	5	„	
„	F	„	2	3	14	„	6	„	
„	G	„	1	2	10	„	5	„	
„	H	„	2	2	3	„	9	„	
„	J	„	2	1	18	„	7	„	
„	K	„	166	2	24	„	217	„	
„	L	„	13	3	37	„	30	„	

Parliamentary enclosure, however, is not to be obtained without conditions. That reckless disregard of the wider public interests both of the locality and of the nation at large in the land to be enclosed of which the administration of the General Enclosure Act from 1845 to 1874 has been accused, has been dispelled by the vigorous and ably-conducted agitation to which we owe the preservation of Epping Forest, Hampstead Heath, and many other priceless commons. In the enclosure of Castor and Ailesworth, in the first place, Ailesworth Heath, which occupies the highest and most remote corner of the parish, was excluded from the operation of the Enclosure Act. It is a wild little common which, beyond feeding a few sheep and furnishing a quarry, seems to be fit for nothing but picnics and blackberrying. Situated at the distance of about five miles from Peterborough, which again stands on the margin of the fen country, it will probably come to be valued by the townsmen for its unprofitable wildness.

Next, the parish boasts its antiquities, the remains of a part of the ancient Roman road from London to York, and certain blocks of stone, locally known as Robin Hood and Little John. The Enclosure Act provides for the preservation of these.

A bathing place in the River Nen, which bounds the parish

on the south, selected at the most convenient spot, and three recreation grounds of 6 acres each, and one of 14 acres, are handed over to the safe keeping of the parish councils of Castor and Ailesworth, besides four pieces of land, making 42 acres in all, for allotments and field gardens. The farmers mournfully point out that these 76 acres thus reserved for the common use and benefit of the villagers are some of the best land and the most conveniently situated. The recreation grounds in particular they scorn as foolishness. Possibly, however, because the village prides itself on its prowess in the football field, the indignation against this supposed fad of the central government is mild compared with that expressed by some of the thrifty people of Upton St. Leonards, near Gloucester, which was being enclosed at the same time. Here the recreation ground was dubbed by some the "ruination ground," enticing as it did the young lads from digging in their fathers' allotments to cricket and football, and so subverting the very foundation of good morals.

Subject to these deductions, the whole of the open commonable lands and many of the old enclosures, after being surveyed and valued, and after roads, where necessary, had been diverted or newly set out, were redistributed among the old proprietors so as to give each his proportional share, as far as possible in the most convenient manner. This was both a lengthy and a delicate task, but it was finally completed in 1898, six years after the matter first came before the Board of Agriculture. Each several proprietor was then required to fence his allotment in the manner prescribed by the commissioners who make the survey and award. The cost of the survey and allotment usually works out at about £1 per acre; the cost of fencing may be a great deal more. Though the Parliamentary expenses are now trifling, the total cost of abolishing the "system of mingle-mangle," as Carew called it in 1600, in any parish where it still exists, is not to be lightly faced in times of agricultural depression.

CHAPTER III.

THE WESSEX TYPE OF VILLAGE COMMUNITY.

TWO DORSET MANORS—STRATTON AND GRIMSTONE.

DORCHESTER is bounded on the south by Fordington Field. The parish of Fordington, up to the year 1875, was unenclosed; it lay almost entirely open, and was divided into about eighty copyholds, intermixed and intercommonable, the manor belonging to the Duchy of Cornwall. But in 1875 the Duchy authorities bought out the copyholders, and the old system disappeared.

About three or four miles from Dorchester, along the road to Maiden Newton and Yeovil, are the two adjoining villages of Stratton and Grimstone, forming together the Prebend of Stratton, belonging till recently to the See of Sarum, which have only been enclosed since 1900. The enclosure was effected without any Parliamentary sanction; it was brought about, I am told by the present lord of the two manors, by the refusal of the copyholders, who held by a tenure of lives, to "re-life." In consequence, all the copyholds, except a few cottages, have fallen into the hands of the lord of the manor; all Grimstone has been let to a single farmer, and Stratton divided into three or four farms.

Besides the very late survival of the common field system in these two manors, there are two other features which make them specially notable. In the first place they are, agriculturally, thoroughly characteristic of the Wessex type of open field village, the type that prevailed over Berkshire, Hampshire, Wiltshire and Dorset. In the second place, the manorial system of village government survived with equal vigour; the proceedings of the manorial courts and the customs of tillage and pasturage forming manifestly only two aspects of one and the

same organisation. It is fortunate that the court-rolls for the last two hundred years have been preserved, and that they are in the safe custody of the present lord of the manor.

On the south-west the lands of Stratton and Grimstone are bounded by a stream, the River Frome, flowing towards Dorchester, from which Stratton Mill has the right of taking a defined amount of water. Between the stream and the villages are the commonable meadows; on the north-east of the villages the arable fields, tapering somewhat, stretch up the hill slope to Stratton and Grimstone Downs. The whole arrangement is shown very clearly in the tithe commutation map, dated 1839. The two manor farms were separate and enclosed, and lay side by side along the boundary between the two manors, in each case comprising about one-third of the cultivated land. The remaining arable land in each manor formed, so far as fences were concerned, one open field, divided into three oblong strips, known respectively in Stratton as the East, Middle, and West Field; in Grimstone as Brewer's Ash Field, Rick Field, and Langford Field. The rotation of crops was: (1), wheat; (2), barley; (3), fallow. The lower part of the fallow field was sown with clover, and was known as the "hatching ground"—a term we find elsewhere in the forms "hitch-land" and "hook-land"—the upper part was a bare fallow. More recently an improved method of cultivation was adopted. The barley crop every third year was maintained, but after it was carried Italian rye grass was sown in the upper part of the barley field (instead of a bare fallow). This was fed off with sheep in the spring, and then put into turnips; the following year barley was sown again. The lower part, however, continued to be sown with clover in the fallow year, this was fed off with sheep, and wheat followed.

The arable fields consisted of "lands" or "lawns,"¹ each supposed to be 40 "yards" (*i.e.* poles) long, and one, two or four "yards" broad—hence supposed to be quarter acres, half acres, or acres. Half acres were the more common; but

¹ Mr. A. N. Palmer notes the terms "loons," "lawnds" and "lownts" in N. Wales and Cheshire ("The Town, Fields and Folk of Wrexham," p. 2).

whatever the area in theory it was somewhat less in actual fact.

The West Field in Stratton was somewhat smaller than the other two in consequence of the extreme portion—that next the down and farthest from the village—being enclosed. These enclosures in shape and arrangement exactly resemble the lands in the open field; they are about one acre each. They are called “The Doles.” Further there are a series of small square enclosures taken out of the down, called “The New Closes.” All the Doles and New Closes were in grass.

A remarkable fact is that all the “lands” were scrupulously separated from one another by meres or balks of turf, which, however, were not known by these names. Among the people they were, and are, known as “walls,” but in the court-rolls one finds the term “lanchetts,” which one connects with “lynches,” and “land-shares,” which seems to explain the term “launchers” which I have found in Devonshire. In the level parts of the fields the “walls” were mere strips of turf about a foot wide; but in the sloping parts they formed steep banks, sometimes several feet high, and the successive “lands” formed terraces one above the other.

All the cultivators, except the tenants of the two manor farms, were copyholders, holding for a tenancy of three lives, the widow of the holder having the right to continue the holding during the period of her widowhood. By the custom of the manor the lessee of the manor had at any time (even though his lease had but a day to run) the right to grant a copyholder two lives, *i.e.*, to accept a fine and substitute two new names for those of dead or dying persons on the “copy.”

The copyholds, when not “cotes” or simply cottages with common rights, were either “half-livings,” “livings,” or, in one or two cases, other fractions of a living. A half-living consisted of four or five nominal acres in each of the common fields, and common rights upon the meadow, common fields and common down, in Stratton, for one horse, two cows, and forty sheep. A whole living consisted of a share about twice as large in the field and meadow, and a common right for two horses, four

cows, and eighty sheep. But each copyhold, whether a whole or half-living, included one dole and one new close. There were three whole livings and twelve half-livings in Stratton, and five "cotes," i.e., cottages with one or two strips of land in the arable fields attached to them. In Grimstone there were four whole livings, six half-livings, one three-quarters living, and one whole and a-quarter living. In either manor, therefore, if we reckon two half-livings as equal to one whole, there were nine whole livings in all; those of Stratton being normally held by fifteen copyholders, those of Grimstone by twelve, though the number might happen in practice to be less. Thus at the time of the tithe commutation (1838) there was in each manor one copyholder who had two half-livings. In all formal documents a "living" is termed a "place," and a half-living a "half-place." The common rights attached to a living in Grimstone were slightly different from those in Stratton. They are further explained below.

Once a year, at about Christmas, the tenants of each manor met, the steward presiding; the elected officials submitted their accounts, and resigned their offices, and their successors were re-elected. The most important of these were two "viewers of the fields and tellers of the cattle," commonly known simply as the "viewers." There was also a "hayward," and two "chimney peepers" (described in the Court-rolls as "inspectors of chimnies"). The inspectors of chimneys do not appear in the rolls of the eighteenth century; instead are the more important officials the "constabul" (*sic*) and "tythingman," who ceased to be appointed presumably after the establishment of the county police and the commutation of the tithes.

The duty of the "chimney peepers" was, as their name implies, to see that chimneys were kept properly swept so as not to endanger a neighbour's thatched roof. The hayward was in charge of the pound; he was entitled to charge 4*d.* a head for all stray beasts impounded if they belonged to the manor, and 8*d.* a head for outsiders.

The "viewers" had more varied duties. In the first place they had to appoint one villager as "Lacy's Bridge man."

"Lacy's Bridge" is a structure of loose stones at a place where the stream, which for the most part bounds Stratton meadow, crosses it; and the duty of the bridge man is to keep it in sufficient repair to enable sheep to cross. The viewers used to appoint the cottagers in turn, going down one side of the road to the end of the village and up the other side.

Next the viewers provided the manor bull. They bought the bull, they charged a fee for his services, and made all necessary regulations. The breed favoured varied from year to year, and the viewers were never known to please everybody with their choice.


Then the viewers appointed the common shepherd, in whose charge were the sheep of the whole manor almost all through the year. And in general they had to enforce all the decisions of the court with regard to the times when sheep or cows should be allowed in the meadow, when the sheep should come into the "hatching ground," how and where horses should be tethered, and particularly to see that each tenant sowed his clover properly. And when the hay in the meadow was ripe, they marked out to each tenant the plots which fell to his share that year. It was usual to re-elect one of the viewers, so that though there was an annual election, each viewer held office for two years, being for the first year the junior viewer, for the second the senior.

There is much that is interesting in the management of the sheep flock. From April 6th to September 18th the sheep fed by day on the down, and were folded by night on the fallow field. The fold began at the top of the field, and gradually worked downwards, covering about half-an-acre every night, and so manuring the whole. There being no other water supply on the downs, all the tenants had to take turns to carry up water to fill the water-troughs, and the viewers saw that they did so. On September 18th the sheep came into the "hatching ground," on which, as we have seen, clover had been sown; and it is noticeable that this crop, sown individually by each copyholder on his own lands, was fed off by the common flock under the

supervision of the common shepherd. In winter the sheep belonging to each tenant had to be folded separately; and the doles and new closes were used for wintering the sheep. Some made it a practice to sell off their flock when feed became scanty, and to buy again the next spring; but the traditional custom was to keep the sheep till they were four or five years old, at which age they became fat, perhaps by superior cunning; meanwhile, of course, they had been yielding wool and manure. In later years, though every half living was entitled to forty sheep, by a common agreement the number was limited to twenty-five in spring, and later in the year to thirty-five, when the lambs reached the age at which they were counted as sheep in the calculation of common rights.


Perhaps the most curious feature in the local system of agriculture was the management of the common meadow. Sheep were allowed in it from March 1st to April 6th (it would only bear ten or eleven), then they had to come out and join the common flock, and the grass was let grow to hay. At hay time the viewers went out and by the help of some almost imperceptible ridges in the soil, and certain pegs driven into the river banks, they marked out to each tenant the plots on which he was allowed to cut and gather the hay. There were forty-seven of these little plots; twenty-seven of them were definite parts of particular copyholds, but nineteen were "changeable allotments," each of which belonged one year to one holding, the next year to another, according to certain rules; while the remaining allotment, a little three-cornered plot in the middle called "100 Acres," amounting perhaps to five perches in area, was divided among the holders of the adjacent "Long lands." On July 6th, the hay having been carried, the cows came in, and grazed in the meadow till November 23rd, and then the meadow was watered.

I have before me the map of the meadow, now somewhat tattered, being drawn upon a half sheet of thin foolscap, and a little notebook recording particulars of the different plots in the meadow, and in the case of the changeable allotments, who were entitled to them each year from 1882 to about 1905, which the



STRATTON MEADOW

Scale 2500



Channell's
9a. Or 17p

viewers used in partitioning the meadow. The map I reproduce. The notebook reads ¹ :—

STRATTON COMMON MEADOW.

Lear Croft Changeable Allotment next the Yard but one to Sparks.²

- 1882. Ozzard.
- 1883. Brett.
- 1884. Ozzard.
- 1885. Green.

Water Gates Changeable Allotment No. 1.

- 1883. M. Dean (Newberry).
- 1884. R. Davis.
- 1885. Dean.
- 1886. Davis.

Hole Rush—Changeable No. 1.

- 1883. Mr. R. Davis.
- 1884. Mr. Dean (Newberry).
- 1885. Mr. Davis.
- 1886. Mr. Dean.

Hole Rush No. 2.

- 1882. Ozzard.
- 1883. Brett.
- 1884. Ozzard.
- 1885. Green.

Hole Rush No. 3, or All Rush.

- 1883. R. Davis.
- 1884. Dean (Newberry's).
- 1885. Davis.
- 1886. Dean.

Hole Rush near the Parish, No. 5.

- 1883. Mr. Dean (Newberry).
- 1884. R. Davis.
- 1885. Dean.
- 1886. Davis.

¹ I give only four years, or a complete cycle, which is usually one of two years, but sometimes of four, and in two cases of eight years.

² " Parks " in map.

ENGLISH PEASANTRY.

Hole Rush No. 4.

- 1883. Mr. Kellaway.
- 1884. Brown.
- 1885. Kellaway.
- 1886. Brown.

Hole Rush No 6, near the Parish.

- 1883. Brown.
- 1884. Kellaway.
- 1885. Brown.
- 1886. Kellaway.

Long Lands No. 2.

- 1883. Mr. Dean (Dunn).
- 1884. Brett.
- 1885. Brett.
- 1886. Dean.

Long Lands No. 3.

- 1883. Ozzard.
- 1884. Mrs. Dunn.
- 1885. Mr. Dean.
- 1886. Mrs. Dunn.

Long Lands No. 1.

- 1883. Mr. Tilley.
- 1884. Ozzard.
- 1885. Tilley.
- 1886. Ozzard.

Long Lands No. 5.

- 1883. Ozzard.
- 1884. Tilley.
- 1885. Ozzard.
- 1886. Tilley.

Long Lands No. 4.

- 1883. Mrs. Dunn.
- 1884. Mr. Dean (Newberry's).
- 1885. Mrs. Dunn.
- 1886. Dean.

The first part of the Three Patches in the Great Horse Shoe is the "Mill Bars Patch," containing about 26 perches.

THE WESSEX TYPE OF VILLAGE COMMUNITY. 27

The second part is the narrow strip next to Mr. Channen's—
17 perches.

The third part is the lower patch adjoining Mr. Channen's—
1 rood 10 perches.

Total, 2 roods 13 perches.

CHANGEABLE ALLOTMENTS IN THE GREAT HORSE SHOE.

The Three Patches are one part.

Three Patches.

- 1883. Ozzard.
- 1884. Mr. Dean (Dunn).
- 1885. Mr. Tilley.
- 1886. Mill.
- 1887. Tilley.
- 1888. Mill.
- 1889. Ozzard.
- 1890. Brett.

The Square Patch is joining the patch by the Mill Bars, may be called the fourth part of the "Great Horse Shoe," it contains about 2 roods and 4 perches.

- 1883. Mr. Tilley.
- 1884. Mill.
- 1885. Ozzard.
- 1886. Brett.
- 1887. Ozzard.
- 1888. Green.
- 1889. Tilley.
- 1890. Mill.

The Stake Weir is one part of the "Little Horse Shoe," about 1 rood and 9 perches changeable.

- 1882. Ozzard.
- 1883. Dean (Newberry's).
- 1884. Tilley.
- 1885. Mill.

The "Little Horse Shoe" changeable. The narrow strip and the strip round the corner next to Stake Weir patch is one part.

- 1883. Mill.
- 1884. Ozzard.
- 1885. Dean.
- 1886. Tilley.

Narrow strip, 16 perches.

Patch round the corner, 1 rood 22 perches.

The small strip of land called "Hundred Acres" is a part of the Long Lands and is divided amongst the half-acres.

The nine Cantons under the Parks Hedge are about 10 perches each.

About the agricultural merits of the whole system of managing common fields, down and meadow, there is naturally a difference of opinion. An old labourer says that before the old customs began to decay "they made the most of everything," that the crops are not so good now, and "you can't get the butter or the cheese" which used to be produced. The butter nowadays goes rancid immediately, and the cheese has no taste. On the other hand, the enterprising young farmer who now holds the manor farm at Stratton, who has himself been a "viewer," says: "They always had two crops," *i.e.*, the corn crops had to struggle with couch grass, which partly for want of sufficient ploughing, and partly because it had a secure foothold in the "walls," was never properly got rid of.

That the life of the old system was gradually dying out before it was ended by the extinction of the copyholds appears from two circumstances: the old habit of mutual help in ploughing, one tenant lending his horse to another, had died out; and the viewers had difficulty in getting their expenses refunded. The wonder is that its vitality was so persistent.

The history of the manors can be pretty fully traced by means of the Court rolls, from 1649, when a Parliamentary survey was held, to the present day. In 1649 Stratton had one copyhold tenant holding a place and a-half, four holding one place each, and ten holding half a place each, making $10\frac{1}{2}$ "places" or

“livings” altogether. There were, besides, 12 copyholders who each held a “customary cottage with thappurtenances.” During the next two hundred years (from 1649 to 1838) the number of “livings” diminished from $10\frac{1}{2}$ to 9; the actual number of holders of livings or half-livings diminished only from 15 to 14; but the twelve “customary cottages with thappurtenances,” which included one or two acres of arable land and corresponding common rights, diminished to five “cotes.” The other cottagers, however, retained the right of cutting as much furze on certain “sleights” on the down, at any one time, as they could carry home on their head and shoulders; and the total number of cottagers was just two less in 1838 than in 1649.

The Court rolls contain, besides declarations of rights of the manor to water from the stream, and to the allegiance of certain residents outside, and a record of the changes in the tenantry, the names of the officers elected, and regulations agreed upon for the management of the land. Thus, there is usually some regulation as to the length of the rope by which a horse may be tethered in the common fields; mares are continually being prohibited from being kept in common or common field; pigs must not be allowed to stray; cow dung must not be removed from the meadow, nor certain thorny bushes in the meadow be cut, nor may ducks or geese be fed in it. The penalty for each of these offences is a fine of 5s. or 10s. The neglect to carry water up to the down for the sheep is another punishable offence. In 1748 it was found that the sheep pond needed to be mended; the viewers accordingly had to see to its repair, and penalties were agreed upon for refusing to pay the proper share of the cost.

Previous to 1765 the dates for, *e.g.*, turning cows into the meadow or sheep into the “hatching ground” varied from year to year; but the settlement then arrived at was maintained for a succession of years. The jury

“PRESENT that the Common Meadow be broke with horses on November 22nd,¹ that it be laid up on January 5th and

¹ At this time the Court met in October.

continue unfed till February 5th, then be broke and fed with sheep.

“ That the Hatching Ground be laid up on January 5th, and not be fed again till September 19th.

“ That the Cow leaze must not be fed with sheep in time of sheep shearing, nor with horses or mares at winnowing time.”

The year 1789 was a comparatively important date in the agricultural history of Stratton during the eighteenth century. At the Court held on October 9th, it was agreed that “ the tenants shall meet in the West Field on the 14th inst. between 9 and 10 in the morning, to bound out the several lands, and afterwards each shall leave a lanchett of a furrow between his and the adjoining land under penalty of a fine of 20s. And no tenant shall turn his plough on his neighbour’s land after the 21st of November.” It would appear that the scrupulous observance of the “ walls ” dividing one man’s land from another, which was such an exceptional feature of Stratton and Grimstone Common Fields, dates from this meeting.

Fordington parish, until the extinction of the copyholds, had many features which compare curiously with those of Stratton and Grimstone. It is very much larger ; for whereas Stratton and Grimstone together have an area of only about 1200 acres, the area of Fordington is 2749 acres, of which, up to 1876, nearly 1800 acres was common field and common meadow, and 618 acres commons adjoining the common field. Fordington is also peculiarly divided into three portions : the arable field and common pastures lying immediately south of Dorchester, the meadows forming a detached area by the side of the River Frome, and the village itself a third detached area.

The copyholds in Fordington were known, some as “ whole-places,” “ half-places,” as in Stratton and Grimstone, but others as “ farthing holds.” One cannot help asking what were the original meanings of these terms, and how they are related to the “ virgates ” of Domesday, and to the “ yardlands ” of the Midlands, and the “ broad ” and “ narrow oxgangs ” of Yorkshire and Lincolnshire. Concerning these terms it appears to be established that a “ yardland ” or “ virgate ” was

originally one quarter of a "carucate," or ploughland, *i.e.*, the amount of arable land (about 120 acres in average soil) which a plough team of eight oxen could plough in a year, together with its due share of meadow and common pasture. A broad oxgang was about 24 acres of arable land, and therefore apparently the northern representative of a yardland or virgate; and a narrow oxgang was about 12 acres of arable, or half a broad oxgang.

In Stratton, as we have seen, every "whole place" or "whole living" had common rights for two horses, four cows, and eighty sheep; every half-place common rights for one horse, two cows, and forty sheep. The areas of land attached to the three whole places were respectively 18 a. 3 r. 35 p., 19 a. 2 r. 3 p., 22 a. 0 r. 11 p., averaging just 20 acres; the half-places varied from 9 a. 0 r. 19 p. to 13 a. 2 r. 25 p., the smaller half-places having an advantage in quality of soil, and the average being almost exactly 11 acres.

In Grimstone the common rights as well as the area of land belonging to particular whole or half-places varied somewhat. The half-places consisted respectively of—

				Area.			Common Rights.		
				A.	R.	P.	Horses.	Cows.	Sheep.
A	...	...	...	11	0	28	1	2	56
B	...	...	...	12	0	7	1	3	48
C	...	...	...	16	3	7	1	3	60
D	...	...	...	12	3	1	1	2	44
E (two half-places)	...	...	...	19	2	27	2	5	96
				(average 12 acres)					
The Whole Places.									
A	...	...	...	21	1	25	2	5	104
B	...	...	...	21	1	38	2	5	96
C	...	...	...	21	0	19	2	4	96
D	...	...	...	20	2	32	2	5	96

The "whole and a-quarter place" had 26 a. 0 r. 13 p. of land and rights for three horses, five cows, and 120 sheep, and the "three-quarter place" 16 a. 1 r. 2 p., with rights for

one horse, five cows, and eighty sheep. If these be added together and divided by two we arrive at two whole places of 21 a. 0 r. 27 p., with the common rights for two horses, five cows, and 100 sheep. This may be taken as the typical whole place, and the half-place is just a little more than the mathematical half of a whole place. The fact that the common rights attached to a given unit were more extensive in Grimstone than in Stratton is the natural consequence of the fact that Grimstone had 244 acres of down and 35 acres of cow-common, Stratton only 190 acres of down and 26 acres of cow-common.

But when we compare these with the whole places, half-places, and farthing holds of Fordington, we find rather a puzzling discrepancy. In the latter parish the fourteen whole places each had, in 1841, the date of the Tithe Commutation, rights for four horses, three cows, and 120 sheep, except one, which had no common rights at all, but, apparently by compensation, had 66 acres of arable land, eleven more than any of the others. The smallest of the others had 42 a. 3 r., the largest 55 a. 0 r. 22 p., the average being about 48 acres; in other words, in Fordington a whole place had more than twice as much arable land as in Stratton or Grimstone, and carried a common right for four horses instead of for two.

Each of the twenty-one half-places in Fordington had common rights for three horses, two cows, and sixty-six sheep—which more closely approximates to three-quarters than to a half of the rights of a whole place. The area of land attached to a half-place is, however, on the average somewhat less than half that attached to a whole place, the largest having 25 a. 1 r. 6 p., the smallest 15 a. 1 r. 36 p., the average being just under 21 acres. It happens curiously that the largest “farthing holds” had more land than the smallest half-places, as their areas range from 11 a. 1 r. 7 p. to 17 a. 3 r. 35 p. There were nineteen of them, and their average area was $14\frac{1}{2}$ acres. Each had a common right for two horses, two cows, and forty sheep.

The following tentative hypothesis may be suggested as an explanation. It is based on the presumption that the *names*

represent a more ancient set of circumstances than the actual facts recorded in the tithe apportionment.

I think it, on the whole, more probable that these units of holdings are based upon ploughing by horses than upon ploughing by oxen. In other words, I think that the system of co-aration persisted unimpaired in these particular villages after horses had superseded oxen for ploughing purposes, which might have happened at a very early date. This seems plainly indicated by the fact that during the 190 years from 1649 to 1839 the majority of the copyholders in Stratton and Grimstone had only one horse apiece, therefore they must have combined to work even a two-horse plough; and, as I have said above, the practice of helping one another with horses for ploughing only died out in very recent years.

I think further, that in all three manors, a "whole place" or "whole living" meant the land cultivated by one plough, but that in Stratton and Grimstone the plough was a light and shallow one drawn by two horses only, and in Fordington a heavier plough drawn by four horses. The soil in Stratton and Grimstone is very thin and stony, and would not bear deep ploughing; that of Fordington is much deeper and heavier. Further, Stratton and Grimstone fields lie on the steep slopes descending from the downs; Fordington field is gently undulating. Therefore, a four-horse plough in Fordington would plough more than twice as much land as a two-horse plough in the other villages. A whole place then in Fordington naturally would have common rights for four horses; in Stratton and Grimstone for two horses only.

A half-place in Stratton and Grimstone was, therefore, the holding allotted to the tenant who had one horse, and it carried a common right for one horse. Though a half-place in Fordington carried in 1841 a common right for three horses, I am inclined to believe that it originally was the holding of a tenant who had two horses, *i.e.*, half a plough team, and originally had a common right for two horses only; and, similarly, though a farthing hold in 1841 had a common right for two horses, I am inclined to think it originally was the share of the man who had

one horse only, and only carried a common right for one horse. That is to say, I think the *names* here a better guide than the nineteenth century common rights. If one were to adopt the opposite view on this point, one would infer that a "half-place" was a misnomer for a "three-quarter place," and was the allotment of the man who had three horses, and that a "farthing hold" should properly be called a half-place. But on this assumption it would be hard to explain the fact that the arable land attached to a half-place is, on the average, a little less than half that attached to a whole place, and that attached to a farthing hold only a little more than one quarter.

It seems quite probable that when in the course of the gradual improvement of horses and ploughs in Fordington, the stage was reached at which three horses were sufficient for a plough, the holders of half-places already possessing two horses each endeavoured to emancipate themselves from the necessity of joint-ploughing, by obtaining an additional horse; and that when they had generally succeeded in this they obtained the right of pasturing three horses each on the commons and common-field; and when a two-horse plough had come into general use, the holders of farthing holds would naturally take similar steps, and so acquire common rights for two horses each.

There is one other noteworthy fact with regard to Fordington revealed by the Tithe Apportionment. Certain lands scattered over the fields of a total area of 4 a. 2 r. 20 p. were the property of the parish constable for the time being; the churchwardens similarly held 1 r. 7 p., the parish hayward 1 a. 3 r. 18 p., and the parish reeve 3 a. 0 r. 17 p. These ancient village offices were therefore in Fordington not entirely unremunerated.¹

In its main features the common-field system of Stratton and Grimstone appears to be typical of that prevailing before

¹ The Boldon Book shows that in the Bishopric of Durham in the twelfth century, the pounder, carpenter and smith generally occupied holdings of about 12 acres in virtue of their callings, to remunerate their services to the manor and to the common ploughs of the manor.

enclosure in the counties of Dorset, Wilts, Hants, Berks, Oxfordshire, and Gloucestershire.

The report of the Select Committee on Commons Enclosure gives a map of a "rotation meadow," in which each strip was held in rotation by different occupiers, in Shilton, Berkshire; and one of a "lot meadow," in which the rotation was not by rule, but by lot, in Bestmoor, Oxfordshire.

CHAPTER IV.

EXTENT OF EXISTING COMMON FIELDS.

A "RETURN of the Acreage of Waste Lands subject to Rights of Common and of Common Field Lands in each Parish of England and Wales, in which the Tithes have been commuted under the Tithe Commutation Acts, so far as the same can be ascertained from the Maps, Agreements, Awards, and Apportionments relating to the Commutation of Tithes in the custody of the Tithe Commissioners for England and Wales, deducting any lands inclosed under the General Enclosure Acts since the Commutation; also the estimated Total Acreage of such lands in the remaining Parishes of each county," dated 27th November, 1873, ordered by the House of Commons to be printed, April 13th, 1874, gives us the following results:—

County.	Number of Parishes stated to have Com- mon Fields.	Area of such Common Fields.	Estimated Area of other Common Fields in the County.
ENGLAND.			
Bedford	9	7,056	12,925
Berkshire... ..	21	13,227	2,705
Buckingham	16	2,315	2,365
Cambridge	9	4,798	2,678
Cheshire	16	599	116
Cornwall	16	895	6
Cumberland	22	1,177	868
Derby	11	1,119	638
Devon	15	1,125	32
Dorset	29	6,793	810
Durham	6	1,936	171
Essex	48	4,614	295
Gloucester	33	4,327	2,986

EXTENT OF EXISTING COMMON FIELDS. 37

County.	Number of Parishes stated to have Com- mon Fields.	Area of such Common Fields.	Estimated Area of other Common Fields in the County.
<i>ENGLAND—contd.</i>			
Hereford	32	2,309	189
Hertford	39	9,311	1,785
Huntingdon	4	1,336	2,336
Kent	21	4,183	126
Lancashire	22	2,125	1,173
Leicester	3	42	93
Lincoln	24	6,258	10,823
Middlesex	6	697	870
Monmouth	2	64	3
Norfolk	52	3,560	394
Northampton	3	4,103	13,446
Northumberland	1	44	7
Nottingham	14	4,282	6,617
Oxford	12	4,120	4,839
Rutland	6	3,930	5,726
Shropshire	12	485	40
Somerset	77	7,794	728
Southampton	25	5,725	663
Stafford	26	1,138	402
Suffolk	34	2,395	184
Surrey	19	3,732	277
Sussex	22	2,969	122
Warwick	5	1,232	1,208
Westmoreland	8	425	359
Wiltshire	44	18,167	4,503
Worcester	20	3,092	1,161
York, City and			
Ainsty	4	187	372
York, East Riding	14	4,046	7,359
York, North Riding	7	547	240
York, West Riding	44	6,488	4,361
<i>WALES.</i>			
Anglesey	2	414	33
Brecon	2	1,549	5
Cardigan	4	372	0
Carmarthen	8	489	38
Carnarvon	1	100	7
Denbigh	4	278	18

County.	Number of Parishes stated to have Com- mon Fields.	Area of such Common Fields.	Estimated Area of other Common Fields in the County.
<i>WALES—contd.</i>			
Flint	5	297	4
Glamorgan	10	783	40
Merioneth	2	110	8
Montgomery	3	1,885	24
Pembroke	8	642	18
Radnor	3	6,167	158

TOTALS.

	Number of Parishes stated to have Com- mon Fields.	Area of such Common Fields.	Estimated Area of other Common Fields.	
England	853	153,867	97,001	250,868
Wales	52	13,086	353	13,439
	905	166,953	97,354	264,307

We have therefore the assurance of the Copyhold, Inclosure and Tithe Commission that in the year 1873 common fields existed in 905 parishes of England and Wales, of a total area of 166,953 acres, and that there was reasonable ground for inferring the existence of 97,354 acres of common field land, scattered presumably over some four or five hundred more parishes ; in other words, that about one parish in every ten in England and Wales presented an example of the medieval system of land holding and cultivation similar, though as a rule on a smaller scale, to the survivals described above.

The statement is amazing, and would be received with incredulity by anyone familiar with the rural districts of any

county of England, so far as it relates to that county. The Commission invites our suspicion of its statistics. The main purpose of the return was to give the acreage of surviving commons; these are estimated at 2,368,465 acres. As late as 1871, however, the Commission had declared, on the basis of an estimate made in 1843, that 8,000,000 acres of commons still existed, and 1,000,000 acres of common field or meadow. A little scrutiny of some details confirms one's suspicions.

Thus, to take a single county, Kent has from the early days of the enclosure controversy been famous as a well enclosed county. The author of the "Discourse of the Common weal of this Realm of England" mentions "those countries that be most inclosed, as essex, kent, devenshire" (1549). Skipping two and a-half centuries, we find the reporter of the Board of Agriculture in 1793 declaring that such a thing as a common field did not exist in Kent.¹ We are confirmed in our acceptance of this statement by finding that there have been no enclosures in Kent of common fields by Act of Parliament, either before 1793 or since. Yet the return gives Kent twenty-one parishes having common fields of an ascertained area of about 4183 acres. It therefore is necessary to criticise the methods by which the figures in the return were arrived at.

They are based on the tithe maps, the Commissioners remarking that "the common field lands are generally distinguishable by the particular manner in which they are marked on the Tithe maps, and their area has been estimated from those maps." The Tithe Commission was appointed in 1836 (6 & 7 Will. IV. c. 71), and the tithe maps and apportionments were made mostly before 1850; we are told "the total area embraced by the Tithe Documents is 28,195,903 acres. The total area of the remaining parishes is 8,961,270 acres."

In order, therefore, for the Commission to have obtained a correct result, it was necessary—

(a) that the common field lands should have been *rightly* distinguished from other lands;

¹ Boys' "Kent," 2nd edition, 8vo. (1786), p. 53.

(b) that their area should have been *rightly* estimated;

(c) that due allowance should have been made for enclosures between the date of the tithe apportionment and the date of the return;

(d) that the area of common field in the parishes for which there are no tithe maps should have been estimated on correct principles.

Not one of these conditions was satisfied.

(d) Taking these in reverse order, it is assumed in calculating the area of common fields in parishes that have no tithe maps, that they have the same ratio of common field to other land as those which have tithe maps. This principle is entirely wrong for two reasons: (1) because Private Enclosure Acts usually arranged for tithe commutation, so that parishes enclosed by such Acts before 1830 are ordinarily among those without tithe maps—and equally among those without common fields; and (2) the existence of unenclosed common fields would be a reason for demanding a commutation of tithe. The importance of this may be shown by taking Bedfordshire as a test case. For sixty-eight Bedfordshire parishes there are no tithe maps, and the Commission estimates that these sixty-eight parishes have 12,925 acres of common fields. But sixty-six out of these sixty-eight parishes were enclosed by Private Acts, leaving two parishes only, of a combined area of 3578 acres, in which a survival of common field might reasonably be deemed possible, though even in these extremely improbable. Instead of 12,925 acres of common field for this part of the county, the only reasonable estimate would be 0.

Similar statements might be made with regard to any other county which was mainly enclosed by Act of Parliament, as Northampton, to which 13,446 acres of common field are attributed to the non-tithe map parishes; Lincoln, to which 10,823 acres are similarly attributed; Berkshire, with 2705 acres; Buckingham, with 2365 acres; Cambridge with 2678 acres; Huntingdon, with 2336 acres; Nottingham, with 6617 acres; Oxford, with 4839 acres; Rutland, with 5726 acres, and the East Riding of Yorkshire, with 7359 acres. For this cause

alone by far the greater part of the 97,354 acres added on to the total estimated from tithe maps must be rejected, and of course any error of over-statement that we find with regard to parishes which have tithe maps will still further reduce the remainder.

(c) Due allowance has not been made for enclosure between the date of the tithe apportionment and the date of the return. It is of course very difficult to say how this could have been done without an elaborate and expensive local enquiry, so far as relates to enclosure without Parliamentary authority. As a matter of fact, no allowance at all has been made for this sort of enclosure. This is justifiable ; but at least a general statement should have been made to the effect that a very large deduction had to be made on this account in order to obtain a correct idea of the position. Further, great carelessness was shown even in allowing for Parliamentary enclosures subsequent to the tithe apportionment. Thus, to take one glaring instance, 1500 acres of common field are credited to Beddington and Wallington, near Croydon, in Surrey. These common fields were enclosed by an Act dated 1850, and the award, dated 1853, was at the time of the return deposited with the Copyhold, Inclosure, and Tithe Commission.

(a) and (b) But it is in distinguishing the common fields and in estimating their area from the tithe maps that the worst mistakes have been made. The Commission says that "the common fields are generally distinguishable by the particular manner in which they are marked on the tithe maps." From a comparison of a good many tithe maps with the figures given in the return, I infer that those to whom the duty of distinguishing the common fields was entrusted, were told that areas divided into sub-divisions on the maps by means of dotted lines were common fields. These dotted lines indicate a division of ownership marked by some slight boundary and not by a hedge. They might indicate allotments, for example, or a number of other local circumstances, besides common fields. The statements that 4183 acres of common field were to be found in Kent, and 13,439 acres in Wales, being specially in direct contradiction of all other evidence that I had collected, I tested these by two

instances. In Kent 1400 acres were assigned to the parish of Northbourne. By a close examination of the tithe map I could find nothing indicating any common field at all; the only excuse for the statement was a few dotted lines, which by a reference to the Award were proved to indicate only that some fields were inadequately hedged. For Wales, I got out the map and award for Llanerlyl, in Montgomery, credited with 1675 acres of common field. Here there was something to be found on the map looking exactly like common field, but the Award showed that these dotted strips of land were "turbaries."

We have seen that the open field parish in its perfection, as Castor and Ailesworth before enclosure, possessed common arable fields, common meadows, common pasture, and frequently commonable waste, like Ailesworth Heath. Where the parish as a whole becomes enclosed without an Act of Parliament, particularly if the enclosure is gradual, the waste frequently remains common. Thus we have the numerous commons of Kent, Surrey, and other counties. Less frequently, but still in a considerable number of cases, the common meadows remain open commonable and unenclosed. Port Meadow at Oxford is a familiar instance. These common meadows are included in the return under consideration among the common fields. Thus, for instance, the surprise with which one receives the information that Tottenham, in 1873, had 300 acres of common fields, disappears when it is perceived that the marshes along the River Lea are meant.

It will also be noticed later on that in parishes where the common field system has disappeared for generations, there are frequently still remaining in the midst of enclosed fields strips of land of different ownership from the rest of the field, but let to the same farmer, and without any visible demarcation. Such fields in Wales and the north-west of England are called "quilleted fields." The tithe map records, with its dotted lines, the area and position of the "quilllets." Such fields are included under "common fields" in this return.

In at least the great majority of cases where the supposed common fields are small, it is probable that nothing more notable

than quilled fields existed at the time the tithe map was made; and even this survival would, in most cases, have disappeared since. Out of the 905 alleged cases of common fields, in 670 cases the areas given are under 100 acres.

In fine, this return of commons and common fields, which gives such a fair promise of numerous surviving common fields, in reality gives little assistance, because there is but the remotest probability in any particular case that those common fields exist. The probability is sufficient in some cases to encourage one to make local enquiries, but these enquiries nearly always end in disappointment. The following cases in which common arable fields theoretically survive, are chiefly interesting as illustrating the phenomena of the decay of the common field system in villages where it has not died a sudden death through enclosure. I omit the case of Hitchin, made famous by Mr. F. Seebohm.

CLOTHALL (HERTS).

Clothall is a parish lying on the north slope of the chalk hills of Hertfordshire, just off the Great North Road, which passes through the adjoining parish of Baldock. Approaching it from the south, one gradually ascends the long slope from Hertford, and suddenly at the summit has before one a far-stretching view over the flat country of Bedfordshire and adjoining counties. The road descends steeply and passes through the Clothall common fields. At the time of my visit the harvest (of barley) was being gathered in; the arrangement of the field was clearly visible. The long, narrow strips of stubble, never quite straight, and never quite of uniform width, were divided by "balks" of grass, grown tall and gone to seed. Each balk was reduced to as narrow dimensions as it could be, without endangering its continued existence, for the sake of separating one strip from another. A view of this field is shown in Mr. Seebohm's "English Village Community."

But there is in Clothall the husk only, and no surviving kernel of the English village community. The whole of the field, estimated at about 600 acres, is let to a single farmer,

who cultivates it on modern principles, but who is bound to preserve the balks. There are but three owners of land in the field. Fifty-six acres are glebe, the remainder belongs in alternate strips to the lord of the manor (the Marquis of Salisbury) and to a gentleman to whom possession passed by marriage, from a family which had been engaged in brewing. The land is famous for barley, and the owner of a local brewery in the early or middle part of the nineteenth century gradually bought up nearly all the land in the common field that did not belong to the lord of the manor. Application was made in 1885 to the Board of Agriculture for enclosure, the manorial authorities and the vicar both desiring it, but the other owner objected.

It is interesting to find that the villagers still hold to the tradition that they have rights of common upon the balks, a tradition which is probably well founded. But they dare not attempt to exercise those rights. An enclosure here, accompanied by the provision of ground for allotments and recreation, would be a boon for the villagers; and it would probably pay the landowners to get rid of those balks, which are as great a nuisance agriculturally as they are interesting from an antiquarian point of view.

The counties of Hertford and Bedford have been, in recent years, particularly rich in survivals of common field, for the enclosure of Totternhoe (p. 65) was only completed in 1891; Yelden had a common field of about 600 acres up till about the year 1881, when the chief proprietor, by buying out or compensating all the other proprietors or owners of common rights, obtained exclusive ownership of the unenclosed land; and at Studham and Renhold similar voluntary enclosures were carried out under the pressure of the chief landowners within the memory of old inhabitants. Fragments of commonable pasture in three different parts of Renhold parish, and a common of about 60 acres in Studham, remain as memorials.

BYGRAVE AND WALLINGTON.

Beneath the long sloping hillside of Clothall lies the little town of Baldock, adjoining Letchworth and the "Garden City";

and on the other side of Baldock is the parish of Bygrave ; which is, like Clothall, still unenclosed, and for the same reason ; the Marquis of Salisbury being here again the lord of the manor, and the other Clothall proprietor the next largest landowner. But in Bygrave the farms, as well as the properties, are very much intermixed. Here and there there are grassy balks between adjacent properties ; and in places the growth of bushes on these has almost made them into hedges, but as a rule there is no boundary between strips belonging to different holdings and different properties. A road through the open fields at one point cuts off the end of a strip of land belonging to Lord Salisbury from the rest of that strip ; it forms a triangular plot too small to repay the trouble of bringing the plough across the road to plough it ; and the men who hold the adjoining land revere the rights of property too much to touch it ; it therefore remains a refuge for all manner of weeds.

As in Clothall, no common rights are exercised over the common fields of Bygrave by the poor of the parish, nor could I hear of any tradition of rights belonging to the poor or to cottagers. But the different occupiers of land in the common fields have, and exercise, the right of shackle, *i.e.*, of grazing cattle after harvest, over one another's holdings. And the lord of the manor has a special right of "sheep-walk" over the whole, for a month, from the first week in May and October. This right is let with one of the farms. It is not actually exercised, because the other occupiers of lands in the open field buy exemption.

The hamlet of Luffenhall, also near Clothall, has "shack lands" held under similar conditions.

The next parish to Clothall on the east, Wallington, is also unenclosed. It has a small common on which cottagers have the right to keep a cow and a calf, but so far as the rest of the parish is concerned, the only surviving feature of the externals of the common field system is the wide, breezy stretch of open land, under wheat, roots and grass ; and of the spirit of the "village community" there is nothing. There are but two farms ; the wages paid are only 10s. to 12s. per week. Such

wages, so near London, naturally fail to keep the labourers in the village; and the population is now (1903) less than 100, though the church has seats for 260. As the men go, more and more land is laid down in grass, and machinery is more and more used; the absence of hedges of course facilitates the use of certain kinds of agricultural machinery. The unenclosed parish of Wallington, in fact, represents in an extreme degree the triumph of all those tendencies against which the opponents of enclosure waged war—great farms, absolute dependence of the labourer, low wages, rural depopulation.

SUTTON (NORTHAMPTONSHIRE).

The parish of Castor, or Caister, includes, besides the hamlets of Castor and Ailesworth, the enclosure of which has been described, the townships of Sutton and Upton. Sutton had not at the time of the enclosure of Castor and Ailesworth been legally enclosed, and the parish is described from the tithe map as consisting of 450 acres of common field and 150 acres of common, out of a total of 888 acres. The vicar, who had bought nearly all the land in the parish, and also the manorial rights, in 1899 applied for an Act of Enclosure, which he obtained in 1901. There were in Sutton certain lands belonging to the township, intermixed with those in private ownership. The rents of these were paid with the poor rates. Up till 1880 the two farmers who between them occupied nearly the whole of the cultivated land, used to confer every year and agree upon their course of tillage. They were then persuaded by the vicar to disentangle their farms, and cultivate them in the ordinary way. At that time there ceased to be in Sutton any visible sign of any exceptional features in the system of landownership. The lands belonging to the township are recorded in the tithe map, and their measurement in the tithe award, but no balks to mark them are preserved.

I am indebted to the vicar of Sutton for the following illustration of the possible evils of the common field system. It occurred in a parish where he had formerly been resident, which he did not name.

In this parish two adjacent strips of land were occupied respectively by a farmer and a shoemaker. The farmer, who was a careful and diligent cultivator, having well manured and laboured his strip, sowed it with wheat, and as harvest approached saw the prospect of an exceptionally good crop. The shoemaker left his strip entirely untouched. But when the farmer was about to begin to reap, the shoemaker intervened, and claimed that the strip which was cultivated was his, and the untilled strip belonged to the farmer. The field jury was summoned, and the extreme positiveness and assurance of the shoemaker carried the day, and the shoemaker reaped the wheat. The farmer then begged his successful adversary for some compensation for his lost labour and expense, but was told that he might consider himself lucky not to be prosecuted for trespass. The farmer then proceeded to make the best of his bad bargain, and set to work to plough up the weeds and thistles that covered the strip of land awarded him. But as he ploughed he continually turned up pieces of leather, corners wasted in cutting out "uppers," and other refuse of a shoemaker's workshop. These he collected and brought before the field jury. The previous decision was then reversed and the shoemaker was compelled to make restitution to the man he had wronged.

ELMSTONE HARDWICKE (GLOUCESTER).

Elmstone Hardwicke is an extremely interesting example of the common field system in a state of natural decay. Very nearly the whole parish belongs to the Ecclesiastical Commissioners, but the holdings are intermixed and in small parcels, over a large part, perhaps 1000 acres, of the parish, the farms having been granted on leases of three lives. The farmers would be glad to consolidate their holdings and enclose, but the Ecclesiastical Commissioners effectually discourage this, as I was told, by exorbitant demands for increase of rent. On the other hand, I was informed that the Commissioners themselves desired to enclose, but did not care for the expense of proceeding by Act of Parliament, and they were endeavouring to

obtain their object by refusing to "re-life," in order that the leases might fall in, and be converted into leases for short terms that might be made to terminate simultaneously. Thus an old farmer who had a lease of 60 acres in 100 different parcels scattered over the common fields, informed me of the negotiations that had been entered into with him. He was by no means disposed to readily part with his lease, as he had two good lives remaining, both being his nephews, one aged 40 and the other 50. "They'll both mak' 'ighty," he said, that being his own age, though he looked a score of years younger.

This one farmer still (in 1899) followed what had been the customary course of cultivation for the parish—a four years course of wheat, beans, wheat, fallow; this being a modification of a still earlier course of wheat, beans, barley, fallow, the soil being more suitable to wheat than to barley. The other farmers followed no fixed rule, each one cultivating his farm as he chose, subject, however, to the right that was still recognised and exercised, that each occupier could turn horses, cattle and sheep on to the common fields after harvest until the first of November. In consequence of the abandonment of the traditional course of cultivation the common use of the fallow-field has been dropped by general consent, for the last forty or fifty years. The institution of the field jury has also disappeared; though the above-mentioned old farmer still posts the notices declaring the fields open or closed, and so may be said to fill the post of "foreman of the fields," he does so by right of inheritance rather than of election, in succession to his father.

Various controversies have arisen recently in Elmstone Hardwicke with regard to the rights of various persons interested. I have referred above to the case of the farmer who, in the spring of 1899, occupying a "headland" in the common fields on which various strips belonging to his neighbours abutted, instead of following the customary practice and waiting to plough till the last, ploughed his headland before the abutting lands were ploughed, and then sued for damages when his neighbours turned their ploughs on his land.

Another farmer who occupied a very small holding in Elmstone

Hardwicke, and a much larger holding in an adjoining parish, made a practice of turning great numbers of sheep on the Elmstone Hardwicke common fields in the open time, which he was able to keep in the close time on his other land. The question arose whether this unfair procedure was lawful. The coming into force of the Parish Councils Act of 1894 also had the effect of suggesting enquiries into the claims of labourers to share in common-right privileges.

The vicar, the Rev. George Bayfield Roberts, accordingly obtained the opinion of Sir Walter Phillimore on the subject. It was as follows:—

“As far as I can gather from the facts laid before me, I think that every freeholder and copyholder has a right to turn cattle upon every part of the common field, and that the right is not confined to the particular field or part of the common field in which he holds land.

“This right passes to the tenant or occupier under each freeholder or copyholder. The tenant, or occupier, has it, not in his own right but merely as claiming under his landlord.

“I know of no rule of law which would give this right to farmers as such, and deny it to cottagers as such, if the latter have holdings on which they can keep their beasts during close time. But the right to turn on to Lammas lands (as this common field is) can only be exercised in respect of beasts used in the cultivation or manuring of the holding in respect of which the claim is made (*Baylis v. Tyssen-Amhurst*, Law Reports 6 Ch. D. p. 500).

“As the cottagers are said to be tenants of the farmers, the latter can make it clear in all future lettings that they do not let with the cottages the right to pasture in the common field.

“(2) The tenant of the Barn farm should keep his land unenclosed during open time, and anyone who has a right to turn on cattle can sue him if he obstructs (*Stoneham v. London and Brighton Railway Co.*, Law Reports 7 Q. B. p. 1), or can pull down the fencing (*Arlett v. Ellis*, 7 B. & C. p. 346).

“(2a). I do not think it would be wise to pull down a whole fence, or sue for the damage caused by the fence, if substantial

and easy openings were made during open time. But there is some authority for saying that the whole fence must be removed (*Arlett v. Ellis*, cited above).

“(3) The only *locus standi* for the Parish Meeting is, if it has been given by the County Council all the powers of a Parish Council under section 19, sub-section 10, of the Local Government Act, 1894 (56 & 57 Vict. c. 73), to apply to the Board of Agriculture under section 9 of the Commons Act, 1876 (39 & 40 Vict. c. 56).

“This power is given to Parish Councils by section 8, sub-section c, of the Local Government Act, 1894.

“Section 9 of the Commons Act, 1876, enables the Inclosure Commissioners (whose place is now taken by the Board of Agriculture) to give information and direction ‘upon application’ in order to bring about ‘the regulation of Commons’; and for this purpose Lammas lands are included as Commons, as they also came under the Inclosure Acts.

“By section 3 a Provisional Order made by the Board for ‘regulation’ may provide for the ‘adjustment of rights,’ and section 4 shows how much can be done upon such an adjustment.”

This opinion was given in March, 1897. The very significant passage which pointed out that since the cottagers held their cottages from the farmers, they could not effectively claim any rights which the farmers did not choose to grant them, threw cold water on the agitation.

Elmstone Hardwicke is apparently another case in which something would be gained and nothing lost by an Act of Enclosure.

EWELME (OXFORDSHIRE).

Rather more than half this parish, near Wallingford, is legally in the condition of open common fields, and there is besides a very extensive “cow-common” on which is a golf course. The neighbouring parishes of Bensington¹ and Berwick

¹ The Vicar of Bensington has the custody of a remarkable eighteenth century map of the three intermixed parishes.

Salome had until 1852 common fields which were in part inter-mixed with those of Ewelme, and there were commons commonable to all three parishes. In 1852 an Act was passed which was carried into effect in 1863 for the enclosure of Bensington and Berwick Salome, and the parts of Ewelme which were inter-mixed with these. Ewelme is owned by a number of small proprietors who chiefly farm their own land. These made a voluntary division,¹ but they still enjoy certain rights of common and of shooting over one another's land. No labourers enjoy rights of common.

There are two significant facts about this parish.

In the first place, one particular farm enjoys a special right of pasturing sheep on the cow-common, not shared by other farms. This is significant when taken into consideration with the facts for Cambridgeshire and elsewhere related below.

Secondly, this gives a typical instance of the effect of enclosure of *commonable waste* on the poor. One of the commons enclosed was known as the "Furze Common," and it supplied the poor of the neighbourhood with their fuel, for *every* inhabitant had the right of cutting furze on it. After enclosure the Furze Common was allotted to one man, who allowed no trespass on it, and the *owners* of cottages were awarded allotments of land in consideration of rights which the *cottagers* had exercised. The lands so allotted became part of ordinary farms, and the poor simply lost their supply of fuel without any compensation whatever. This was done under the sanction, not of an Enclosure Act rushed through Parliament before 1845, but of the Enclosure Commissioners, appointed expressly to prevent any injury to the class least able to guard its own interests, as well as to facilitate enclosure.

¹ Exchanges of land in common fields so as to enable proprietors to consolidate their properties are authorised by 4 & 5 Will. IV. c. 30.

CHAPTER V.

THE ISLE OF AXHOLME.

To catch the spirit of the common field system, to see that system no mere historical survival, but developing in harmony with modern needs, one must go to the Isle of Axholme. Starting from Doncaster eastwards, through somewhat devious roads, one descends gradually to a wide belt of reclaimed fen. Between this fen on the west, and the river Trent with more fen on the east, is a ridge of low hills, comprising the four large parishes of Haxey, Epworth, Belton and Owston. These constitute the Isle of Axholme—an island, indeed, up to the time of the great drainage operations of Vermuyden in the reign of James I. It was, no doubt, a very ancient home of fishermen and fowlers, who gradually brought the island itself into cultivation, using the plough as a subsidiary means of subsistence. The strenuous opposition offered by the people of Axholme to the work of the Dutch engineer is well known. Even after they were beaten, and the greatest drainage scheme of the seventeenth century was carried through, the four Axholme parishes retained extensive fens, used as common pastures.

When in the eighteenth century the great trade of driving Scotch cattle to the London market, in which Sir Walter Scott's grandfather was a pioneer, sprang up, the route followed diverged from the great north road in Yorkshire, in order to avoid turn-pikes, and the cattle, grazing as they slowly plodded southwards, and fattening on the roadsides, came through Selby, Snaith and the Isle of Axholme. To protect their fields the islanders hedged them along the roadsides, leaving only narrow thoroughfares; then, to make these thoroughfares passable for themselves, they laid down for footpath a stone pavement which still exists for twenty miles. But the old hedges have in many places

disappeared, so that the fields lie open to the road; and in particular, the gates which then guarded every entrance to the fields are now generally represented by gaps.

At the end of the eighteenth century by far the greater part of the island proper was in the condition of open arable fields, with properties and holdings intermixed, as in the open fields of Laxton; though near each village there were enclosed gardens, and closes of pasture. It would appear that the original system of cultivation was a four-year course of husbandry, so that one-fourth of the arable land was at any time fallow, and used as common pasture, and common rights were exercised on two of the other three-fourths after harvest; one-fourth probably being under turnips. On the margin of the hill there were perhaps commonable meadows, though I cannot trace them. Beyond, the common fens and marshes, used mainly for grazing horned cattle, extended over an area of about 14,000 acres.

Arthur Young visited the island at this time, and thus describes it:

“In respect of property, I know nothing more singular respecting it (the County of Lincoln), than its great division in the Isle of Axholm. In most of the towns there, for it is not quite general, there is much resemblance of some rich parts of France and Flanders. The inhabitants are collected in villages and hamlets; and almost every house you see, except very poor cottages on the borders of commons, is inhabited by a farmer, the proprietor of his farm, of from four or five, and even fewer, to 20, 40, and more acres, scattered about the open fields, and cultivated with all that minutiae of care and anxiety, by the hands of the family, which are found abroad, in the countries mentioned. They are very poor respecting money, but very happy respecting their mode of existence. Contrivance, mutual assistance, by barter and hire, enable them to manage these little farms, though they break all rules of rural proportion. A man will keep a pair of horses that has but 3 or 4 acres by means of vast commons and working for hire.

“The enclosure of these commons will lessen their numbers and vastly increase the quantity of products at market. Their

cultivated land being of uncommon fertility, a farm of 20 acres supports a family very well, as they have, generally speaking, no fallows, but an endless succession of corn, potatoes, flax, beans, etc. They do nearly all their work themselves, and are passionately fond of buying a bit of land. Though I have said they are happy, yet I should note that it was remarked to me, that the little proprietors work like Negroes, and do not live so well as the inhabitants of the poor-house; but all is made amends for by possessing land."¹

In 1795 the chief landowners took steps to obtain an Act for enclosing all four parishes. There were stronger reasons for enclosing than in the majority of the East Yorkshire and Lincolnshire parishes all around, in which Parliamentary enclosure was being pushed furiously on, for the fens were capable of enormous improvement. But in the Isle of Axholme it was not possible for the chief landowners to overbear the opposition of the villagers. One peculiar feature of the locality was that every cottage had a common right, and there were no rights attached to land apart from cottages. This fact, and the peculiarly wide distribution of property, caused the decision to rest with the peasantry. They raised no objection to the division and drainage of the marshes, perceiving that their allotments would be far more valuable after drainage than their common rights before; so this part of the scheme was generally agreed to. But on the question of the enclosure of the arable fields they were not complacent. They saw that the expense of hedging a small allotment would be heavy, and the injury done by the hedge to a small plot, of say 1 or 2 acres, by shading the land and sheltering it from the wind would more than counterbalance the advantage of having that holding in one piece instead of in two or three, to say nothing of the loss of the space given up to hedges. They also probably feared that the arable land, if enclosed, would largely be laid down to grass, and so the benefit of an increased demand for labour and higher wages promised by the enclosure of the marshes would be lost, at least in some

¹ "Agricultural Survey of Lincolnshire," p. 17.

degree, through the enclosure of the fields. Accordingly the necessary consent of a "three-fourths majority in number and value" of the owners was not obtained, and the proposal to enclose was defeated. It would appear that all the educated, intelligent, and influential people did their best to overcome this "ignorant prejudice." But on the other hand there were the votes of all those cottagers who did not as yet possess strips in the common fields, but who hoped to be able to purchase them. They saw that while thousands of acres of land lay immediately round the villages in acre, half-acre, and rood strips, there was a chance of buying one, and so taking the first upward step from the rank of the landless labourer. On enclosure those strips would give place to closes of at least several acres each, and the closes would be quite out of their reach. Blind, obstinate, wilful, and prejudiced as the villagers seemed to their betters, the event shows that they were entirely accurate in their view of the situation.

Arthur Young's account of these proceedings is as follows: "In the Isle of Axholm there is an immense inclosure on the point of beginning, the Act and survey having been passed of no less than 12,000 acres of commons in the four parishes of Haxey, Hepworth, Belton, and Owston. I passed these commons in various quarters, and rode purposely to view some parts; they are in a wretched and unprofitable state, but valued, if inclosed, in the ideas of the islanders at 10s. or 11s. an acre.

In Haxey there are 305 claims on account of 3810 acres.

„ Hepworth „ 236 „ „ 2285 acres.

„ Belton „ 251 „ „ 3664 acres.

„ Owston „ 229 „ „ 4446 acres.

"Cottage rights are claims, but lands without a cottage have none. It was a barbarous omission that when the Act was procured they resisted a clause to divide the open arable fields subject to rights of common. But they have here, by a custom, a right of inclosure which is singular; every man that pleases may enclose his own open field land notwithstanding the rights of common upon it while open; and accordingly many do it

when, by purchase, they get five or six acres together, of which I saw many examples." ("Agricultural Survey of Lincolnshire," p. 79.)

Somewhat later a second attempt was made in the parish of Owston to obtain an enclosure with partial success. Three of the four fields were divided and enclosed: but the same motives which prevented the enclosure of the four parishes at the previous attempt were strong enough to secure that one field should remain open. It was in 1811, I was locally informed, that the Owston Enclosure took place. I can find no record of the Act.

As we saw above, the old system (probably a four-field course) of cultivation had dropped into disuse even before the beginning of the nineteenth century, but still, up to about the year 1850, the custom remained that on one of the four fields, that under wheat, after the crops had been carried, the "Pindar" gave notice that "the fields are to be broken," and over that field common rights of pasture were exercised for about a month, from some day in October to Martinmas (November 23rd). Then the Pindar kept watch over the grazing animals night and day, and by night built up enormous bonfires, with all the boys of the village clustering round and roasting potatoes.

But about 1850 even this custom disappeared, and now every holder of lands in the open fields cultivates them as he chooses, but they must be under some form of tillage as long as they remain open. But the tendency, observed by Arthur Young, for the larger owners of lands in the common fields to buy, sell and exchange strips with other owners with the object of getting some half-dozen acres in one continuous piece and then enclosing them, has continued up to the present day. Such enclosures are laid down in grass, and in this way the area of the open fields has gradually been reduced.

The strips of land in the open fields are known as "selions," the auctioneers' notices of a sale reading, "All that selion piece of land," etc. They are also known as "acres," "half-acres," "roods," etc., but these terms must not be taken as exactly defining their area. A nominal acre varies in area from a minimum of about half an acre to a maximum of an acre and a

half. As the half-acres and roods similarly vary, it follows that the largest "half-acres" are bigger than the smallest "acres."

The general aspect of the fields is well shown in the photograph taken for me by Mr. Newbit, of Epworth. I asked in a bar-parlour in Haxey, "Are these allotments both sides of the road?" A labourer answered, "Yes, but there are seven miles of these allotments." But the publican corrected him. "Well, it's not allotments exactly, it's a *very old system*, that's what it is." Further conversation with one man and another gave me a strong impression that the people of Axholme are proud of their "very old system." That they have some reason to be proud of it Mr. Rider Haggard bears witness:

"The Isle of Axholme is one of the few places I have visited in England which may be called, at any rate in my opinion, truly prosperous in an agricultural sense, the low price of produce notwithstanding, chiefly because of its assiduous cultivation of the potato."¹

Axholme may be described as a district of allotments, cultivated, and in great part owned, by a working peasantry. The "assiduous cultivation of the potato" is rather an indication of the real strength of Axholme agriculture, than a true explanation of it. At the time of Arthur Young's visit, the isle was noted for the cultivation of flax and hemp; and this continued to be a feature of the local agriculture till about thirty or forty years ago, when the "assiduous cultivation of the potato" succeeded it. Now, as Mr. Rider Haggard notices, experiments are carried on with celery. The small holders, I was assured on all sides, cultivate the land much more thoroughly than large farmers do their farms, and the very look of the crops confirmed this eloquently, even to my unskilled observation. Mr. Rider Haggard quotes a local expert, Mr. William Standring, as saying, "Wheat crops in the isle *averaged seven quarters* (56 bushels) an acre, the oats nine or ten quarters, the clover hay, which grew luxuriantly, two or three tons an acre, and the roots were splendid." He continues, "That Mr. William Standring

¹ "Rural England," Vol. II., p. 186.

did not exaggerate the capacities of the isle, I can testify, as the crops I saw there were wonderfully fine throughout, particularly the potatoes, which are perhaps its mainstay.”¹

The secret of the agricultural success of Axholme is clearly *la carrière ouverte aux talents*, which is secured to agricultural labourers by the open fields. The spirited and successful cultivation of varying crops follows naturally.

How the upward ladder is used, was well explained by a Mr. John Standring, himself a holder of ten acres, before the Select Committee of the House of Commons on Small Holdings in 1889.

It is first to be noticed, however, that the general level of wage is exceptionally high for a purely agricultural district at a considerable distance from any considerable town. The customary wage, I was informed in 1903, was 3s. per day. Mr. Rider Haggard, in 1901, found it “2s. 9d. a day for day men, 18s. a week for horsemen, and 16s. a week, with cottage, for garth-men. Men living in the house with foremen and owners receive about £24 per annum and food, and horsemen £30 per annum and food.”

But when the labourer who has been living in marries and takes a cottage, he also takes up a holding in the fields. He begins with one “land,” then takes a second, a third, and so on. The following table, showing the way in which land is held in the parish of Epworth, was submitted to the Select Committee² by Mr. J. Standring:—

Of holdings over 200 acres there are 2 occupiers.

“	“	100	“	and under 200, there are 12 occupiers.
“	“	50	“	“ 100 “ 14 “
“	“	20	“	“ 50 “ 31 “
“	“	10	“	“ 20 “ 40 “
“	“	2	“	“ 10 “ 115 “
“	“	$\frac{1}{2}$	“	“ 2 “ 80 “

The eighty holders occupying from half an acre to two acres would all be men in regular employment, as a rule, agricultural

¹ “Rural England,” Vol. II., p. 194.

² Report, p. 189.

labourers. A body of these sent their deposition to the Select Committee in the following form:—

“We, the undersigned, being agricultural labourers at Epworth, are in occupation of allotments or small holdings, varying from 2 roods to 3 acres, willingly testify to the great benefit we find from our holdings. Where we have sufficient quantity of land to grow 2 roods each of wheat, barley and potatoes, we have bread, bacon, and potatoes for a great part of the year, enabling us to face a long winter without the dread of hunger or pauperism staring us in the face.”

But the more enterprising of these labourers do not rest content with so small a holding, and these pass into the next class, those who hold up to 10 acres. “Many such,” says Mr. J. Standring, “keep a horse and a cow and a few pigs. And on some of the stronger land two or three of these will yoke their horses together and work their own land, and also land belonging to other men similarly situated who do not keep horses. As a rule they have done very well—I scarcely know a failure.” The payment for horse-hire is usually made in labour.

The most successful of these again recruit the ranks of the larger farmers. “I do not believe there is one in ten in my parish, and in the adjoining parish, among those who are renting from 50 to 100 acres, but what, in my time, has been an agricultural labourer or an agricultural servant before he was married; and each of them, to my own knowledge, has commenced with two or three acres, and in some cases not more than one acre . . . one man who is now occupying 200 acres was a labourer in his early days.”

These bigger farmers sometimes move elsewhere, and take larger farms, or bring up their sons in other occupations than farming, so that the farm of 150 to 200 acres becomes again available for division into small holdings. Thus, in spite of the continual growth of the holding occupied by individual men at different stages in their career, the average size of holdings does not show any tendency to increase. This is well shown by the figures given for Epworth, respectively, by Arthur Young and Mr. J. Standring, at about an interval of a hundred years.

There were only 236 claimants of allotments in the Epworth commons at the end of the eighteenth century; in 1889 there were 291 occupiers of the 5741 acres in the parish, occupying therefore, on an average, less than 20 acres each.

The same eagerness to own land which Arthur Young noticed has also continued to prevail. Land is bought on the building society principle, money for the purpose being borrowed usually at 5 per cent. per annum, very frequently through the lawyer who conducts the sale. In the days of agricultural prosperity land in the open fields of Haxey, Epworth, and Belton was sold at £130 per acre; land in the one remaining open field of Owston as high as £140 per acre. Even now, in spite of the tremendous fall in price of agricultural produce, the ordinary price is about £70 to £75 per acre; which is about twenty-five years' purchase of the rent.

It is obvious that a man who borrows money at 5 per cent. to buy land which can only be let at 4 per cent. on the purchase price embarks on a speculation which from the purely commercial point of view, can only be profitable provided the land is appreciating in value. There were naturally cases of men who, at the time when prices were falling most rapidly, were unable to keep up their payments of interest and instalments of principal, and who had in consequence, after a severe struggle, to forfeit their partially won property. At this time the Isle of Axholme won the evil repute of being "the paradise of lawyers." But it would, I believe, be fair to say that the peasantry on the whole stood the strain of agricultural depression exceptionally well, and that their prosperity, with steadier prices, revived exceptionally quickly.

The Isle of Axholme has been singularly successful in preserving the spirit of the common field system—social equality, mutual helpfulness, and an industrial aim directed rather towards the maximum gross produce of food than towards the maximum net profit; while at the same time it has discarded those features of the system which would have been obstacles to agricultural progress. The "barbarous omission" to enclose the open arable fields has been abundantly justified.

SOHAM.

The parish of Soham, in Cambridgeshire, is another example of a great development of small holdings in connection with the persistence of open arable fields. This parish, unlike most Cambridgeshire parishes, has never been enclosed by Act of Parliament, and the tithe map indicates the survival of about 1100 acres of common field and 456 acres of common in a total of 12,706 acres. Since the tithe commutation the area of common has shrunk to about 236 acres, but from the Ordnance map it appears that there is still a very large area of open field land in four large fields, known as North Field, Clipsatt Field, No Ditch Field, and Down Field; and a smaller one, Bancroft Field. Mr. Charles Bidwell gave the Special Committee on Small Holdings (1889) the following account of holdings in this parish:—

Under 1 acre	...	...	...	...	195 holdings.
Over 1 and under 5 acres	...	...	...	...	77 „
„ 5	„ 10	„	...	...	34 „
„ 10	„ 20	„	...	...	43 „
„ 20	„ 50	„	...	...	57 „
„ 50	„ 100	„	...	...	32 „
„ 100	„ 200	„	...	...	6 „
„ 200	„ 500	„	...	...	8 „
„ 500	„ —	„	...	...	5 „

(Appendix, p. 501.)

Thus the total area of the parish is held by 457 occupiers, who therefore hold, on an average, 28 acres each. In this case it is stated that the occupiers of the smallest holdings derive considerable benefit from the common. A German enquirer who visited Soham as an example of an unenclosed parish, found it less poverty stricken than the other parishes in the neighbourhood, on account, he was told, of the existence of the common pastures. (W. Hasbach, *Die englischen Landarbeiter*, 1894.)

WESTON ZOYLAND.

The idea occurs to one, whether it would not have been possible to secure by an Act of Enclosure for a common field,

the abolition of common rights which hindered each farmer or peasant from cultivating his holding to the best of his ability, and the laying together of the scattered strips which formed each holding, without ruining the small proprietors and small farmers, or encouraging the laying down of tilled land under pasture.

We find *one* example of such an attempt. The parish of Weston Zoyland, in Somerset, in 1797 enclosed 644 acres of commonable pasture, and at that time and in that neighbourhood the enclosure of Sedgemoor was being rapidly pushed on, as rapidly, in fact, as the local farmers could be induced to take up the land. Perhaps in consequence of this quenching of the land hunger of the farmers with capital, when in 1830 it was resolved to deal with the common fields, the Act took the form of one for *dividing and allotting*, but not enclosing, Weston Field. The consequence is that this great field of 500 acres still remains open and unenclosed; the land is specially fertile, there are an exceptionally large number of small properties in it, and it is all kept under tillage. I am informed that one of the first acts of the Weston Zoyland Parish Council, when, on coming into existence, it took over the custody of the parish maps and documents, was to re-define the roads that passed through the field, in accordance with the Commissioners' map and award.

CHAPTER VI.

SOME RECENT ENCLOSURES.

UPTON ST. LEONARDS (NEAR GLOUCESTER).

THIS enclosure took place at the same time as that of Castor and Ailesworth, and was completed in 1899. The common fields consisted of 1120 strips of arable land, total area 520 acres, and the "balks" or "meres" separating the strips were estimated at 14 acres. There were more than eighty owners.

No recognised course of husbandry had been followed for about sixty years previously. It is believed that before that time a four-year course obtained, but when mangel wurzels were introduced to the neighbourhood the recurring fallow was discontinued. The right of common after harvest was, however, still maintained. If any cultivator chose he might grow turnips, but he did so at his own risk, and had to keep a boy to guard them from the opening of the fields to the time they could be pulled. Old mere stones are found in the meadows of this parish, and various local traditions remain belonging, apparently, to a period when the village customs resembled those described for Stratton and Grimstone.

TOTTERNHOE (BEDFORDSHIRE).

The Enclosure Act was passed in 1886, and the award is dated 1891. Before enclosure Totternhoe was a typical open-field parish; there were only 370 acres of old enclosure, to 1797 acres of common field arable, and 193 acres of common. The situation of Totternhoe is like that of Clothall, on the steep northern slope of the Hertfordshire chalk hills, which here have an almost mountainous appearance. The greater part of the parish was in the ownership of the lord of the manor, but there were forty

owners of land altogether, the others being chiefly yeomen. The movement for enclosure came from these yeomen. They took this step in order to protect themselves against the tenants of the lord of the manor, who, whether from ignorance or otherwise, endeavoured to prevent the exercise of well-known rights of common over land in their occupation. The hill top was saved as an open space, and is a favourite picnic resort for the people of Dunstable. Recreation grounds and land for allotments were also set out, as has been the rule since the passing of the Commons Act of 1876. I asked one of the yeomen, who had taken a leading part in bringing about the enclosure, whether it had benefited the parish. He said undoubtedly it had done so, but "the parish has not recovered from it yet." Questioned as to how this could be, he gave me to understand that the actual increase to the cultivators in annual value was not equal to the interest on the capital expended on carrying out the enclosure; that the assessment had gone up, and the burden of rates and taxes was consequently increased. The land allotted to the lord of the manor still, in the summer of 1900, was mainly unenclosed, and one could get something of the impression of the "champion" country, an impression of great open fields sweeping up to bare downs.

NORTH AND SOUTH LUFFENHAM AND BARROWDEN (RUTLAND).

The first steps towards the enclosure of these three parishes were made immediately after the passing of the 1876 Act; the Enclosure Act was passed in 1878, and the awards were made in 1881 and 1882. Out of 5480 acres in the three parishes, 4800 were common-field arable, a heath claimed by both Barrowden and South Luffenham occupied 390 acres, and much of the remainder was commonable meadow and pasture. Two systems of cultivation obtained. Part of the land being heavy clay was on a three years' course of wheat, beans, etc., and fallow, as at Laxton and Eakring; the lighter land was under a six years' course. The report of the Enclosure Commissioners says of Barrowden that the 1240 acres of arable land "is divided in

2790 strips, some not more than 12 feet wide, each divided from its neighbour by a green balk, which is a nursery of weeds." Old farmers, however, assured me that the balks were mostly gone before enclosure. Field reeves were elected, and they settled any dispute that arose in consequence of the absence of balks, and individual farmers quickly detected, by pacing across their strips, if a furrow had been appropriated by a neighbour.

Here, again, I asked whether the enclosure had been a benefit, and I was told that the labourers had benefited by the allotments and recreation grounds; that the lord of the manor of South Luffenham had benefited, because he got the disputed moor, but that farmers, as farmers, had gained nothing, and as common-right owners they had lost through the enclosure of the moor.

Enclosure in this case originated in what may be called the normal way, *i.e.*, on the initiative of the lords of the manors. It was the doubtful ownership of the Barrowden and Luffenham moor which had until 1876 prevented enclosure; then the respective lords agreed to combine to obtain an enclosure of all three parishes, and let the Commissioners determine to which parish the moor belonged. It was awarded to Luffenham, but the Luffenham freeholders lost it just as much as those of Barrowden; it is now the private property of the lord of the manor.

HAM FIELD.

A curious case of enclosure by Act of Parliament unconnected with the General Enclosure Acts is that of Ham Field by the "Richmond, Petersham and Ham Open Spaces Act, 1902" (2 Edward VII., c. ccliii.). It is entitled, "An Act to confirm agreements for vesting common and other land in the local authorities of the districts of Richmond and Ham, and the Surrey County Council as public open spaces, and for other purposes." But while it does incidentally confirm these agreements, the "other purposes" comprise the main object of the bill, which is to allow the owners of Ham Common, of whom

the Earl of Dysart is the principal, to enclose Ham Common Field, and convert it into building land.

The preamble is similarly misleading. The first sentence runs, "Whereas the prospect from Richmond Hill over the valley of the Thames is of great natural beauty, and agreements have been entered into with a view to preventing building on certain lands hereinafter mentioned"—a sentence admirably framed to disguise the fact that the effect of the Act is to extinguish the common rights over Ham Field which had previously prevented building, and so to convert the middle distance of the famous view from Richmond Hill into an expanse of roofs, perhaps of villa-residences, and perhaps——!

The agreements recited in the Act represent the consideration for which the public authorities mentioned bartered away the beauty of the view. Kingston Corporation gets nine acres for a cricket field; Richmond Corporation is confirmed in the ownership of Petersham Meadows, which was formerly a subject of dispute, and acquires a strip of land along the river; and the Surrey County Council acquires 45 acres of riverside land. The meadows and riverside land in each case are to be maintained as open spaces by the authorities. Ham itself merely gets the freehold of Ham Common, which means, in effect, that what slight danger there might have been of the enclosure of this part of the open and commonable land of the parish is removed.

The Earl of Dysart, at the cost of a sacrifice that is probably apparent rather than real, obtains by this Act the right to convert some 200 acres of arable common field into a valuable building estate; the smaller owners acquire a similar right without any compensating sacrifice at all; and the only losers by this profitable transaction are the people of London, who were not consulted in the matter.

MERROW.

The parish of Merrow, adjoining Guildford on the east, is stated in the return of 1873 to have had 850 acres of common

field. The land in question covers the lower slopes of the chalk hill, the higher portion of which is Merrow Down ; beneath it is Clandon Park, the seat of Lord Onslow. Up to about the year 1873 this common field did exist ; the properties of Lord Onslow, the chief proprietor, were very much intermixed with those of smaller proprietors ; the farm holdings were similarly intermixed with one another, and with a number of strips of land occupied by labourers and cultivated as allotments. But no common rights were exercised over these lands, either by the occupiers over one another's lands, or by the villagers, within living memory ; nor, except that the whole of the field was in tillage, was there any common rule for its cultivation. The existence of a great extent of common is in itself a sufficient explanation of the disappearance of common rights over the tilled land.

In 1870 the present Lord Onslow came into the property, and when a year or two later he attained his majority, he proceeded to consolidate his property in Merrow Field, by buying out the other proprietors, or giving them land elsewhere in exchange. The field is still bare of hedges, and under tillage ; but enclosure, in the technical sense, has been completely carried without an Act of Parliament.

Since the enclosure the allotments, which had been numerous, have generally been given up ; but the labourers do not attribute this to the enclosure, but to the industrial evolution. " There are no farmers nowadays, only land spoilers. They've turned market gardeners, and they sell *milk* " (with intense scorn). " The land ought to grow beef, and barley to make good beer, that's what Englishmen want,—yes, and wheat to make bread. But now they all grow garden stuff, what's the good of an allotment to a man ? If you have anything to sell, you can't sell it. It's no good growing any more than you can eat."

It may be added that along the river Wey, from Guildford down to Byfleet, there are some very extensive lammas meadows, known by such names as Broad Mead and Hook Mead. The holdings in these are intermixed, individual pieces sometimes not exceeding an acre.

STEVENTON AND THE BERKSHIRE DOWNS.

That part of Berkshire which lies between the valley of the Kennet and the Thames would appear, from the return of 1873, to be specially rich in surviving open fields. The Blue Book assigns to

Brightwell	...	...	1000 acres of common field.		
West Hagbourne...	...	550	"	"	
East Hendred	...	2794	"	"	
West Hendred	...	1900	"	"	
East Ilsley	...	1400	"	"	
Wallingford St. Leonard...		570	"	"	
Yattenden	...	252	"	"	

As Brightwell was enclosed in 1811, and East Hendred in 1801, the statement with regard to these two parishes plainly is incredible; but in view of the undeniable fact that Steventon, which lies almost in the centre of this district, was not enclosed till 1883, there seemed so much possibility of survivals in the other parishes that in July, 1904, I traversed the whole district in search of such survivals. But the search was entirely unsuccessful; it was plain that Steventon was at the time of its enclosure the last remaining example of the old system in this part.

Here, as in the Hertfordshire district described above, and in the Wiltshire district dealt with in Chapter X., "Enclosure and Depopulation," enclosure is one aspect of a change of which the most vital aspects are the engrossing of farms and the consolidation of properties. In each parish this movement proceeds along the line of least resistance; in one parish all impediments in the way of the most profitable management of estates are swept away by the drastic remedy of an Enclosure Act; in others they are removed gradually.

The latter method I was enabled, by the help of Mr. Bridges, to trace in detail in the case of Yattenden. The Board of Agriculture return, as we have seen, assigns 252 acres of common field to Yattenden. The tithe map, dated 1845, on

which this is based, shows in one corner of "Yattenden Great Field" about 20 acres of intermixed ownership and occupation, forming part of one "furlong," remaining in the characteristic common-field arrangement; the rest of the so-called "Yattenden Great Field" and "Everington Field" were in part divided into hedged fields, and in part into compact stretches of about 20 acres each, still unhedged, with here and there single acres detached in the midst of them; many of these single acres being glebe.

An older manorial map, dated 1773, showed that at that date nearly half the parish was open; the eastern part was already divided into closes, except for a small stretch of lammas meadow, divided into small intermixed holdings, by the river Pang; but the western part, Yattenden and Everington fields, were almost entirely open, and divided in furlongs, and the furlongs in acre and half-acre strips. These strips on the map are all marked with the letters of the alphabet, to indicate whether they are held by the lord of the manor, by his tenants, or by other owners.

In other words, the process of gradual enclosure, which began before 1773, was continued afterwards, and was nearly complete in 1845. The end came about the year 1858, when Frilsham Common, in an adjoining parish, was enclosed. About half of the intermixed strips in Yattenden Great Field belonged to a yeoman, who was, his brother told me, "a great man for defining his boundaries." The enclosure of Frilsham Common gave the slight stimulus to the mind of Yattenden necessary to overcome its mental inertia, and make change possible, so the yeoman in question was able to effect the exchanges he desired, and others following his example, the lay properties were all separated. But still the glebe consists in part of an acre here and an acre there in the midst of lands belonging to laymen. These are let with the lands in which they lie; they have no mark to distinguish them, nor boundaries to limit them; the tithe map and award preserve the record of them, and the vicar receives their rent.

This circumstance of the glebe lying in part in separate

unfenced strips scattered over the parish, let with the lands in which they lie, and so not influencing the agriculture of the parish, though testifying to the past system, is by no means uncommon in the parishes not enclosed by Act of Parliament.¹

In general the results of the two different methods of enclosure in this district are practically identical. Superficially the characteristic features of the "champaign" or "champion" country remain. The population is concentrated in the villages; the sites of which appear to have been originally selected for convenience of water supply; outside the villages are the long sweeps of open fields of barley, wheat or beans, lying generally open to the roads, and to one another, and to the open down, though one notices a tendency to an increased use of wire fencing. The monotony is broken by the beautiful curves of the hill slopes, and by clumps of trees; here and there, on steeper inclines, lynchets are clearly visible, and occasionally what looks like an inconsequent hedge, beginning and ending in the middle of the field—an old "mere" or "balk" on which bushes happened to grow.

On the other hand, the farms run generally from 200 to over 1000 acres each; machinery is extensively used; the supply of labour, though not so superabundant as a generation or two ago, is still sufficient, the customary wage being 2s. per day. The men themselves struck me as being of finer physique than the agricultural labourers I have seen in any other part of the South or Midlands of England; but they appear to be as completely shut out from any rights over the land, from any enterprise of their own upon the land, or from any opportunities for rising into the farmers' class as can well be conceived. Only one man whom I met could remember a different condition. He, a labourer of seventy-three, said that in North Moreton before the enclosure (completed in 1849) every villager who could get a cow could keep it in the open fields, and all the villagers also had rights of cutting fuel. Under the Enclosure Act some

¹ Mr. A. N. Palmer, in "Ancient Tenures of Land in the Marches of North Wales," gives a list of parishes in one Hundred containing, or known to have contained, "quilled fields," *i.e.* fields containing strips of land belonging to a different owner from the rest of the field, these strips being usually glebe.

moneys were set aside to provide the poor with fuel in compensation for these rights, but latterly the amount provided had much diminished.

Steventon, which lies in the centre of this district, is to some extent exceptional. The manor has always been in ecclesiastical hands, from the first time when the village was founded as a settlement from the Abbey of Bec in Normandy to the present day, when it is held by the Ecclesiastical Commissioners. In the intervening period it belonged to Westminster Abbey.

No doubt it was in consequence of this that through the greater part of the nineteenth century, while all the other parishes passed into their present condition of large farms, the farms and properties in Steventon remained small. Up to about 1874 there were some eighteen yeomen farmers in the parish, which comprises 2,382 acres, fully three-quarters at that time being arable. In addition, the lands belonging to the Ecclesiastical Commissioners were divided into small holdings, and all these were intermixed. The system of cultivation was very simple. The arable land was divided into two fields, one known as the "white corn field," growing wheat or barley, the other as the "black corn field," growing pulse or some other crop.

In the severe agricultural depression that followed 1874, culminating in 1879, the yeomen were obliged to borrow in order to continue farming, and they mortgaged their lands to certain gentlemen in the neighbourhood who had money to invest. As one bad season followed another, loan had to be added to loan, till the security was exhausted, and the land passed into the possession of the mortgagee. In this way the number of landowners was reduced to five. Then enclosure, which had been proposed and rejected in the forties, was resolved upon. The Act was obtained in 1880, and the award was made in 1883.

There was considerable disappointment among those who carried out the enclosure at the results. They were surprised and disgusted at the amount of land reserved for allotments and recreation ground; they were also surprised at the expense, which amounted, I was told, to nearly £10,000. Some were

unable to meet the calls upon them, and went bankrupt. But a large portion of the cost was for road-making, and when this had been paid for, the chief advantage which had been gained by the whole proceeding, economy in horse labour, was realised. Where previously it had taken three horses to get a load of manure to a given spot in the open fields, along the tracks assigned for that purpose, one horse could draw the same load to the nearest point on the metalled roadway, and a second horse hitched in front would enable it to reach its destination.

ENCLOSURE of COMMON FIELDS
BY ACT OF PARLIAMENT.

-  Enclosed before the General
Enclosure Act of 1801.
 Enclosed between 1802 and 1845.
 under General Enclosure
Act of 1845.

Scale 1:5,000,000 or 1 inch = 79 Stat. miles.

10 0 20 40 60 80 100



CHAPTER VII.

AGRICULTURE IN OPEN FIELD PARISHES A HUNDRED YEARS AGO.

A GLANCE at the accompanying Enclosure Map of England will indicate the importance of common fields in the social life of rural England at certain dates. It was prepared in the following manner: On the Ordnance County diagrams each parish which had an Enclosure Act by which common field arable was enclosed was coloured; if the Act was passed between 1700 and 1801 it was coloured yellow; if passed after the general Enclosure Act of 1801 and before that of 1845, it was coloured green; if after 1845, purple. A map of England was drawn summarising the results of the county maps. On this *at least* all purple patches showed parishes which possessed open field arable in 1845; *at least* all the green and purple area combined indicated parishes which had open field arable in 1802; *at least* all the coloured area had open field arable in 1700. In the printed map these colours are represented by three forms of shading. Of the unshaded area one can simply say that the Enclosure Acts throw no light upon its agricultural history so far as the land under tillage is concerned. To a very great extent it was undoubtedly being enclosed otherwise than by Act of Parliament simultaneously with the progress of Parliamentary enclosure, but to a still greater extent it either never passed through the common field system or was enclosed before 1700. This statement raises questions which are dealt with below. For the present I have to deal with the general history of those parishes which did pass through the common field system.

The original Board of Agriculture, which was an association on similar lines to those of the Royal Agricultural Society, but

enjoying a grant from the Treasury, was founded in 1793, with Arthur Young as secretary and Sir John Sinclair as president. It immediately took in hand the work of making an agricultural survey of Great Britain, county by county. Some counties were surveyed several times, but the original survey of England was completed in the years 1793 and 1794. William Marshall, the ablest agricultural writer of the time, single-handed accomplished an agricultural survey of England, ignoring county divisions and dividing the country according to natural divisions marked by similarity of soil, crops and agricultural methods. The two surveys together give us ample information on the different methods of cultivating open or common fields at the end of the eighteenth century.

On the whole, the most general system, particularly in the midland counties where common fields remained most numerous, was the following form of the three-field system:—

“One part” (or one of the three fields) “is annually fallowed, a moiety of which is folded with sheep and sown with wheat; another moiety is dunged and sown with barley in the succeeding spring. The part which produces wheat is broken up and sown with oats, and the part which produces barley is at the same time generally sown with peas or beans, and then it comes in routine to be again fallowed the third year.”¹ This gives us the following rotation of crops: (1), wheat; (2), oats; (3), fallow; (4), barley; (5), peas or beans; (6), fallow. This was the system prevailing in Huntingdon.

The same system prevailed in the heavy clay lands of Bedfordshire, but in the lighter lands sometimes a four-field course was adopted, sometimes the half of the nominally fallow field that had the previous year given crops of wheat and oats was sown with turnips, and clover was sown with barley the succeeding year.²

The commonest four-field course is that described for Isleham, Cambridgeshire: (1), wheat; (2), barley; (3), pulse or oats; (4), fallow; the fallow field being dunged or folded with sheep.

¹ Maxwell, “Huntingdon,” p. 9.

² T. Stone, “Bedfordshire,” p. 8.

At Castle Camps, also in Cambridge, a two-field course of alternate crop and fallow obtained.¹

Coming further south for Hertfordshire, we are told that the "common fields are mostly by agreement among the owners and occupiers cultivated nearly in the same way as in the enclosed state."² In Buckinghamshire the regular three-fields course was followed in some parts, but in Upton, Eton, Dorney, Datchett, Maysbury and Horton, "the occupiers have exploded entirely the old usage of two crops and a fallow, and now have a crop every year."

Two Buckinghamshire parishes underwent experiences which have been wrongly cited as typical of the inconveniences of common fields, whereas they are rather instances of the lawless conduct of village bullies. Steeple Claydon had 2500 acres of common field, on which the customary course was one crop and a fallow. "About fourteen years ago" (*i.e.*, about 1779) "the proprietors came to an agreement to have two crops and a fallow, but before the expiration of ten years one of the farmers broke through the agreement, and turned in his cattle upon the crops of beans, oats and barley, in which plan he was soon followed by the rest."³ The agreement, if that of a three-fourths majority (see below), was legally binding on all owners and occupiers, and the first farmer was liable to the same pains and penalties as if he had turned his cattle into crops standing on enclosed fields belonging to another farm. Possibly, however, the crops were a failure, and feeding them off with cattle was as good a way of dealing with them as another.

A still more difficult case to understand is that of Wendon (3000 acres common field). It is reported as follows:—"About fourteen years ago the parishioners came to an agreement and obtained an Act to lay the small pieces of land together. . . . When the division took place, the balks were of necessity ploughed up, by which a great portion of the sheep pasture was

¹ Vancouver, "Cambridgeshire," p. 33.

² D. Walker, "Hertfordshire," p. 49.

³ William James and Jacob Malcolm, "Buckingham," p. 30.

destroyed.¹ It then became expedient, and it was agreed upon at public vestry, to sow clover and turnips as a succedaneum for the balks. Two years since, one of the farmers, occupying 16 acres of these common fields, procured in the month of May a large flock of lean sheep, which he turned on the clover crops; being then nearly in bloom, the greater part of which they devoured."

Of Oxfordshire we are told "the present course of husbandry is so various, particularly in the open fields, that to treat of all the different ways of management would render this report too voluminous. It may suffice generally to remark that some fields are in the course of one crop and fallow, others of two, and a few of three crops and a fallow. In divers unenclosed parishes the same rotation prevails over the whole of the open fields; but in others, the more homeward or bettermost land is oftener cropped, or sometimes cropped every year."² Where one crop and a fallow was the custom the crop might be wheat, barley or oats; and sometimes tares were sown on the fallow field and cut green. The three and four-field systems prevalent were those described above.

In Berkshire a six-year course, evidently evolved from an older three-years course, was found:—(1), wheat; (2), barley; (3), oats, with seeds; (4), clover, mowed, and then grazed upon in common; (5), oats or barley; (6), fallow.

An agreement to withhold turning out stock during the time in which a field was commonable by ancient custom, in order that turnips, vetches, etc., might be grown, was practised, and termed "hitching the fields."³ We get the same expression for Wiltshire, where a part of a field set aside for vetches, peas, beans, turnips, or potatoes was called a "hookland" or "hitchland" field.⁴ In Wiltshire customs similar to these described as surviving recently in Stratton and Grimstone were prevalent;

¹ James and Malcolm, "Buckingham," p. 29. I have been unable to find any trace of this Act.

² Richard Davis, "Oxfordshire," p. 11.

³ William Pearce, "Berkshire," p. 29.

⁴ Thomas Davis, "Wiltshire," p. 43.

clover was generally substituted for fallow, and was partly mowed for the individual benefit of particular occupiers, and partly fed upon by the village flock. The following systems are reported :—

(a) First, wheat; second, barley with clover; third, clover part mowed, part fed.

(b) First, wheat; second, barley; third, oats with clover; fourth, clover part mowed, part fed.

(c) First, wheat; second, barley with clover; third, clover mowed; fourth, clover fed (one-third or a quarter of this field being "hitchland").¹

Turning northwards again from the centre of England, in Rutland the old three-year course of two crops and a fallow was universal in the unenclosed parishes;² in Lincoln two, three and four-field systems were practised;³ the two-field course was also prevalent in Yorkshire.⁴

A singular practice was followed in the East Riding Wolds. "The greater part of the Wold townships which lie open have a great quantity of out-field in leyland, *i.e.*, land from which they take a crop every third, fourth, fifth, or sixth year, according to the custom of the township."⁵

In constrast we may mention the Battersea common fields, which were "sown with one uniform round of grain without intermission and consequently without fallowing."⁶

¹ Thomas Davis, "Wiltshire," p. 43.

² John Crutchley, "Rutland," p. 8.

³ Thomas Stone, "Lincoln," p. 26.

⁴ Isaac Leatham, "East Riding," p. 40.

⁵ Isaac Leatham, "East Riding," p. 42.

⁶ James and Malcolm, "Surrey," p. 48.

CHAPTER VIII.

NORFOLK AGRICULTURE.

WHEN we come to Norfolk we find hints at so many special features that Norfolk agriculture demands separate treatment. The preamble of a Norfolk Enclosure Act is remarkably different from those for the rest of the country. A typical one is 1795, c. 67 :

“Whereas there are in the parish of Sedgeford in the county of Norfolk divers lands and grounds, called whole-year lands, brecks, common fields, half-year or shack lands, commons and waste grounds And whereas there are certain rights of sheep-walk, shackage and common, over the said brecks, half-year or shack land, commons and waste grounds. And great part of the said whole-year lands, as well as the brecks, common fields, and half-year or shack lands, are inconveniently situated,” etc.

Or again 1804, c. 24 :

“Whereas there are in the parish of Waborne in the county of Norfolk divers lands and grounds called whole-year lands, common fields, doles, half-year or shack lands, commons and waste grounds.”

“Whereas the said common fields, doles, half-year lands, shack lands, commons and waste grounds, are subject to certain rights of sheep-walk, shackage and common, and great part of the said whole-year lands, common fields, and half-year or shack lands are inconveniently situated for the various owners and proprietors thereof.”

Other Norfolk acts mention doles, ings, carrs, and buscallys. Buscallys we may take to mean woods in which rights of common for fuel were practised. Dr. Murray's Dictionary gives us bushaile or buscayle, from Old French *boschaille*, Low Latin *boscalia*, shrubberies, thickets, etc. “Dole,” is

connected etymologically both with "deal" and with the word "run-dale," concerning which see below. The word is frequently found elsewhere, as in the "dolemeads" at Bristol and Bath, and usually means meadows, the ownership of which is intermixed in small parcels, which are commonable after hay harvest, but sometimes the word is used of arable land (see below). The Act for Earsham, Ditchingham and Hedenham (Norfolk, 1812, c. 17) has the sentence, "The said dole meadow lands lie intermixed and dispersed." The "ings" and "carrs" are best understood by the help of the old Ordnance Survey map for Norfolk. The carrs are the lowest, swampiest part of the common pastures which reach down to the rivers; the ings, while also low-lying, are separated from the rivers by the carrs, and intervene between the carrs and the tilled lands.

There remain the expressions whole-year lands, half-year or shack lands, and brecks, to interpret.

Half-year lands obviously means lands commonable for half the year, *i.e.*, after the crop has been carried. They are also "shack" lands, or lands on which right of "shackage" exists. "Shack" is connected with "shake," and right of shackage appears to be the right to carry off the gleanings after the crop has been carried and the fields are thrown open. It is, however, to be noticed that half-year or shack lands are mentioned as something distinct from common fields. The distinction is said to be that common rights on shack lands can be exercised only by the owners or occupiers of those lands. Shack lands may be termed common fields, but the term common field may be reserved for those fields over which cottagers or toft holders or others also possess rights of common.

"Brecks" are asserted by William Marshall ("Rural Economy of Norfolk," Vol. I., p. 376) to be "large new-made enclosures," but as is seen from the wording of the Acts quoted, they are enclosures still "subject to certain rights of shackage, sheepwalk, and common."¹ Lastly, what are "whole-year lands"?

¹ 1820, c. 29 (Blakeney, Wiverton and Glanford) mentions "whole-year lands, whole-year brecks, whole-year marshes." In this case, apparently, brecks are not commonable.

Since half-year lands are lands which for half the year are common, and for half the year are in individual ownership and use, one would argue that whole-year lands must be lands which are in individual ownership and use the whole year; for if they were common the whole year they would be termed simply "commons." We get further light by comparing the preambles of other Norfolk Acts. Some instead of whole-year lands mention every-year lands, others speak of "whole-year or every-year lands," while finally Icklingham in Suffolk (1813, c. 29) gives us "every year lands or Infields."

Now "infields" is a familiar expression in Scottish agriculture. Even in the Lothians, up to the middle of the eighteenth century the cultivated land was divided into infield and outfield. The outfield, like the outfield on the Yorkshire Wolds, only bore occasional crops, and was never manured, all the manure being reserved for the infield, which was made to bear a crop every year. In Haddington the customary course was: (1) pease; (2) wheat; (3) barley; (4) oats; and then the land was dunged and planted with pease again; and leases stipulated for "the preservation and regular dunging of the mucked land shotts."¹ Such lands might obviously be described as every-year lands, and since this method of cultivation implies that immediately one crop is carried preparation must be made for the next, and therefore is not easily consistent with common rights, so these lands are also "whole-year lands." It may be noted that the Norfolk preambles (as in the Sedgeford example, quoted above), while stating that the "whole-year lands," as well as the brecks, common fields and half-year lands are inconveniently situated, *i.e.*, are intermixed, by implication give us to understand that they are not subject to rights of shackage, sheep-walk, and common.

It is the more curious to find that Norfolk and the adjoining part of Suffolk followed a traditional method of cultivation in this respect similar to that of the East of Scotland, because there

¹ George Buchan Hepburn, "Agriculture of East Lothian," 1794, p. 49.

are so few traces of anything similar in the intervening counties. I find infields mentioned twice in Northumberland, once in Lincoln, whole-year lands once in Huntingdon. There is also mention of half-year lands in Yorkshire and Cambridgeshire. The Wessex custom of "hitching the fields," or "cropping the homeward or bettermost part of the common fields every year" is not the same thing, because there, as we saw in the case of Stratton and Grimstone, the extra crop was raised for common, not for individual, benefit. Battersea common fields were worked as every-year lands, and so are the Axholme fields to-day; but in these cases the custom was locally derived from some other form of cultivation; whereas in Norfolk and Suffolk the peculiar customs must have been indigenous and ancient.

One is also tempted to ask whether it is a coincidence that Norfolk farmers in the latter half of the eighteenth century, and Lothian farmers in the nineteenth, enjoyed and deserved an extremely high reputation for scientific, enterprising, and skilful agriculture. The ancient custom of raising crops every year from the same land must have necessitated the gradual accumulation of knowledge on the best ways of preventing exhaustion of the soil, by marling, manuring, deep ploughing, and various rotations of crops. When turnip culture was introduced into England, it was to Norfolk that the new idea was brought. There was no obstacle to growing turnips on the Norfolk whole-year lands, such as would have arisen if toft holders had the right to turn horses, cattle and sheep on to the lands at Lammas; and the intervention of a new crop which gave an opportunity for getting the land clean of weeds, and increased its fertility for grain crops, was a far more obvious boon there than on lands subject to a periodic fallow.

But to return to the typical Norfolk Enclosure Act preamble. We have only half explained the problem suggested by the four different names, each evidently with a distinct meaning, but all meaning arable land in which ownership is intermixed as in an ordinary common field, viz., whole-year lands, half-year lands or shack lands, brecks and common fields. The rest of the

explanation is, I think, to be looked for in the direction suggested by the prominence given to the statement, "They are subject to rights of sheep-walk." Elsewhere one finds a close connection between sheep and common fields. Thus we have seen that at Eakring certain common right owners make a speciality of pasturing sheep on the common fields. The Swedish traveller Kaln, whose account of his visit to England has recently been translated into English, observed the same thing on the open field parishes of Hertfordshire and Bedfordshire in the year 1748 (p. 302). But in 1793 where there were open chalky downs in open field parishes the right of pasturing sheep on the downs and of having the combined flock of the village folded over the arable in the common field was valued too highly by every occupier to be ceded to an individual speculator (Davies, "Wiltshire," pp. 8, 15, 61, 80). In these cases right of common for sheep has been democratically shared.

But this is not universal. The Enclosure Commissioners, in their thirty-eighth report (1883), record the application for an Enclosure Act for Hildersham, Cambridgeshire. In this parish the two *manor farms* had the right of turning their sheep every sixth year on to the stubbles of the other farms. Similarly, I am told by Major Barnard, of Cheltenham, that in the Cambridgeshire parish of Bartlow, where he was born, which was enclosed with Shudy Camps and Castle Camps in 1863, that the right of feeding sheep on the common fields belonged to the lord of the manor only. These Cambridgeshire parishes are close to the borders of Norfolk and Suffolk, and the following passage from Tusser's "Champion and Several" (date 1573) suggests the same rule as applying to Norfolk and the "champion" (*i.e.*, open field) part of Suffolk:—

In Norfolk behold the despair

Of tillage, too much to be born,
By drovers, from fair to fair,
And others, destroying the corn,
By custom, and covetous pates
By gaps and by opening of gates.

What speak I of commoners by
 With drawing all after a line ;
 So noying the corn as it lie,
 With cattle, with conies and swine,
 When thou hast bestowed thy cost
 Look half of the same to be lost.

The flocks of the lords of the soil
 Do yearly the winter corn wrong,
 The same in a maner they spoil
 With feeding so low and so long,
 And therefore that champion field
 Doth seldom good winter corn yield.

If it be urged that the two italicised lines are not necessarily to be read together, in view of the other topics touched on in the intermediate lines, the argument is not much affected, for Tusser shows no knowledge of any "champion" counties other than Leicestershire, Cambridgeshire, and Norfolk, and elsewhere in the poem he deals with the special evils afflicting the two former counties.

I may also refer to the Act, 25 Henry VIII. c. 13, to limit the number of sheep which may be possessed by a single owner, in which occurs the passage:—

X. Be it also further enacted by the authority aforesaid, That no manner of Person or Persons, of what Degree soever he or they be, being Lord or Lords, Owner or Owners, Farmer or Farmers, of or in any Liberty of Fold Courses within any Town, Tything, Village or Hamlet within any of the Counties of Norfolk or Suffolk, from and after the Feast of the Nativity of our Lord God next coming, shall take in farm, for term of years or otherwise, any Quillets of Lands or Pastures, that is to say, any number of Acres of Land or Pasture appertaining to any other Person or Persons, lying and being within the limit Extent or Precinct of the said Liberty of the said Fold Courses ; but that they shall permit and suffer the said Persons, having or being, for the time, Owner or Owners, Lessee or Lessees of the said Quillets, to manure and pasture the said Quillets ; and

also to suffer sheep of the said Owner or Owners, Farmer or Farmers of the said Quillets, after the Rate of the said Quillets, to go with the Flock of the Owner, Farmer or Occupier of the said Liberty or Liberties of the said Fold Courses, paying the customary charge for the same, after the Rate and Use of the Country, there commonly used, without any interruption therein to be made by the said Owner or Owners, Farmer or Farmers, or Occupiers of the said Liberties, upon pain of forfeiture for 3s. 4d. for each offence.

“XI. Provided . . . it shall not . . . be available to any tenant Owner or Occupier of any such Quillet or Quillets to claim, have or use hereafter any such pasture, or Feeding of his sheep, in or with any such Fold Courses, but only where the tenants, Owners and Occupiers of any such Quillets have had, or might have had heretofore of Right and Duty, or used to have Pasture and Feeding in the said Fold Courses, by reason of their tenures, and Occupations of the said Quillet and Quillets, and none otherwise; and where they have not used, nor ought to have any Sheep fed or kept within such Fold Courses, by reason of the said tenures, that the Owners or Occupiers of such Fold Courses may take such Quillets, lying within their Fold Courses, in Farm, agreeing with the Owners or Occupiers of the said Quillets for the same.”

It would appear from these clauses that there had been in still earlier times generally throughout Norfolk and Suffolk a right pertaining to the Lord of the Manor of feeding flocks of sheep over the whole manor, that this right, in the reign of Henry VIII. was frequently sold or leased under the denomination “A Liberty of Fold Courses”; secondly that the exercise of this right was apt to interfere with the cultivation of peasants’ holdings in the common fields; thirdly that it was customary for the sheep belonging to the peasants to be pastured and folded with the flock of the Lord of the Manor for a fixed customary fee.

There is yet another respect in which Norfolk agriculture shows a difference, but of degree, not kind, from other common-

field agriculture. Complete enclosure of common-field arable involves three processes—

(1) The laying together of scattered properties, and consequent abolition of intermixture of properties and holdings ;

(2) The abolition of common rights ;

(3) The hedging and ditching of the separate properties. This third process is the actual “enclosing” which gives its name to a series of processes which it completes.

But sometimes the hedging and ditching takes place independently of the other two processes, and strips of an acre, two or more acres, and even half-an-acre are enclosed in the middle of the common-fields, and, what is more remarkable, the little enclosed strips are sometimes the property of several individuals. In the collection of maps of open field parishes belonging to certain Oxford Colleges, published by Mr. J. L. G. Mowat, several such instances may be noticed.

Such enclosures were at first commonable ; but common rights were of course exercised over them with greater difficulty than over the open parts of the enclosed fields, a fact on which the above quoted opinion on the Barn farm at Elmstone Hardwicke incidentally throws some light. The maintenance of these common rights is a sort of test of the democratic vigour of the village, and it may be noticed that old enclosures subject to common rights were particularly numerous in Yorkshire.

Norfolk was remarkable for the extent to which actual hedging and ditching preceded legal enclosure. The Board of Agriculture reporter says, “for notwithstanding common rights for great cattle exist in all of them,¹ and even sheep-walk privileges in many, yet the natural industry of the people is such, that wherever a person can get four or five acres together, he plants a white-thorn hedge round it, and sets an oak at every rod distance, which is consented to by a kind of general courtesy from one neighbour to another.”²

Two Acts incidentally show to what an extent such hedges

¹ *I.e.*, of the enclosures he is going to describe.

² Nathaniel Kent, “Norfolk,” p. 22.

enclosed lands belonging to two or more proprietors. One Norfolk Act has the provision, "All enclosures where two or more proprietors are connected and where the property is not separated by a hedge or ditch shall be deemed to be Common Field." The same clause differently expressed occurs in the Act for Ormesby and Scratby (1842, c. 9): "All old enclosures within the said parishes in which there are lands belonging to different proprietors, shall be deemed to be open Fields."

A brief account of a surviving Norfolk open field parish is given in Appendix E., p. 331.

CHAPTER IX.

13 GEO. III. c. 81.

ONE of the most striking and interesting features of the open field village life is the existence of a self-governing constitution for the settlement of disputes, and the most profitable use of the village lands—the annual meetings of farmers and common-right owners; the institution of field reeves and field juries; the division among commoners of the profits of the common property. One cannot but look upon this as the survival of an ancient village communal life, which must have been much stronger and more vigorous in earlier days, when each village was more of a self-contained and isolated economic unit; and particularly while the co-operative ploughing persisted, from which the intermixture of lands in common field arable is admitted to have originated. Even in its degenerate state, when co-operative ploughing has been extinct for generations, the open field parish involves a certain partnership among the cultivators, necessitating some recognised rules, mutual consultation, and organised combination: how much more binding the necessity must have been in the Middle Ages? Hence from the very necessity of the case, there must have been a bond between the village workers, such as is conveyed by the words “village community,” which probably preceded, and underlay as a foundation, the better known manorial and parochial institutions, the manorial organisation arising from the contact between the village community and the Central Government, or outside enemies, the parochial from its contact with the Church.

But while these features of common-field management in general are survivals of “the village community,” it is possible *in any particular village* that such institutions and customs were the creation of the legislature since the latter part of the

eighteenth century. For in the year 1773 a noteworthy Act was passed for the better regulation of the culture of common arable fields. It enacts that "where there are open or common field lands, all the Tillage or Arable lands lying in the said open or Common Fields, shall be ordered, fenced, cultivated or improved, in such manner as three-fourths in number and value of the occupiers shall agree, with consent of the owner and tithe-owner."

Such agreements were to be binding for six years, or two *rounds*, "according to the ancient and established course of each parish or place"; i.e., presumably, in a parish where the ancient customary course had been one crop and a fallow, the agreement was binding for four years; where it had been three crops and a fallow, for eight years. Further, every year between the 21st and 24th of May a field reeve or field reeves were to be elected. These field reeves, acting under the instructions of a three-fourths majority in number and value, might delay the opening of the common fields, might give permission for any balks, slades or meers (those words are synonyms) to be ploughed up, an equivalent piece of land being laid down in common, and boundary stones being put down instead. Since this Act was designed in the interest of better cultivation, and for the advantage of the proprietors and large occupiers, special provision is made that if the cottagers owning common rights feel themselves prejudiced, they may claim to have a separate piece of land set out as a common for them.

The effect of the Act was to enable the common-field system to be adjusted to the new agriculture of the eighteenth century, which was marked by the introduction of turnips, artificial grasses, and the abandonment of frequent fallowing. A precise account of the adoption of a scheme under the Act is given us by the prime mover.

In the township of Hunmanby, in the East Riding of Yorkshire, the cultivators had fallen into one of the besetting temptations to which "champion" farmers were liable. They had gradually extended the arable fields at the expense of the common pasture, till the manure produced by the latter was

insufficient for the needs of the former, and the land was losing its fertility. Isaac Leatham got his brother farmers to agree to abandon the old (three-year) course of husbandry, and to substitute the following six-year course :—

1. Turnips, hoed, and fed off with sheep.
2. Barley with grass seed.
3. Grass.
4. Grass.
5. Wheat.
6. Oats or peas.

The grass seed sown with the barley was bought in common, and paid for proportionately. From the time the barley was carried until it was time to plough for the wheat crop, one gathers that the grass, which had been sown with the barley, was being fed with sheep; therefore, at any particular time after the course was established, half the common field area was feeding sheep, or growing turnips for sheep, and half was growing grain or pulse. The sheep flock was managed in common; each occupier was allowed to contribute sheep to it in proportion to his holding; the whole was under the care of two shepherds, who folded the sheep nightly upon different strips of land in succession, so that all occupiers received equal benefit. Field reeves were appointed.

“Thus,” says Isaac Leatham, “an open field is enjoyed in as beneficial a manner as if it were enclosed . . . two persons are fully sufficient to attend the sheep-stock, instead of many . . . the precarious rearing of fences is avoided, and the immense expense of continually repairing them saved.”¹

I take it that Isaac Leatham, who, by the way, was a strong advocate of enclosure in general, meant that the open field was, *on the whole*, enjoyed in as beneficial a manner as if it were enclosed, because there still remained the great disadvantage that each occupier had his lands in widely scattered strips, and had to waste much time and labour in cultivating them; cross-ploughing, which might, or might not have been desirable, was

¹ Isaac Leatham, “East Riding,” p. 46.

any way impossible; the village lands had to be treated as one whole, so no enterprising and original man was able to experiment with new ideas, nor could any further improvement be adopted without the consent of a three-fourths majority; and, perhaps, the keeping of sheep in a common flock put obstacles in the way of improving the breed.

I may add that an Act for the enclosure of Hunmanby was passed in the year 1800, so that Isaac Leatham's course was abandoned just seven years after he wrote about it so triumphantly.

The Act of 1773, therefore, was, perhaps, not a brilliant success in Hunmanby; perhaps, on the other hand, improved agriculture excited an appetite for further improvement, and one novelty having been accepted, the stiff conservatism which might have postponed enclosure, was broken down. But, as a glance at the map for the East Riding will show, the whole countryside was subject to a rage for enclosure, and the famine prices for grain of 1796, doomed to recur again in 1800-1, in 1812, and 1817, were acting as a powerful solvent to all old agricultural customs.

It is quite obvious that the Act of 1773 was an endeavour to select out of the customs and traditions prevailing in different villages those which were most in harmony with advanced agriculture, to further amend these, and to make them universal.

So far as I know, Hunmanby is the only place where it has been recorded as having been put into execution, and it has been doubted whether it was not practically a dead letter. My own impression is that the distribution of the "sicks" at Laxton was consciously arranged in accordance with the provisions of the Act, that originally the method of choosing the fallow crops in Castor and Ailesworth was an application of it, and also the six years' course used for part of the fields of Barrowden and Luffenham, but I can bring no evidence to support this view. If, however, it is correct, the Act may have been of considerable use to many other parishes also by clearly defining methods of procedure which otherwise would be determined by custom only.

CHAPTER X.

ENCLOSURE AND DEPOPULATION.

THE very word "enclosure" to a historical student suggests "depopulation." The two words are almost treated as synonyms in Acts of Parliament, tracts, and official documents of the sixteenth century. In the seventeenth century we find the proverbs, "Horn and thorn shall make England forlorn," "Inclosures make fat beasts and lean poor people," while the superstition grew up that inclosed land was cursed, and must within three generations pass away from the families of "these madded and irreligious depopulators," these "dispeoplers of towns, ruiners of commonwealths, occasioners of beggary . . . cruell inclosiers."

After the Restoration, the literary attack on enclosure becomes more feeble, the defence more powerful. W. Wales in 1781, the Rev. J. Howlett in 1786, published statistics to show that enclosure had the effect of increasing the population, the latter tract being widely quoted; there ceased to be any opposition from the Central Government to enclosure, and private Acts were passed in continually increasing numbers; finally the one practical measure carried through by the Board of Agriculture was the General Enclosure Act of 1801, to simplify and cheapen Parliamentary proceedings. Dr. Cunningham sums up the case as follows: "He (Joseph Massie) was aware that enclosing had meant rural depopulation in the sixteenth century, and he too hastily assumed that the enclosing which had been proceeding in the eighteenth century was attended with similar results; but the conditions of the time were entirely changed. Despite the reiterated allegation,¹ it is impossible to believe that enclosing in the eighteenth century implied either more pasture

¹ By the opponents of enclosure.

farming or less employment for labour. The prohibition of export kept down the price of wool; the bounty on exportation gave direct encouragement to corn-growing; the improved agriculture gave more employment to labour than the old."¹

Taken in one sense, I must admit the substantial accuracy of this opinion. On the other hand I am disposed to maintain the general accuracy of the statements with regard to depopulation made by the opponents of enclosure, (a) provided these statements are understood in the sense in which they are meant, and (b) statements only with regard to the part of the country the writer is familiar with are regarded, and his inferences with regard to other parts are neglected.

For it must be remembered that side by side with the movement for the enclosure of arable fields, there was going on a movement for the enclosure of wastes. From Appendix A. it will be seen that 577 Acts for enclosing wastes and common pastures were passed between 1702 and 1802, and over 800,000 acres were so added to the cultivated area of England and Wales. There were besides enclosures occasionally on a large scale by landed proprietors of wastes on which either common rights were not exercised, or on which they were too feebly maintained to necessitate an Act. The Board of Agriculture report for Notts records that 10,666 acres had recently been so enclosed from Sherwood Forest alone.² Lastly there was the continual pushing forward of cultivation by farmers, squatters, etc. It is impossible to do more than form a vague guess as to the quantity of land so enclosed, but reasons will be given later for the belief that it was far greater than the area of commons and waste enclosed by Act of Parliament.

Now the opponents of enclosure of the sixteenth, seventeenth and eighteenth centuries almost without exception opposed simply the enclosure of arable common fields; they usually expressly approve the enclosure of waste, as increasing the means of subsistence of the people. The advocates of enclosure on the other hand are equally concerned in advocating both

¹ "Growth of English Industry and Commerce," Vol. II., p. 384 (1892).

² Robert Lowe, "Nottingham," Appendix.

kinds of enclosure. Hence we have statements to the effect that the enclosure of arable fields in the "champion" districts of England (*i.e.*, the part much shaded on the map) caused rural depopulation, met by statistics and arguments to prove that all kinds of enclosure proceeding over all parts of England and Wales, on the whole, tended to increase population, urban and rural. Through looseness of wording on both sides, the controversialists seem to be contradicting one another; whereas, in reality, both might equally be right.

At the present day this particular issue is dead, though a similar question, the question whether by means of the modern representative of the open field, *viz.*, the allotment field, and modern representative of the ancient co-operative ploughing, *viz.*, co-operative purchase of machines, manures and seeds, borrowing of capital, sale of produce, and perhaps co-operative stockbreeding, the decay of the agricultural population can be arrested, is a living issue. Nor is there any period of the nineteenth century in which any serious rural depopulation as a result of enclosure, and consequent laying down in pasture, of common fields, could be asserted. Since Free Trade began to seriously affect the prices of British grain—and that was not for a good many years after 1846—the common fields have been too few, and the other forces tending towards rural depopulation too great, for this particular force to be felt. And if it were felt, no one would seriously urge that the hardly pressed farmer should be compelled to cultivate the land in a manner wasteful of labour, in order that more labourers might be employed. In the earlier part of the nineteenth century war, protection and a rapidly growing wealth and population so effectively encouraged tillage that attempted prohibition of conversion of arable to grass would have been superfluous.

Yet much, I think, can be learnt on the historical question from the present aspect of the country, even by anyone who merely travels by express train through the Midlands. Having spent a day in traversing the length and breadth of the great fields of Castor and Ailesworth, yellow with wheat and barley or recently cut stubble, I went straight through the county of

Northamptonshire, seeing on either side scarcely anything but permanent pasture. From Northampton to Leicester was the same thing; again from Leicester to Uppingham. Just beyond Uppingham the cornfields become far more extensive; what were the Rutlandshire common fields till 1881 are still mainly under tillage. All this country of permanent pasture was mainly enclosed during the eighteenth century. Very frequently one can see on heavy land the old ridges piled up in the middle, ending in the middle of one field, crossing hedges, and showing plainly that very little, if any, ploughing has been done since the enclosure was effected.¹ The impression made on my mind by this apparent confirmation of all that the denouncers of "cruell Inclosiers" alleged was a very powerful one.

Before examining the evidence for and against rural depopulation in particular parts of England as the result of the extinction of common fields, it is well to consider the *a priori* arguments put forward by Dr. Cunningham.

It is urged, in the first place, that owing to the relatively high price of corn and low price of wool, there was no motive for lay-down arable as pasture. Dr. Cunningham seems to ignore the fact that sheep and cattle produce mutton, beef, milk, butter, cheese, and hides, as well as wool, and it is by the profit to be derived from all of these products together, and not from any one of them, that the question of laying down in pasture will be determined. That laying down arable in pasture was profitable is indicated by the surprise Arthur Young expressed in 1768 that landlords did not enclose, and put the land to grass, on passing through Bedfordshire,² and by Adam Smith's reference in "The Wealth of Nations" to the exceptional rent commanded by enclosed pasture.³ We have, further, the clear statement of the Board of Agriculture: "Whereas the price of corn from 1760 to 1794 was almost stationary, the products of grass land

¹ Arthur Young ("Eastern Tour," Vol. I., p. 54) noticed this in 1771 in the great pasture closes of Northamptonshire: "All this fine grass on so excellent a soil lies all in the broad ridge and furrow."

² "Northern Tour," 2nd. ed., p. 56.

³ McCulloch's ed., p. 69.

have risen greatly throughout nearly the whole of that period.”¹ William Pitt, again, in a pamphlet published by the Board in 1812 on the “Food Produced from Arable and Grass Land,” says that through the “increased luxury of the times more beef and mutton and butter are used than formerly, even by equal numbers, and consequently more inducement to throw all the best corn to grass” (p. 35). William Culley adds in a footnote that “In the Northern Counties more rent per acre is given for ploughing than for grazing farms . . . more rent is given for grazing than for arable farms in the Southern Counties.” If this was so when famine prices were paid for wheat, how much more in normal times?

It is said, in the second place, that “the new agriculture gave more employment to labour than the old.” No doubt such an improvement as the substitution of well-hoed turnips for a fallow, the sowing of grass seeds with barley so as to produce a second crop, or feed for cattle after the barley was carried, both gave increased employment to labour, and tended to increased prosperity for the labouring as well as other classes. But these changes, as we have seen, and as Dr. Cunningham himself points out, might take place independently of enclosure, and might not follow if enclosure did take place. Whether they usually did follow upon enclosure is a question that has to be settled by an appeal to contemporary evidence. In taking this evidence reference must always be carefully made to the *time* and the *place*.

The Board of Agriculture’s General Report on Enclosures (1808) quotes with approval an anonymous pamphlet published in 1772: “The advantages and disadvantages of enclosing waste lands and common fields,” by “A Country Gentleman.” This tract appears to be a very able and impartial attempt to estimate the effects of enclosure on all the classes interested. The way in which Acts then originated, and the manner in which proposals were received, is described thus:—

“The landowner, seeing the great increase of rent made by his neighbour, conceives a desire of following his example; the

¹ “General Report on Enclosures,” p. 41.

village is alarmed ; the great farmer dreads an increase of rent, and being constrained to a system of agriculture which neither his experience nor his inclination tempt him into ; the small farmer, that his farm will be taken from him and consolidated with the larger ; the cottager not only expects to lose his commons, but the inheritable consequence of the diminution of labour, the being obliged to quit his native place in search of work ; the inhabitants of the larger towns, a scarcity of provisions ; and the Kingdom in general, the loss of inhabitants " (p. 1).

The general conclusion seems to be that all these anticipations and fears, with the exception of the last two—a scarcity of provisions for large towns, and a general loss of inhabitants for the kingdom, are well founded. With regard to the landowner and tithe-owner :—

"There can be no dispute that it is the landowners' interest to promote inclosures ; but I verily believe, the impropietor of tithes reaps the greatest proportional benefit, whilst the small freeholder, from his expenses increasing inversely to the smallness of his allotment, undoubtedly receives the least " (p. 25).¹

Of the small farmer :—"Indeed I doubt it is too true, he must of necessity give over farming, and betake himself to labour for the support of his family " (p. 31).

With regard to the increase or diminution of employment for labourers, he gives the following statistical table, an estimate based on his observation :—

1,000 Acres of	Before En- closure gives Employment to	After En- closure gives Employment to
A Rich Arable Land	20 families	5 families
B Inferior Arable	20 "	16 $\frac{1}{4}$ "
C Stinted Common Pastures	$\frac{1}{2}$ a family	5 "
D Heaths, Wastes, etc.	$\frac{1}{2}$ "	16 $\frac{1}{4}$ "

¹ This is badly expressed. He refers to the fact that a small allotment is more expensive to fence, proportionally to its size, than a large one.

It will be seen that his observation is that enclosed arable employs $16\frac{1}{4}$ families per 1000 acres, open field arable 20 families per 1000 acres; that common pastures, heaths, wastes, etc., employ only 1 family per 2000 acres; but enclosed pasture employs 5 families per 1000 acres. It will also be seen that his observation is that after enclosure rich land becomes pasture, inferior land arable.¹

With regard to the effect of this on population, he names in one passage² Northamptonshire, Leicestershire and Lincolnshire perhaps, as containing "an infinitely greater proportion of common fields, while Northumberland, Westmoreland and Yorkshire exceed in moors, heaths and commons," and in another he mentions Oxfordshire, Buckingham, Northamptonshire and part of Leicester as counties in which rich arable land would be the main subject of an Enclosure Act. A typical parish in this district might include 1000 acres of rich arable land, 500 acres of inferior arable, 500 acres of stinted common, with no heath or waste. Before enclosure it would provide employment for $30\frac{1}{4}$ labouring families according to the table, after enclosure to $15\frac{1}{2}$. If eight such parishes were enclosed, 117 families would be sent adrift—families of poor and ignorant labourers, looking for new homes under all the disabilities and difficulties springing from Acts of Settlement, and a Poor Law administration based on the assumption that those who wander from their native place are all that is implied in the words "vagrants" and "vagabonds." Not eight, but a hundred and twenty-six Acts for enclosing common fields were passed for the four counties he names in the ten years 1762—1772, immediately

¹ This is in harmony with all other eighteenth century information with regard to the Midland Counties. As one example we may cite the Vale of Belvoir, the north-eastern corner of Leicestershire. Here, in consequence of enclosure, "all the richest land in the vale, formerly under tillage, was laid down in grass, but the skirtings of the Vale, formerly sheep-walk, were brought into tillage." The landlord, the Duke of Rutland, forbade any land worth more than a guinea per acre to be tilled. The enclosure of the twelve parishes in the Vale took place between 1766 and 1792. (William Pitt, "Agriculture of Leicestershire," 1809.)

² Page 43.

preceding the publication of this pamphlet. Assuming the accuracy of the "Country Gentleman's" statement, this would mean that some 1800 odd families, comprising about 9000 individuals, would, in consequence of enclosure, be sent adrift in that short period in the four counties. The quotations given below from three other authors, indicate that even this was an under-statement. The process continued without intermission for many years afterwards.

A specially interesting tract, published in 1786, entitled "Thoughts on Inclosures, by a Country Farmer," gives a detailed account of the results of one case of enclosure. The locality is not named, but it is pretty clear that it was within this Midland country in which enclosure was attended by the conversion of arable to pasture.

On the general question the writer says:—"To obtain an Act of Parliament to inclose a common field, two witnesses are produced, to swear that the lands thereof, in their present state, are not worth occupying, though at the same time they are lands of the best soil in the kingdom, and produce corn in the greatest abundance, and of the best quality. And by inclosing such lands, they are generally prevented from producing any corn at all, as the landowner converts twenty small farms into about four large ones, and at the same time the tenants of those large farms are tied down in their leases not to plough any of the premises, so lett to farm,¹ by which means of several hundred villages, that forty years ago contained between four and five hundred inhabitants, very few will now be found to exceed eighty, and some not half that number; nay some contain only one poor decrepid man or woman, housed by the occupiers of lands who live in another parish, to prevent them being obliged to pay towards the support of the poor who live in the next parish" (p. 2).

The profit of enclosing, he maintains, was dependent upon simultaneous conversion into pasture, for "In some places the lands inclosed do not answer the ends of pasturage, and in

¹ See note ¹ on next page.

that case tillage is still to be pursued; because the rents cannot be raised so high as in respect of pasturage, therefore the landowner has not the advantage as in case the land turns out fit for pasturage, and is oftener the loser by that proceeding than the gainer."¹

The particular enclosure he cites is that of a parish enclosed about forty years previously. Before enclosure it contained eighty-two houses, of which twenty were small farms and forty-two were cottages with common rights. It had 1800 acres of common field arable, 200 acres of rich common cow pasture, and 200 acres of meadow, commonable after hay harvest. The common pasture fed two hundred milch cows and sixty dry ones till hay harvest, at which time they were turned into the meadows, and their place taken by about one hundred horses. Twelve hundred sheep were fed on the stubbles.

The gross produce of the parish before enclosure he values as follows:—

	£	s.	d.
1,100 quarters of wheat at 28s. per quarter	1,540	0	0
1,200 quarters of barley at 16s. per quarter	960	0	0
900 quarters of beans at 15s. per quarter	675	0	0
250 todods of wool at 16s. per todd	... 200	0	0
600 lambs at 10s. each	... 300	0	0
5,000 lbs. of cheese at 1½d. per lb.	... 31	5	0
6,000 lbs. of butter at 5d. per lb.	... 125	0	0
100 calves at 20s. each	... 100	0	0
150 pigs at 12s. each	... 90	0	0
Poultry and eggs...	... 80	0	0
	<u>£4,101</u>	<u>5</u>	<u>0</u>

The quantities estimated are eminently reasonable, and in harmony with other statements available with regard to the produce of the common fields of the Midlands; the prices also are clearly not over-stated.

¹ Arthur Young ("Eastern Tour," 1771, p. 96) remarks that in Leicestershire "Landlords in general will not allow an inch to be ploughed on grazing farms."

As the result of enclosure the twenty farms were consolidated into four, the whole area was devoted to grazing, sixty cottages were pulled down or otherwise disappeared, and the necessary work was done by four herds (one for each farm) at £25 a year each, board included, and eight maidservants at £18 a year each, board included.

The gross produce of the parish after enclosure was:—

					£	s.	d.
Fat beasts	...	...	...	...	960	0	0
Sheep and lambs	...	...	...	...	760	0	0
Calves	...	...	...	...	165	0	0
Wool	...	...	...	...	235	0	0
Butter	...	...	...	...	190	0	0
Cheese	...	...	...	...	100	0	0
Horses	...	...	...	...	250	0	0
					£2,660		
					0		
					0		

But while the gross produce was thus reduced by about one-third, the gross rent was raised from £1187 17s. 0d. to £1801 12s. 2d.¹

Though unfortunately the parish is not identified, and the witness is anonymous, the whole statement appears to have been carefully and exactly made. In this case we have no fewer than sixty families of small farmers or agricultural labourers expelled from their homes in a single parish of about 2300 acres.

An even more striking example of local depopulation caused by enclosure is supplied by the Rev. John Howlett, one of the strongest advocates of enclosure. He quotes from a private correspondent: "As to Inclosure, I can mention two villages in this County (Leicestershire) within two miles of each other, Wistow and Foston,² which formerly contained thirty-four or

¹ According to the "Country Gentleman's" calculations, the gross produce of the 1800 acres of common field and 200 acres of common pasture would be before enclosure £4419 8s., and after, £3000, which agrees very closely with the "Country Farmer's" statement, the absolute amounts being greater, the ratio between them practically identical.

² Each of these was enclosed without an Act of Parliament.

thirty-five dwellings, but by enclosure Foston is reduced to three habitations: the parsonage house accommodates one family, and the two other buildings are occupied by shepherds, who manage the stock for their different renters, as the whole of the parish belongs to one person. And as to Wistow, the thirty-four mansions have vanished in a very few years, and no dwelling remains but the late Sir Charles Halford's hall house, who owns the lordship; and these are called improvements, for double or treble rents ensue." ("Enclosures and Depopulation," p. 12.)

What became of these farmers and labourers? The "Country Farmer" says: "Many of the small farmers who have been deprived of their livelihood have sold their stock-in-trade and have raised from £50 to £100, with which they have procured themselves, their families, and money, a passage to America."

John Wedge, the Board of Agriculture reporter for Warwick, says seven years later: "About forty years ago the southern and eastern parts of this county consisted mostly of open fields. There are still about 50,000 acres of open field land, which in a few years will probably all be inclosed. . . . These lands being now grazed want much fewer hands to manage them than they did in the former open state. Upon all enclosures of open fields the farms have generally been made much larger; from these causes the hardy yeomanry of country villages have been driven for employment to Birmingham, Coventry, and other manufacturing towns."¹ Such information, given by the representative of an enclosure-advocating corporation, circulated among the members for correction before final adoption, is unimpeachable evidence for the particular time and place.

The rising industries of Birmingham and other Midland towns found employment, no doubt, for many of the exiles from the villages. On the whole, the ruling opinion seems to have found all this very satisfactory. The gross produce of food by these Midland parishes might be diminished on enclosure, but the net produce, as was shown by the increase of rent, certainly

increased, and an abundant supply of labour was furnished for those metal working industries which were of the greatest importance in times of war.¹ When we think of the horrible sanitary conditions of English towns during the eighteenth century, of Fielding's description of the London lodging-houses, of Colquhoun's attempts at a statistical account of London thieves, of Hogarth's pictures, which interpret for us the meaning of the terrible fact that right through the eighteenth century the deaths "within the bills of mortality" regularly far exceeded the births, we feel that there was another side to the shield, though possibly the sanitary and social condition of Midland towns was less terrible than that of London.

The connection between enclosure of common fields and rising poor rates in the eighteenth century is illustrated repeatedly in Eden's "Condition of the Poor."

In Buckinghamshire we find the two neighbouring parishes of Maids Morton and Winslow. The former contained 30 acres of old enclosure, 60 to 70 acres of commons, and the rest of the parish, about 800 acres, was common field. The poor-rates in the years 1792 to 1795 were 3*s.* 6*d.*, 3*s.*, 3*s.*, 3*s.* 6*d.* There were "several roundsmen." Wages were nominally 1*s.* to 1*s.* 2*d.* per day, but piecework was general, and 1*s.* 3*d.* to 1*s.* 6*d.* was generally earned. The rent of farms varied from £17 to £90 per farm, and from 18*s.* to 20*s.* per acre.

Winslow contained 1400 acres, and was entirely enclosed in 1744 and 1766. Only 200 acres remained arable. The farms varied from £60 to £400 per annum each, the wages were 6*s.* to 7*s.* per week, "most of the labourers are on rounds," and the poor rates from 1792 to 1795 were 5*s.* 8*d.*, 4*s.*, 5*s.*, and 6*s.* "The rise of the Rates is chiefly ascribed to the Enclosure of common fields; which it is said has lessened the number of farms, and from the conversion of arable into pasture, has much reduced the demand for labourers. An old man of the parish says, before the enclosures took place, land did not let for 10*s.* per acre." (Vol. II., pp. 27—33.)

¹ 1756—1763, 1775—1784, 1792—1815 were times of war.

In judging the rise of poor rate, it must not be forgotten that where the rent rises at the same time as the nominal rate, the sum of money actually raised for Poor Law purposes is increased in a greater ratio than the nominal poor rate. If, for example, by enclosure the rental of a parish is increased 50 per cent., but the poor rate doubled, the yield of the poor rate is increased threefold. And if a considerable number of labourers are driven elsewhere, the amount of destitution produced by the change is far greater even than that indicated by a threefold increase in the amount of relief given.

The latter side of the process is illustrated in the case of Deddington in Oxfordshire. Here, "the high rates in this parish are ascribed to the common field of which the land principally consists; whereas the neighbouring parishes have been enclosed many years, and many small farms in them have been consolidated; so that many small farmers with little capitals have been obliged, either to turn labourers or to procure small farms in Deddington, or other parishes that possess common fields. Besides this, the neighbouring parishes are, many of them, possessed by a few individuals, who are cautious in permitting new comers to obtain a settlement." (Vol. II., p. 891.)

In Leicestershire the complaint is naturally more loud and general. In the account of Kibworth Beauchamp we read as follows:—

"No account of the Rates in any of the divisions, previous to the enclosure of the common fields, can be obtained; but it is said that they were not one-third of what they are at present; and the people attribute the rise to the enclosures; for they say 'That before the fields were enclosed, they were solely applied to the production of corn; that the poor had then plenty of employment in weeding, reaping, threshing, etc., and could also collect a great quantity of corn by gleaning; but that the fields being now in pasturage, the farmers have little occasion for labourers, and the poor being thereby thrown out of employment, must of course be employed by the parish.' There is some truth in these observations: *one-third or perhaps one-fourth* of the number of hands which were required twenty

years ago, would now be sufficient, according to the present system of agriculture, to perform all the farming work of the parish."

He adds that if it were not for the fact that many labourers were getting employment in canal cutting, the rates would be much higher still, and "the tradesmen, small farmers, and labourers are very loud in their complaints against those whom they call monopolising farmers and graziers, an evil which, they say, increases every year." (Vol. II., p. 383.)

In Northamptonshire we find the case of Brixworth, enclosed in 1780, a parish of 3300 acres. Before enclosure it consisted almost entirely of common fields. At the time of Eden's writing, sixteen years later, only one-third remained arable. The expenditure on the poor in 1776, before the enclosure, was £121 6s., in the six years 1787 to 1792 it averaged £325 (Vol. II., p. 529). Again, with regard to local urban opinion, he notes that "the lands round Kettering are chiefly open field: they produce rich crops of corn. The people of the town seem averse to enclosures, which they think will raise the price of provisions, from these lands being all turned to pasture, when inclosed, as was the case in Leicestershire, which was a great corn country, and is now, almost entirely, converted into pasture."

Arthur Young, a little more than twenty years previously (in "Political Arithmetic," published in 1774), while arguing in favour of enclosure on the depopulation count, makes an admission against it with regard to pauperism. "Very many of the labouring poor have become chargeable to their parishes, but this has nothing to do with depopulation; on the contrary, the constantly seeing such vast sums distributed in this way, must be an inducement to marriage among all the idle poor—and certainly has proved so." (Pp. 75, 76.)

As a general rule it may be said that where after enclosure pasturage was increased at the expense of tillage, rural depopulation resulted; where the amount of land under tillage was increased the rural population increased. Further, that enclosure in the northern and western parts of England in the seventeenth and eighteenth centuries increased the area

under tillage; that the balance between the production of bread and meat for the whole country, so disturbed, was maintained by the conversion into pasture, on enclosure, of much of the "champion" corn growing land, particularly in those midland counties nearest to the northern and western ones in which the complementary change was taking place. By means of the Enclosure Acts, interpreted by the light of the above statements, we can trace these two compensating movements through the eighteenth century.

The following passage in Arthur Young's "Political Arithmetic," published in 1774, at the time, that is, when he was an eager advocate not only of enclosure of all sorts, but also of the engrossing of farms and the raising of rents, sums up the two movements:—

"The fact is this: in the central counties of the kingdom, particularly Northamptonshire, Leicestershire, and parts of Warwick, Huntingdonshire, and Buckinghamshire, there have been within thirty years large tracts of the open field arable under that vile course, 1. fallow, 2. wheat, 3. spring corn, inclosed and laid down to grass, being much more suited to the wetness of the soil than corn." Here he admits local depopulation takes place, though he claims that a greater *net* produce is, as the result of enclosure, supplied by such districts to the rest of the kingdom. But then, he asks with regard to the opponents of such enclosure, "What will they say to the inclosures in *Norfolk, Suffolk, Nottinghamshire, Derbyshire, Lincolnshire, Yorkshire* and all the northern counties? What say they to the sands of *Norfolk, Suffolk and Nottinghamshire*, which yield corn and mutton from *the force of INCLOSURE alone*? What say they to the Wolds of *York and Lincoln*, which from barren heaths at 1s. per acre, are *by INCLOSURE alone* rendered profitable farms? Ask *Sir Cecil Wray* if without Inclosure he could advance his heaths by sainfoine from 1s. to 20s. an acre:—What say they to the vast tracts in the peak of Derby which *by INCLOSURE alone* are changed from black regions of ling to fertile fields covered with cattle? What say they to the improvements of moors in the northern counties, where

INCLOSURES alone have made these countries smile with culture which before were black as night ? ”

He then proceeds to ridicule the view of his opponents, that the enclosure of waste, though desirable in itself, should as far as possible be so conducted as to create small farms and small properties, a view with which in later years, and after his tour in France, he very much sympathised. Into the merits of this controversy we need not go; what we have to note here is Arthur Young's evidence to the fact that from about 1744 to 1774 there was simultaneously proceeding a rapid enclosure of waste in Norfolk, Suffolk, Nottinghamshire, Derbyshire, Yorkshire, and Lincolnshire and the northern counties, by which the acreage under tillage was vastly increased, and a compensating enclosure of arable common fields in Northamptonshire, Leicestershire, Warwickshire, Huntingdonshire and Buckinghamshire, involving the conversion of arable to pasture, of small farms into much larger ones, and of the peasantry into urban labourers.

It only remains to be added that the former movement, if it was on at all as great a scale as Arthur Young gives us to understand (and I don't see why one should doubt this) must have proceeded largely, if not mainly, without the intervention of Parliament. This is in the first place antecedently probable. Secondly, whereas between 1727 and 1774 there were 273 common field parishes enclosed by Acts of Parliament in the five counties of Northamptonshire, Leicestershire, Warwick, Huntingdonshire and Buckinghamshire, the commons, fens, moors, etc., attached to only 109 parishes in Norfolk, Suffolk, Nottinghamshire, Derbyshire, Lincolnshire, Yorkshire, Durham and Northumberland were so enclosed. Unless the area of about 100,000 acres thus enclosed in these 109 parishes was merely a fraction of the total area of waste enclosed by all sorts of methods in this latter group of counties, Arthur Young was misleading his readers, for he certainly intends to give the impression that the enclosure of arable fields in the Midlands was on a much smaller scale than the reclamation of heaths, moors and fens in the northern and eastern counties. Thirdly,

with regard to Norfolk, Arthur Young specifies enclosure without Acts of Parliament as one of the causes of the great agricultural improvement in parts of Norfolk ("Eastern Tour," 1771, Vol. II., p. 150):—"From forty to sixty years ago, all the Northern and Western and a great part of the Eastern tracts of the country were sheep-walks, let so low as from 6*d.* to 1*s.* 6*d.* and 2*s.* an acre. Much of it was in this condition only thirty years ago. The great improvements have been made by reason of the following circumstances:—(1) By inclosing without assistance of Parliament."

Six other reasons follow, then the remark: "Parliamentary enclosures are scarcely ever so complete and general as in Norfolk," *i.e.*, as the enclosures without the assistance of Parliament in Norfolk. I have only been able to find eleven Acts of Enclosure for Norfolk before 1771; seven of these were for the enclosure of common field parishes, and four for the enclosure of waste. In other words, the Parliamentary enclosure of these sheep-walks at the time when Arthur Young wrote had proceeded to a merely trifling extent.

We have, then, by Arthur Young's confession, in the five counties of Northampton, Leicester, Warwick, Huntingdon, and Buckingham enclosure admittedly accompanied by decay of tillage and rural depopulation. From "A Country Gentleman's" list we can add Oxfordshire and parts of Lincolnshire. That the same prevailing economic motive operated in Bedfordshire can be shown from Arthur Young's "Tour through the North of England." The country in June, 1768, from St. Neots to Kimbolton was in general open—"the open fields let at 7*s.* and 7*s.* 6*d.* per acre, and the *inclosed pastures* about 17*s.* Hence we find a profit of 10*s.* an acre by *inclosing and laying to grass*." He might here ask, as he does with regard to the district in Buckinghamshire between Aylesbury and Buckingham, which he found in 1771 in the condition of open field arable, under a course of fallow, wheat, beans, fallow, barley, beans. "As to the landlords, what in the name of wonder can be the reason of their not inclosing! All this vale would make as fine meadows as any in the world."

As for Gloucestershire, William Marshall ("Rural Economy of Gloucestershire," 1789, p. 21), estimates the rents in the Vale of Evesham at 10s. to 15s. per acre for common field arable, 10s. to 20s. per acre for enclosed arable, and 20s. to 50s. per acre for enclosed pasture. Here again there can be no doubt that enclosure implied laying down at least all the good land in grass.

A Select Committee of the House of Commons appointed to consider the high prices of food in December, 1800 (1800 and 1801 being famine years), made enquiry, by the help of the parish clergy, into the increase or decrease of land under different crops, and of cattle, sheep, and pigs in the districts which had been enclosed in the previous 45 years by private Acts (*i.e.*, since 1755). The total result showed a net gain in area under wheat in 1,767,651 acres enclosed of 10,625 acres; the area under wheat being before enclosure 155,572 acres; after, 165,837 acres. But these figures included all sorts of enclosure. The Board of Agriculture ("Gen. Report," pp. 39 and 232), by leaving out cases where waste only was enclosed, obtained the following result for cases of enclosure of all commonable lands, under Acts passed between 1761 and 1799, in parishes where commonable arable was included. Taking the counties in groups we have:—

			Wheat Acreage Increased		Wheat Acreage Decreased	
			in Cases.	by Acres.	in Cases.	by Acres.
MIDLAND COUNTIES.						
Rutland	...	...	0	—	10	596
Warwick	...	...	2	93	30	2,871
Leicester	...	...	11	453	63	4,340
Northampton	...	...	11	450	75	7,016
Nottingham	...	...	14	923	28	1,823
Oxford	...	...	8	285	11	508
Buckingham	...	...	6	161	32	3,085
Bedford	...	...	7	668	23	1,801
Total	...	...	59	3033	262	22,036

	Wheat Acreage Increased		Wheat Acreage Decreased	
	in Cases.	by Acres.	in Cases.	by Acres.
EASTERN COUNTIES.				
Norfolk	8	627	1	10
Suffolk	3	150	0	
Huntingdon	7	469	9	530
Cambridge	7	895	2	184
Essex	1	40	0	
Hertford	3	174	1	7
Total	29	2,355	13	731
NORTHERN COUNTIES.				
Northumberland ...	2	80	1	93
Durham	1	20	2	172
Yorkshire	40	3,411	22	1,991
Lincoln	48	2,422	41	2,843
Derby	3	60	10	345
Total	94	5,993	76	5,444
SOUTHERN COUNTIES. (South of Thames).				
Berkshire	5	312	3	249
Wiltshire	12	884	11	528
Hampshire	6	256	2	90
Dorset	4	105	5	177
Somerset	1	50	1	33
Sussex	1	180	0	
Total	29	1,787	22	1,077
WESTERN COUNTIES.				
Gloucester	17	948	20	988
Hereford	1	40		
Shropshire	2	115		
Staffordshire	—	—	1	300
Worcester	9	345	3	155
Total	29	1,448	24	1,343
GRAND TOTAL ...	239	14,507	407	30,894

In estimating the significance of these figures it must be borne in mind that the figures for acreage in wheat after enclosure were collected at a time of famine prices for wheat. Probably many thousands of acres of old arable common field, which had been enclosed and laid down in grass, in each of these counties, were again ploughed under the stimulus of wheat prices exceeding 100*s.* per quarter.

So much with regard to the connexion between depopulation and enclosure in the second half of the eighteenth century. With regard to the first half, the following account is supplied by a certain John Cowper, "Inclosing Commons and Common field lands is contrary to the interest of the Nation" (1732):—

"When these commons come to be inclosed and converted into pasture, the Ruin of the Poor is a natural consequence; they being bought out by the lord of the *Manor*, or some other person of substance.

"In most open field parishes there are at a medium 40 farmers and 80 cottagers who hold their lands in common, and have right of commonage one with another. Suppose each person employs 6 labourers, we have in all 660 persons, men, women and children, who besides their Employment in Husbandry, carry on large branches of the Woollen and Linnen Manufactures."

With regard to the plea that hedging and ditching will employ many hands, he says: "This is so contrary to constant experience, that it hardly deserves to be taken notice of. I myself, within these 30 years past, have seen above 20 Lordships or Parishes inclosed, and everyone of them has been in a manner depopulated. If we take all the inclosed Parishes one with another, we shall find hardly ten inhabitants remaining, where there were an hundred before Inclosures were made. And in some parishes 120 families of Farmers and Cottagers, have in a few years been reduced to four, to two, aye, and sometimes to but one family. And if this practice of inclosing continues much longer, we may expect to see all the great estates ingrossed by a few Hands, and the industrious Farmers and Cottagers almost intirely rooted out of the kingdom. Raising Hedges and sinking ditches may indeed employ several hands for a year, or hardly so

long, but when that is once over, the work is at an end. . . . Owners of inclosed Lands, if they have but a little corn to get in, are already forced to send several miles to open field parishes for Harvest men."

Six open field farms, averaging 150 acres each, and the little holdings of twelve cottagers, would be let together, after enclosure, as one grazing farm, and the total rent thus be raised from £300 to £600. But whereas one acre of arable land would previously have produced 20 bushels at 3s. per bushel, a gross return of £3; after enclosure it would contribute to the fattening of a bullock to the extent of 25s. The gross produce is decreased; but the net produce is increased. Of the £3 produced by the acre of common field under wheat, 50s. would go in expenses, leaving 6s. 8d. to the landlord and 3s. 4d. to the tenant. Of the 25s. produced by the same acre enclosed under grass, 13s. 4d. would go to the landlord, 11s. 8d. to the grazier.

It is interesting in passing to note the association of common field agriculture with manufacture in the domestic stage indicated by this passage.

We have also direct evidence of the same movements in the seventeenth century. On the one hand Walter Blyth ("The English Improver," 1649, p. 40) has the passage:—"Consider but the Woodlands, who before Enclosure, were wont to be relieved by the Fieldon, with corne of all sorts. And now growne as gallant Corne Countries as be in England, as the Western part of Warwickshire, and the northern parts of Worcestershire, Staffordshire, Shropshire, Derbyshire, Yorkshire, and all the countries thereabouts." On the other hand, from the controversy between the two John Moores on the one hand, and Joseph Lee and an anonymous controversialist on the other, we can pick out certain statements of matters of fact that passed uncontradicted.

This controversy arose out of the enclosure of Catthorp, a parish in the extreme south-west corner of Leicestershire, bordering on Northamptonshire and Warwickshire. Lee was the parish priest of Catthorp, and a party to the enclosure. In his "Vindication of Regulated Inclosure," he gives a list of fifteen parishes within three miles of Catthorp which had been

enclosed. He also gives a list of nineteen parishes, enclosed from twenty to fifty years, in which depopulation had not yet taken place. This second list, as John Moore remarks, "they were forced to fish up out of the counties of Leicester, Warwick, Northampton, etc.," and it is significant that two only of the fifteen parishes enclosed near Catthorp are asserted by Lee not to have been attended by depopulation. If we go a little earlier we find in 1607 an insurrection against enclosures, followed by a searching enquiry by James I.'s government, and no doubt by renewed vigilance, for a while, in the enforcement of the Depopulation Acts. It may be regarded as axiomatic that in a corn-growing country,¹ enclosure which does not diminish tillage, does not provoke riot and insurrection.

While, however, enclosure which does not diminish the land under tillage does not, as a rule, cause rural depopulation, it is a rule not altogether without exception. One of the most striking passages in Cobbett's "Rural Rides" is that written in August, 1826, in which he describes the valley of the Wiltshire Avon:—

"It is manifest enough, that the population of this valley was, at one time, many times over what it is now; for, in the first place, what were the twenty-nine churches built for? The population of the twenty-nine parishes is now but little more than one-half of the single parish of Kensington,² and there are several of the churches bigger than the church at Kensington. . . . In three instances, Fifield, Milston, and Roach-Fen, the *church porches* would hold all the inhabitants, even down to the bed-ridden and the babies. What then, will any man believe that these churches were built for such little knots of people? . . . But, in fact, you plainly see all the traces of a great ancient population. The churches were almost all large, and built in the best manner. Many of them are very fine edifices; very costly in the building; and, in the cases where the body of the

¹ Riots may occur on the enclosure of waste, where the enclosed waste gave a livelihood to a considerable specialised population, as in Hatfield Chase and the Fens. See Dr. Cunningham's "Growth of English Industry and Commerce," Vol. II., pp. 187, 188.

² Just above he states it at 9,116.

church has been altered in the repairing of it, so as to make it smaller, the tower, which everywhere defies the hostility of time, shows you what the church must formerly have been. . . . There are now no less than nine of the parishes out of the twenty-nine, that have either no parsonage houses or have such as are in such a state that a parson will not, or cannot, live in them. . . . The land remains, and the crops and the sheep come as abundantly as ever ; but they are now sent almost wholly away. . . . In the distance of about thirty miles, there stood fifty mansion houses. Where are they now ? I believe there are but eight, that are at all worthy of the name of mansion houses. . . . In taking my leave of this beautiful vale I have to express my deep shame, as an Englishman, at beholding the general extreme poverty of those who cause this vale to produce such quantities of food and raiment. This is, I verily believe it, the worst-used labouring population upon the face of the earth.”¹

When Cobbett wrote, the process of Enclosure for this corner of Wiltshire was practically complete. Thomas Davis, whose account of the agriculture of Wiltshire is the most interesting of the whole series of county surveys, wrote when the process was in its early stage, and wrote predicting depopulation. He says, “The greater part of this country was formerly, and at no very remote period, in the hands of great proprietors. Almost every manor had its resident lord, who held part of the lands in demesne, and granted out the rest by copy or lease to under tenants, usually for three lives renewable. A state of commonage, and particularly of open common fields, was particularly favourable to this tenure. . . . The north-west of Wiltshire being much better adapted to inclosures and to sub-division of property, than the rest, was inclosed first ; while the south-east, or Down district, has undergone few inclosures and still fewer sub-divisions.”

The common field system was called “tenantry.”² The tenants ordinarily were occupiers of single “yardlands,” rented

¹ “Rural Rides,” 1830 edition, pp. 375—390.

² Thos. Davis, Wiltshire, p. 8.

³ *Ibid.*, p. 14.

at about £20 a year each. A typical yardland consisted,¹ besides the homestead, of 2 acres of meadow, 18 acres in the arable fields, usually in 18 to 20 pieces, a right on the common meadows, common fields, and downs for forty sheep, and as many cattle as the tenant could winter with the fodder he grew.² His forty sheep were kept with those of his neighbours, in the common flock of the manor, in charge of the common shepherd. They were taken every day to the downs, and brought back every night to be folded on the arable fields, the usual rule being to fold one thousand sheep on a "tenantry" acre (but $\frac{3}{4}$ of a statute acre) per night. In breeding sheep regard was had to what may be termed folding quality (*i.e.*, the propensity to drop manure only after being folded at night) as much as to quality or quantity of wool or meat.³

On the enclosure of such a manor the common flock was broken up, and the position of the small farmer became untenable. It is true, says our author, that he has the convenience of having his arable land in fewer pieces; but if he has his 18 acres all in one piece instead of in 20, he cannot plough them with fewer than the three horses he previously ploughed with. Then he has no enclosure to put his horses in; he no longer has the common to turn them on. His right on the down would entitle him to an allotment of sheepdown of about 20 acres, perhaps two miles from home. This is too small for him to be able to take it up, so he accepts instead an increase of arable land. But now he has no down on which to feed his sheep, no common shepherd to take charge of his sheep, which are too few to enable him individually to employ a shepherd. He, therefore, must part with his flock and then has no sheep to manure his land; further, having no cow-common, and very little pasture land,

¹ Contrast with such farms those described by Cobbett 30 years later: "At one farm 27 ricks, at another 400 acres of wheat stubble in one piece, at a third a sheepfold about 4,000 sheep and lambs, at a fourth 300 hogs in one stubble, a fifth farm at Milton had 600 qrs. of wheat, 1,200 qrs. of barley of the year's crop, and kept on an average 1,400 sheep" (pp. 363, 4, 5). "The farms are all large" (p. 361).

² *Ibid.*, p. 15.

³ *Ibid.*, p. 61.

he cannot keep cows to make dung with his straw. Lastly, the arable land being in general entirely unsuited to turn to grass, he is prevented from enclosing his allotment, and laying it down in pasture.¹ Obviously in such circumstances the small farmer, after for a few years raising diminishing crops from his impoverished arable land, must succumb, and in some cases help as a labourer to till his fields for another man, in other cases drift to the towns or enlist.

The contemporaneous decay of rural manufacturing industry,² of course, greatly aggravated the depopulating effects of enclosure. It may even have precipitated enclosure by weakening the position of the small farmer during the period of the French wars : during a time, that is, in which a combination of causes, apart from enclosure, was favouring the extension of large farms at the expense of small farms.³

In the south-east of Wiltshire, then, enclosure was followed by no increase of pasture farming, but it was followed by local depopulation. Whether the depopulation was merely local, or national as well, would depend upon whether, after enclosure, the total production of food of the parish were increased or diminished. Thomas Davis tells us that in many cases it was diminished, the reason, no doubt, being that there was a lack of farmers with sufficient enterprise and control of capital to absorb the small farms, as their occupiers began to drift towards bankruptcy. That such a result as this was felt to be an impending danger is shown by his statement :—"In some late inclosures allotments of arable land to small farmers have been set out adjoining to each other, directing the same to remain in an uninclosed state with a common right of sheep-feed over the

¹ *Ibid.*, p. 80.

² "The villages down this Valley of Avon, and indeed, it was the same in almost every part of this county, and in the North and West of Hampshire also, used to have great employment for the women and children in the carding and spinning of wool for the making of broadcloth. This was a very general employment for the women and girls, but it is now wholly gone." (Cobbett, "Rural Rides," p. 385, 1830 edition, written August, 1826.)

³ These causes were (a) the great fluctuations in prices of agricultural produce ; (b) the custom of using poor relief as a supplement to agricultural wages. The way in which these operated is ably dealt with by Dr. Cunningham.

whole, and a common allotment of down land and another of water-meadows, and some inclosed pasture to each if necessary."

In this district, consisting of open downs, stretching for miles along the summits and higher slopes of the chalk hills; intersected by winding rivers bordered by flat alluvial land of naturally rich pasture, but converted by irrigation into the famous Wiltshire water meadows, the long lower slopes of the hills, as it were, decreed by nature to be noble corn fields, cultivation had to be on a large scale; the unit of cultivation had to be a piece of land of reasonable width, stretching from the river to the summit of the downs. Hence small farms could not exist without some degree of organised mutual help. When that organisation, which in this district was furnished by the common field system, was terminated by Enclosure Acts, consolidation of farms became necessary.

Nowhere else are these conditions present in quite so fully developed a degree as in Wiltshire, which contains the central hub from which radiate the three great belts of chalk down, the South Downs, the North Downs, and the range containing the Chilterns, the chalk hills of Hertfordshire, the Gog-Magogs of Cambridgeshire, and their continuation into Norfolk. But the most essential feature of Wiltshire agriculture, viz., the combination of sheep down and arable field, may be said to be characteristic of all this country. This is the country from which in the sixteenth century came the great indignant outcry against enclosure, which in More's "Utopia" enters into the classic literature of our country. When it is remembered that the economic motive of enclosure then was the high price of wool, that private individuals are stated to have owned flocks of ten thousand, twenty thousand, and even of twenty-four thousand sheep, it is easy to conceive of whole parishes being converted into great sheep runs.

¹ Preamble to 25 Henry VIII. c. 13.

CHAPTER XI.

ENCLOSURE AND THE POOR.

"The Poor at Enclosure do Grutch
Because of abuses that fall."

TUSSER, "Champion and Several."

DURING the nineteenth century the controversy with regard to enclosure did not turn upon the question whether it did or did not injure the mass of the rural poor of the locality, in their capacity of agricultural labourers, by depriving them of employment; but whether it injured them by depriving them without compensation of rights which they had enjoyed before enclosure, but which could not be legally established; and whether poor owners of common rights have received compensation: the question, in fact, whether the poor are justified in "Grutching at Enclosure," because of real abuses in the method of carrying it out. On this question no distinction need be drawn between the two classes of Enclosure Acts.

I do not think that much complaint can be made with regard to the administration of the Enclosure Acts since 1876 by the Board of Agriculture. By the provision of adequate allotment grounds and recreation grounds compensation is made to those villagers who can claim no specific rights of common; and though no doubt many of the owners of single common rights are dissatisfied with the plots of land assigned to them, there seems to be no reason for doubting that the Commissioners appointed have endeavoured to deal with rich and poor with equal fairness. Further, a great deal of the work of the Board in its capacity of Enclosure Commissioners has been the regulation of commons; and to a certain degree they have become a body for preserving instead of destroying commons. They may even be described as the most potent force for the preservation

of existing common-fields, simply by insisting on a certain method in the division and allotment, which may be too expensive.

But this verdict of "Not guilty" only applies to the enclosure authority since it was chastened and corrected by the movement for the preservation of commons. All the early reports of the Enclosure Commissioners, or the Enclosure, Tithe and Copyhold Commissioners give abundant evidence of the hard, legal spirit in which the claims of cottagers were considered, and the slight reasons which were considered good enough for refusing recreation grounds and allotments. The twenty-seventh annual report—the *apologia* of the Commissioners—pleads, as we have seen above, that 8,000,000 acres of commons, and 1,000,000 acres of commonable arable fields or meadows still existed, which was absurdly inaccurate, and that "of all modes of tenure in a fully peopled country there is none more prejudicial to improved culture than that of holding in common." Again, the thirty-second report makes a great deal of the fact that the 590,000 acres of common and commonable land dealt with since the Act of 1845 had been distributed among 26,000 separate owners; which, however, only proved that the number of people who owned rights over unenclosed land had been greater than the number of owners of a corresponding area of enclosed land—but whether that was because commons and common fields favoured the creation or preservation of small properties (as it certainly does in many cases), or whether because a multiplicity of owners favours the preservation of commons and common fields (which is always the case), no credit was due to the General Enclosure Act, or to the body administering it.

We find that between 1845 and 1875, out of a total area of 590,000 acres divided and allotted, just 1758 acres were set aside for recreation grounds, and 2195 acres for field gardens and allotments. The administration of the Act since 1877 is, therefore, a very severe condemnation of its administration in the earlier period.

We have seen in the case of Ewelme and the neighbouring parishes, how the cottagers were injured on enclosure, by losing

their source of fuel, without getting any compensation. I am indebted to Mr. John Swain for the following description of the effects of enclosure of a Welsh mountain.

“The parish of —, in the county of Montgomeryshire, is about five miles long by two miles broad. It consists for the most part of a hill, lying between a river and one of its tributaries. The hill rises to about 900 feet above sea level, and contains no unenclosed land. We have, therefore, in this parish, two strips of low-lying meadow land, land of a moderate quality on the hill slopes, and rough pasture land near the summit. On this hill most of the cottage holdings are to be found, usually in some sheltered hollow near a spring or a running stream. . . .

“Previous to the Enclosure Act, passed early in the nineteenth century, the greater part of the hill was open. The farms occupied the bottom lands, and the foot of the hill, up which they crept, their boundary fences forming an irregular line on the hillside, being higher or lower as the nature and quality of the land tempted enclosure. The unenclosed portion of the hill was used as a common pasture by all the farmers whose land adjoined it, and the amount of stock each one was allowed to feed on it was roughly regulated by the size of his holding.

“About 120 years ago a number of the poorer peasantry began settling on this common land. There was a general understanding that if a house was raised during the night so that the builders were able to cause smoke to issue from the chimney by sunrise, they thereby established a right of possession which none could gainsay. Timber in the neighbouring woods was abundant and cheap, so an intending squatter had little difficulty in procuring the material for building his cottage. With the help of his friends he procured sufficient wood for the framework, and then selected a convenient site in a sheltered spot with a southern aspect, and marked down the foundations of his future dwelling. When all preparations were made he gathered together all the help he could, and in the dusk of the evening had all his materials conveyed to the selected spot. Rough stonework was laid to form the foundations and chimney end of the cottage, and then the framework was quickly set up.

The panels were interwoven with stout laths, and covered with clay, over which was smeared a coating of lime-plaster, while a roof of thatch completed the edifice. Windows were not for a time considered necessary, but the entrance was carefully secured by a stout door. Then just as the dawn was breaking, a fire was kindled on the hearth, and the curl of smoke above the rude chimney told the workers that they could now relax their efforts. . . .

“A dwelling-house having been erected, the next step was to appropriate a few acres of land surrounding it. . . . The difficulty of obtaining sufficient land for the keep of a cow was no more than the labour of enclosing and reclaiming it.

“In this way some thirty or forty families were settled in cottages built by themselves, around which were three or four fields, where for many years they lived in undisturbed possession. By patient labour the gorse and fern were got rid of, trees were planted round the cottage, or allowed to grow where they sprang up in suitable places in the hedgerows; by cultivation and manuring the herbage was improved.

“With the Enclosure Act there came a disturbance of this state of affairs. The partition of the unappropriated land seems to have been carried out fairly, by adding to each farm a quantity of land in proportion to the amount of pasturage the occupier enjoyed on the common. . . . When, however, we come to consider the case of the cottager, his treatment was by no means fair. Enclosures of over twenty-one years' standing were not interfered with, and their owners were left in undisturbed possession, but such as had been enclosed for a shorter period were claimed by the Lord of the Manor, who lived some twelve miles away, and possessed little or no land in the parish. He advanced his claim cautiously, asking only a nominal rent, and as unlettered peasants felt the inequality of a contest in the matter, this rent was paid. Consequently more than half the cottage holdings fell into his hands, and the poor occupiers were deprived of the ownership of the dwellings they had erected, and of all the improvements they had put into the land they had enclosed. None of them had to leave their holdings, and the

rent at first charged was trifling; but except in cases where life-leases were granted, the cottagers had lost all their rights, and they and their holdings were left entirely in the hands of a large landowner."

The Enclosure Act, of course, prevented the creation of any more cottage holdings. The fertility of the soil in these small holdings, Mr. Swain says, is enormously greater than that of the land, naturally similar, on the other side of the hedge. Usually the cottager gets a neighbouring farmer to plough half an acre of his holding for him, paying for this service in labour at harvest time; and keeps the rest, except the garden plot, under grass. The average size of the holding is about six acres; which is found sufficient for two cows, a heifer, a calf, several pigs, thirty fowls, and a dozen ducks. The produce supplies all the vegetables, fruit, milk, butter, eggs and bacon consumed by the family, and brings in the following money returns, on Mr. Swain's calculations:—

	£	s.	d.
One cow and one calf sold per annum (the other calf being reared to replace the cow sold) 	14	0	0
Six pounds of butter per week, at 1s. per lb.	15	12	0
1 pig, sold at a net profit of 	2	10	0
20 fowls 	2	5	0
400 eggs (allowing 600 for home con- sumption) 	1	8	0
	<u>£35</u>	<u>15</u>	<u>0</u>

As Mr. Swain writes from an intimate personal knowledge, I have no hesitation in accepting his statement as approximately accurate.

The injury to the cottagers does not end with the prevention of the creation of fresh holdings, and the transfer of the ownership of most of those already existing to the lord of the manor. For the landlord, managing his estate in the ordinary way, through the intermediaries of steward and agent, is almost invariably led into merging such small holdings into larger

farms, in spite of the high rents which would often be gladly paid.

It will be seen that these two cases are in the nature of things typical. Similar hardships may be regarded as the almost inevitable effect of any enclosure which included any considerable quantity of waste land; and if the enclosure is necessary or highly desirable, some compensating advantages ought to be provided for the inhabitants as such. The smallness of such provision between 1845 and 1875 is very significant. And it makes one seriously doubt whether in their zeal for furthering improved culture, the Commissioners were as considerate as was desirable to the cottager who had a legal common right. But on that point we can apply no statistical test.

If we turn from enclosures since 1845 to enclosures before, we have a verdict from the old Board of Agriculture in its General Report on Enclosures published in 1808, which, so far as it is biassed, is biassed entirely in favour of enclosure. It says: "The benefit (of enclosure) in this case (to the poor) is by no means unmixed."

The loss of fuel is declared to be the chief injury; and besides, "In some cases many cows had been kept without a legal right, and nothing had been given for the practice."

"In other cases, where allotments were assigned, the cottagers could not pay the expense of the measure, and were forced to sell their allotments."

"In others they kept cows by right of hiring their cottages, or common rights, and the land going, of course, to their proprietor, was added to the farms, and the poor sold their cows. This is a very common case."¹

The results are given of an investigation into the results of sixty-eight Enclosure Acts, chiefly in the Eastern Counties; testimony having been obtained from the clergy and others considered to be impartial witnesses. In fifteen cases it is asserted that the poor were not injured by the enclosure; in fifty-three cases

¹ "General Report on Enclosures," pp. 12, 13.

that they were. The general tenour of the statement in these cases is to the effect that the condition of the poor has become very much worse, that they have lost all their cows,¹ and they no longer are able to buy milk for their children. Here are a few of the more striking descriptions:—

Ackworth, Yorkshire. The parish belonged to near 200 owners; nearly the whole of whom have come to the parish since the enclosure, or changed the quantity of their lands.

Todenham, Gloucester. Nothing increased but the poor. Eight farmhouses filled with them.

Tingewick, Bucks. Milk to be had at 1*d.* a quart before; not to be had now at any rate.

Passenham, Northamptonshire. (The poor) deprived of their cows, and great sufferers by the loss of their hogs.

Tulvy, Bedfordshire. Cows lessened from 110 to 40.

Letcomb, Berkshire. The poor can no longer keep a cow, and they are therefore now maintained by the parish.²

Alconbury, Huntingdon. (1791, c. 70.) Several who kept cows before were, upon enclosure, forced to part with them, and have kept none since. The cottage allotments going to the landlords were thrown together, and the inhabitants left without cows or land. Those who had allotments given in lieu of their rights, not being able to enclose them,³ were forced to sell, and became as the rest in this respect. Before enclosure milk could readily be bought, poor people could lay out a half-penny or a penny every day, but nothing of the sort could be got since.⁴

With regard to Buckingham in general, we have the following statement from a later survey for the Board of the County:—

“The poor and persons with little capital (such as butchers, common shepherds, etc.) derive benefit from open fields and commons, by being enabled to keep horses, cows, and sheep. . . . It will be difficult to prove that in any case the poor have been benefited (by enclosure). No instances of benefit on this score

¹ This is specifically asserted in 17 cases.

² “General Report on Enclosures,” pp. 150—152.

³ Because of the expense.

⁴ “General Report,” p. 154.

have been stated to me. On the contrary, an increase of poor (*i.e.*, of paupers) has been the general complaint."

Similar evidence is given by two professional Enclosure Commissioners. Mr. Forster, of Norwich, "lamented that he had been accessory to injuring 2000 poor people, at the rate of twenty families per parish. Numbers in the practice of feeding the commons cannot prove their right; and many, indeed most who have allotments, have not more than one acre, which being insufficient for the man's cow, both the cow and land are usually sold to opulent farmers. The right sold before the allotment produced much less than the allotment after it, but the money is dissipated, doing them no good when they cannot vest it in stock."¹

Mr. Ewen, another Commissioner, "observed that in most of the enclosures he has known the poor man's allotment and cow are sold five times in six before the award is signed." A third Commissioner, Mr. Algar, declared that he made it a practice to give an allotment whenever a cottager could merely prove that he had been in the practice of cutting turf. But one wonders whether Mr. Algar did not find this custom of his prejudicial to the demand for his professional services.

In estimating the weight of this evidence, both as to depopulation and as to injury to the poor, it must be borne in mind that it is taken almost entirely from the mouths of advocates, and mostly very enthusiastic advocates, of enclosure. They are admissions of men who feel that the general case in favour of enclosure is so strong that they may well candidly admit the existence of some drawbacks. Of course, some advocates of enclosure are not disposed to make any admissions at all. Many urge the moral evils engendered by waste lands, as: "Where wastes and commons are most extensive, there I have perceived the Cottagers are the most wretched and worthless; accustomed to rely on a precarious and vagabond subsistence from land in a state of nature, when that fails they recur to pilfering, and thereby become a nuisance to their honest and

¹ "General Report," p. 157.

industrious neighbours; and if the father of a family of this sort is withdrawn from society for his crimes, his children become burthensome to the parish. It may truly be said that for cottagers of this description the game is preserved, and by them destroyed; they are mostly beneath the law and out of reach of detection; and while they can earn four or five shillings, and sometimes more, in a night, by poaching, they will not be satisfied with 10*d.* or 1*s.* a day for honest labour.”¹ A not unusual style of argument is the following:—

“To deprive the poor of that benefit, which, in their present state, they derive from the waste lands, must no doubt, at first view, sound harsh. But it ought to be remembered that in this wealthy county, where there is so much work to be done, and so few hands comparatively to do it, there are few poor that do not deserve to be so. Those persons who are disqualified to provide for the calls of human nature by the feebleness of infancy, the crushing hand of disease, or the infirmities of old age, cannot be said to be poor, because *all* the landed property, situate within their respective parishes, is always liable to be charged with their maintenance.”²

After reading of the good fortune of these Herefordshire labourers, so much in demand in a wealthy county that the benefits derived from wastes and commons are of little concern to them, one naturally inquires, what were their wages? Day labourers earned in summer, “6*s.* a week and a gallon of drink to each man”;³ in winter, 5*s.* a week and three quarts; in harvest, 14*d.* a day and meat and drink: the hours of labour being in harvest time and in winter as early and as late as they could see; in summer, not harvest, from 6 to 6. Leaving out the cider, this works out at a penny an hour, and a penny in 1794 would not buy very much more of the ultimate necessities of life in Herefordshire than it will to-day.

There seems, underlying John Clark’s words, a notion that if any injury is done to the poor by enclosure, proper and sufficient

¹ D. Walker, “Hertfordshire” (1794), p. 53.

² John Clark, ‘Hereford’ (1794), p. 27.

³ *Ibid.*, p. 29. “Drink” of course means cider.

compensation will be made in the ordinary course to the persons injured out of the poor-rates. The logical deduction is that the profits of enclosure should contribute to the poor-rates, and I have noted thirteen enclosures of wastes and commons in which this was done. Another logical deduction was that the poor rate in parishes in which waste was enclosed was, in part at least, a species of common property belonging to the poor; and to deprive them of this property was robbery, unless the commons were restored. This view was vigorously expressed by Cobbett in his "Political Register," at the time of the introduction of the Poor Law of 1834, and from him became part of the traditional stock of political ideas handed down through the Chartists to the Labour movement of recent times.

Arthur Young, in a pamphlet published in 1801,¹ not only insists upon the injury to the poor from Enclosure Acts as ordinarily drawn and put into execution, but pleads for enclosure on methods which would tend to the social elevation of the labourer. His proposals, which strike one as, for the time, wise and statesmanlike, though they ignore some considerations which would be of great importance to-day, were:

(1) That in the case of small commons in the midst of an enclosed country, labourers should be allowed to absorb the whole by gradual encroachments, thus building up small properties for themselves.

(2) In the case of extensive wastes, procedure must be by Act of Parliament, but all Acts should secure enough land for every cottager to keep a cow both summer and winter, such land to be *inalienable from the cottage, and the ownership to be vested in the parish.*

I have found one Act which realises Arthur Young's ideal of an Enclosure Act. It was passed in 1824 for Pottorn in Wiltshire, and though it was an Act for the enclosure of a common only, no commonable meadow or common field being included, I give its provisions here on account of its intrinsic interest.

The ownership of the whole common was vested in the Bishop

¹ "Enquiry into the propriety of applying wastes to the better support and nourishment of the poor."

of Salisbury, who was lord of the manor, the vicar and churchwardens, in trust for the parish. The trustees were required to lease it in small holdings, with or without rent, to poor, honest, and industrious persons, who had not, except in cases of accident or illness, availed themselves of Poor Law relief.

The following Acts, all (except that for Earsham) for "extinguishing village communities," *i.e.*, for enclosing all the commonable lands of the parishes or townships, which in each case include commonable arable fields, have special provisions to safeguard the interests of the poor :—

1757, c. 53. Wimeswould, Leicestershire. Cottagers who have no land are to have a share together within one fence, which they may afterwards separately enclose if they like. This is specially interesting as anticipating the modern practice of providing allotments for such cottagers.

1767, c. 49. Carlton in Lindrick, Nottingham. Three acres (out of a total of 2492 acres) are to be set aside for building cottages for the benefit of the poor.

1779, c. 89. Evenley or Bury Manor, Northampton. Lands to the value of £10 per annum (out of £1200) are to be set aside for the most deserving poor not receiving poor-relief.

1785, c. 56. Eight parishes in Wiltshire enclosed by one Act. Not more than ten acres in each parish is to be set aside, free of taxes, for fuel for the poor.

1805, c. 19. Palling, Norfolk. One-twentieth of the whole area is to be vested in the lord of the manor, vicar, and overseers, in trust for the poor, for common of pasture and fuel.

1807, c. 18. Herringswell, Suffolk. An allotment is to be made for fuel for the poor.

1809, c. 7. Barton Turf, Norfolk. Thirty acres is to be reserved for common for the poor.

1810, c. 55. Great Sheepey, Leicestershire. *Every cottage to have not less than 3 acres allotted to it.*

1812, c. 3. Little Brandon, Norfolk. Ten acres to be set aside for the benefit of the poor, partly to be used as common for fuel, or to be leased to pay for fuel; another part to provide a common pasture for the poor inhabitants; while the *remainder*

(how much? one wonders) was to be leased in aid of the poor-rates.

1812, c. 17. Earsham, Norfolk. Five acres to be set aside to be leased to buy fuel for the poor.

Also in the Acts for Northwold, Norfolk (1796, c. 14), Lower Wilbraham, Cambridge (1797, c. 89), and Barnady, Suffolk, allotments were made inalienable from the cottages for which they were assigned. At Northwold land capable of supplying annually 12,000 turves per annum was reserved as a common turbarry for the poorer owners of common rights.¹

This list of Acts containing special provisions for the benefit of the poor is not a complete one, but if it were it would not, I believe, include more than one per cent. of the Enclosure Acts passed prior to 1845. Arthur Young did not over-state the case when he wrote: "By nineteen Enclosure Acts out of twenty, the poor are injured, in some grossly injured. . . . The poor in these parishes may say, and with truth, *Parliament may be tender of property, all I know is, I had a cow, and an Act of Parliament has taken it from me.*"²

¹ I must here refer to the extraordinary Act by which Pickering Moor (Yorkshire, West Riding) was enclosed in 1785 and divided equally among all owners of common rights, the poorest cottager owning an ancient cottage getting as much as the largest landowner. Before enclosure the yeomen of Pickering had pastured such animals on the moor as they could provide with winter keep. The great tithes were rented by an enterprising lessee, who conceived the idea of parcelling the moor into small farms which would grow corn and yield tithes. In spite of the disinclination of the yeomen to any change, he procured the passing of an Enclosure Act, in which it was declared that the moor was equally the property of all ancient cottages and messuages, and was required to be divided equally among the owners of all of these. A peculiar clause in the Act enacted that no part of the moor should be "deemed barren in respect of tithes." The larger yeomen felt themselves to be cheated, and were very indignant, but through inertness and lack of co-operation they failed to take steps to prevent the Act being executed. This they presumably might have done by an appeal to Quarter Sessions.

² "Enquiry into the propriety of applying wastes to the better support and maintenance of the poor," 1801, p. 42.

CHAPTER XII.

THREE ACRES AND A COW.

THAT the poor were not always the only sufferers from an Enclosure Act, is shown by the account given by the General Report on Enclosures of the way in which farmers were affected. After referring to the idea that opposition from farmers is usually to be ascribed to ignorant prejudice, the report proceeds:—

“In many instances they have suffered considerably for four, five, or six years. From the first starting the project of an Enclosure Act to the final award, has, in numerous cases, taken two, three, four, and even five or six years; their management is deranged; not knowing where their future lands will be allotted, they save all their dung till much of it is good for little; they perform all the operations of tillage with inferior attention; perhaps the fields are cross-cropped and exhausted, and not well recovered under a course of years. Rents are greatly raised and too soon; so that if they do not absolutely lose five years they at least suffer a great check. In point of profit, comparing the old with the new system, attention must be paid to their capitals; open field land is managed (notwithstanding the inconvenience of its pieces) usually with a less capital than enclosures; and though the *general* profit of the latter exceeds that of the former, yet this will entirely depend on the capital being adequate. In cases where the new enclosures are laid down to grass, all this becomes of tenfold force; to stock rich grass lands demands a far greater sum than open field arable; the farmer may not possess it; this has often happened, and drove them to seek other investments, giving way to new-comers more able to undertake the new system introduced; and if profit be measured by a percentage on the

capital employed, the old system might, at the old rents, exceed the profits of the new; and this is certainly the farmers' view of the comparison. He also who had given the attention of a life to the regular routine of open field arable, without 10 acres of grass ever having been in his occupation, may find himself much at a loss in the regular purchase and sale of live stock, the profit of which depends so much on habitual skill. Add to all this the previous circumstance of laying down to grass, the business of all others of which farmers know the least, of which I have many times seen in new enclosures striking instances; and if all these points be duly considered, we shall not find much reason to be surprised at the repugnance shown by many farmers to the idea of enclosing." (Pp. 31, 32.)

While the whole of this description of the ordeal that the farmers had to pass through is interesting, the point I desire here to emphasize is the need of a larger capital after enclosure. Those who had the requisite skill, knowledge, energy and capital survived the crisis; they were able to take up the farms which their weaker neighbours were compelled to relinquish; to send, in almost every case, a larger *surplus* of food from the lands of the parish to maintain the state and power of England, and to pay higher rents. In perhaps the majority of cases they raised a larger gross produce, and provided maintenance and employment for a larger population than before. In some cases even (though these were rare exceptions) the labouring population gained in material prosperity as well as in numbers. But in any case the relationship between employer and employed was notably altered.

In the open field village the entirely landless labourer was scarcely to be found. The division of holdings into numerous scattered pieces, many of which were of minute size, made it easy for a labourer to obtain what were in effect allotments in the common fields. If he had no holding, he still might have a common right; if no acknowledged common right, he might enjoy the advantage of one in a greater or less degree. From the poorest labourer to the richest farmer, there was, in the typical open field village, a gradation of rank. There was no

perceptible social gap between the cottager who worked the greater part of his time for others, and for the smaller part of his time on his own holding, who is therefore properly termed a labourer, and his neighbour who reversed that distribution of time, and is therefore to be deemed a farmer. It was easy for the efficient or fortunate man to rise on such a social ladder; equally easy for the inefficient or unlucky to slip downwards.

After enclosure the comparatively few surviving farmers, enriched, elevated intellectually as well as socially by the successful struggle with a new environment, faced, across a deep social gulf, the labourers who had now only their labour to depend upon. In the early part of the nineteenth century, at any rate, it was almost impossible for a labourer to cross that gulf; on his side the farmer henceforward, instead of easily becoming a farm labourer if bankrupt, would rather try his fortune in the growing industrial towns.

Our "Country Farmer" gives us a vivid picture of one side of the social change ("Thoughts on Enclosure," p. 21). Of the farmer after enclosure he says:

"Their entertainments are as expensive as they are elegant, for it is no uncommon thing for one of these new created farmers to spend ten or twelve pounds at one entertainment; and to wash down delicate food, must have the most expensive wines, and these the best of their kind; and to set off the entertainment in the greatest splendour, an elegant sideboard of plate is provided in the newest fashion. As to dress no one that was not personally acquainted with the opulent farmer's daughter can distinguish her from the daughter of a Duke by her dress, both equally wishing to imitate something, but they know not what.

"View the farmer before the land was inclosed, and you will find him entertaining his friends with a part of a hog of his own feeding, and a draught of ale brewed from his own malt presented in a brown jug, or a glass, if it would bear it, which was the utmost of his extravagance: in those happy days you might view the farmer in a coat of the growth of his flock; and

spun by his industrious wife and daughters, and his stockings produced from the same quarter of his industry, and his wife and daughters clad from their own hands of industry and their own flock."

As for the other side of this social change, the labourer's side, it seemed so serious an evil to many even of the progressive landlords and agriculturists who strongly advocated enclosure, that they busied themselves to find a remedy.

In 1897 the Board of Agriculture drew the attention of its members to a typical case. Mr. Thomas Bernard communicated an "Account of a Cottage and Garden near Tadcaster." The cottager had held two acres of land and a common right at Poppleton for nine years, and there had lived comfortably and brought up six children. The enclosure of the parish turned him adrift, but he prevailed upon a landlord to let him have a piece of roadside waste for a garden, saying, "I will show you the *fashions* on it." The landlord was so delighted afterwards with the way in which this garden was cultivated, that he offered the man to let him have it rent free. Particular attention was directed to the man's reply:—"Now, sir, you have a pleasure in seeing my cottage and garden neat: and why should not other squires have the same pleasure in seeing the cottages and gardens nice about them? The poor would then be happy and would love them and the place where they lived; but now every nook of land is let to the great farmers; and nothing left for the poor but to go to the parish." ("Communications to the Board," Vol. I. p. 404.)

It was by "going to the parish" that the labourer could bring home to the landlord the idea that the spirit of ambition and self-reliance fostered by the possession of two acres and a common right was of value to the nation. The national emergency due to the famine prices of food during the French War, which produced the complete change in the spirit of the administration of the Poor Law associated with the "Speenhamland Act of Parliament," also forced into public attention the desirability of both providing agricultural labourers with some other supplement to their wages, and of encouraging them to avoid pauperism.

We accordingly find the Board of Agriculture offering for 1800 three gold medals :—

“To the person who shall build on his estate the most cottages for labouring families, and assign to each a proper portion of land, for the support of not less than a cow, a hog, and a sufficient garden—the Gold Medal.”

“To the person who shall produce the most satisfactory account of the best means of supporting cows on poor land in a method applicable to cottagers—the Gold Medal,” (doubts having been raised with regard to the practicability of cottagers keeping cows except on rich soil).

“The Board having received information that the labouring poor of Rutland and Lincolnshire, having land for one or two cows, and a sufficiency of potatoes, have not applied, in the present scarcity, for any poor law relief; and it appearing to be a great national object to spread so beneficial a system, the Board will give to the person who shall explain, in the most satisfactory manner, the best means for rendering this practice as general through the kingdom as circumstances will admit—the Gold Medal.” (“Communications,” Vol. II.)

Each of these medals was again offered in subsequent years.

The question appears to have been first brought before the Board of Agriculture by the Earl of Winchilsea, in a conversation at the Farmers' Club with Sir John Sinclair, President of the Board, in 1795. At Sir John Sinclair's request, the Earl of Winchilsea put his views in writing, and they were submitted to the Board, in the form of a letter, dated Jan. 4th, 1796. This letter is a convincing statement in favour of the case for “three acres and a cow,” and deserves the attention of politicians of to-day.

Beginning by stating that he has made further enquiries, since the conversation with Sir John Sinclair, into the practice of agricultural labourers keeping cows, he continues :—“I am more and more confirmed in the opinion I have long had, that nothing is so beneficial, both to them and to the landowners, as their having land to be occupied either for the keeping of cows, or as gardens, according to circumstances. By means of these

advantages, the labourers and their families live better, and are consequently more fit to endure labour; and it makes them more contented, and gives them a sort of independence, which makes them set a higher value on their character. . . . When a labourer has obtained a cow, and land sufficient to maintain her, the first thing he has thought of has been how he could save money enough to buy another; . . . there are from 70 to 80 labourers upon my estate in Rutland, who keep from 1 to 4 cows each. . . . I am informed that those who manage well clear about 20*d.* per week, or £4 6*s.* 8*d.* per ann. by each cow.”¹

If the cow died, it was, he says, a great misfortune for the labourer, but he contrived to beg or borrow the money necessary to obtain another cow—“I scarcely ever knew a cow-gait given up for want of ability to obtain a cow, except in the case of old and infirm women.”

He classifies the situation of labourers, in order of felicity, as follows:—

(1) Those who have a sufficient quantity of grass enclosed land to enable them to keep one or more cows winter and summer, and a garden near their house; a grass field allotted to a certain number being as advantageous, or nearly so, as separate small enclosures.

(2) Those who have a summer pasture for their cow, and some arable land, on which they grow the winter provision. This is slightly less advantageous than (1), because tilling the arable land takes up more time.

(3) Those who have a right of common for the summer keep of the cow, and a meadow, or arable ground, or the share of a meadow in common, for the winter provision. If it were not that commons are usually over-stocked, this would be equivalent to (1) or (2).

(4) Those who have a right of common, but no cow, and a garden. In this case geese and pigs can be kept.

¹ Milk being valued at 1*d.* per quart; it seems clear also that what is consumed at home is not included in this calculation.

(5) Those who have a right of common and no garden. In this case the value of the right of common depends upon whether fuel is obtained from the common or not.

(6) Those who have several acres of arable land, and no summer pasture for a cow. This, he maintains, is of little value, because of the large expenditure of labour necessary for cultivating the land, but he admits that many would differ from him on this point.

(7) Those who have a garden near the house.

(8) Those who have no land whatever. "This is a very bad situation for a labourer to be placed in, both for his comfort and the education of his children."

Then he continues, in words which seem in general as true and weighty now as when written or as at any time within the last hundred years:—"In countries where it has never been the custom for labourers to keep cows, it would be very difficult to introduce it; but where no gardens have been annexed to the cottages it is sufficient to give the ground, and the labourer is sure to know what to do with it, and will reap an immediate benefit from it . . . there should be as much as will produce all the garden stuff the family consumes, and enough, with the addition of a little meal, for a pig. I think they ought to pay the same rent that a farmer would pay for the land, and no more. I am persuaded that it frequently happens that a labourer lives in a house at 20s. a year rent, which he is unable to pay, to which, if a garden of a rood was added, for which he would have to pay five or ten shillings a year more, that he would be enabled, by the profit he would derive from the garden, to pay the rent of the house, etc., with great advantage to himself.

"As I before mentioned, some difficulties may occur in establishing the custom of labourers keeping cows in those parts of the country where no such custom has existed; wherever it has or does exist it ought by all means to be encouraged, and not suffered to fall into disuse, as has been the case to a great degree in the midland counties, one of the causes of which I apprehend to be, the dislike the generality of farmers have to seeing the labourers rent any land. Perhaps one of their reasons

for disliking this is, that the land, if not occupied by the labourers, would fall to their share ; and another, I am afraid, is, that they rather wish to have the labourers more dependent upon them, for which reasons they are always desirous of hiring the house and land occupied by a labourer, under pretence, that by that means the landlord will be secure of his rent, and that they will keep the house in repair. This the agents of estates are too apt to give in to, as they find it much less trouble to meet six than sixty tenants at a rent day, and by this means avoid the being sometimes obliged to hear the wants and complaints of the poor." . . . The landlord naturally yields to this pressure . . . "and it is in this manner that the labourers have been dispossessed of their cow-pastures in various parts of the midland counties. The moment the farmer obtains his wish, he takes every particle of the land to himself, and relets the house to the labourer, who by this means is rendered miserable, the poors rate increased, the value of the estate to the landlord diminished, and the house suffered to go to decay . . . Whoever travels through the midland counties, and will take the trouble of enquiring, will generally receive the answer, that formerly there were a great many cottagers who kept cows, but that the land is now thrown to the farmers ; and if he enquires still further, he will find that in those parishes the poors rates have increased in an amazing degree, more than according to the average rise throughout England."

Sir John Sinclair,¹ President of the Board of Agriculture, did not agree that a plot of a few acres of arable land was, by itself, of little value to the agricultural labourer. He estimates that two cows can be kept on 3½ acres of arable land, and that the net produce, valuing milk at 1*d.* per quart, would amount to £21 per annum, about as much as the man's wages. He advocated spade labour, and recommended that the cottager should rather hire men to dig for him, than get the land ploughed. In confirmation of this opinion Sir Henry Vavasour cited an example of a cottager holding 3 acres who kept two cows and two pigs. The

¹ "Communications to the Board of Agriculture," Vol. IV., p. 358.

butter alone paid the rent, and the gross produce was estimated at £54 per annum, exclusive of milk and vegetables consumed at home.

It is of course practically impossible to calculate how much effect this landowners' agitation for the policy of "Three acres and a cow" had on the number of such cottage holdings. Lord Brownlow¹ writes: "In all open field lordships there have always been pastures in which the cottagers have had their share of benefit; but the practice of enabling cottagers to keep cows in inclosed parishes, is in my neighbourhood rare, and of recent date." Accounts are sent of cottage holdings provided by the Earl of Carrington, and of large allotments provided by Mr. Thomas Estcourt; but I cannot say how extensively their example was followed.

Mr. W. E. Bear's report to the recent Labour Commission, on the agricultural labourers of the Southwell Union, contains the following passage, in which we probably see some fruits of the Earl of Winchilsea's movement:—"Small holdings, of three to ten acres commonly, are let with cottages in a few parishes, and called 'cottagers.' This custom appears to be a very old one, dating back far beyond the time when the term 'three acres and a cow' was invented. In Ossington, Mr. Richardson told me, it was 50 years old or more; but he said it was falling into disuse. I found some 'cottagers' in Averham, Ossington and Hockerton, and heard of them in another parish or two. They usually consist of grass land, and are best so, as the labourer can leave his wife to manage the cow or two kept on them, and work for wages regularly. In Averham some of these small holdings have been given up, apparently because they were partly arable, and occupiers found that they could not keep regular places and also attend to their land. But where the land is all pasture, they are excellent institutions, providing families with milk, and adding to the incomes by means of milk or butter, poultry, eggs and pork sold. These little holdings are let from £2 10s. to £3 an acre, including the cottage" (par. 51 A).

¹ "Communications to the Board of Agriculture, Vol. IV., p. 367.

The same Commissioner found in Leicestershire a system of common cow-runs for cottagers which also probably dates from the eighteenth century, being in some way a survival from the common field system. He describes it as follows :—

“ There are cow plots let with cottages in several parishes. Some have already been referred to as existing on the Earl of Dysart’s estate. One example is to be found at Saxby, where cow runs of 6 a. 3 r. 12 p., each in common, are let with a cottage and garden at £10 per annum. At Grimston I visited some which are let by Mr. Wright or Mr. Reckitts, who appear to be somehow connected on the same estate. . . . Some of these cow-plots are $3\frac{1}{2}$ acres in extent, and their holders are allowed to keep only one cow, as three or more of them occupy a pasture in common, having a portion of their $3\frac{1}{2}$ acres each year to mow and another portion to feed. The rent, including cottage and garden, is £10. There are some other cow plots of 8 acres on which two or three cows are kept, the rent being £15. In these cases, too, the pasture is common to several holders, each one having a piece to mow, while they run their cows together on the portion devoted to grazing. As an example of the advantage which a cow plot may sometimes be to a labourer and his family, I may mention the case of a widow who has $3\frac{1}{2}$ acres and a very good cottage for £10 per annum. Last year she had an exceptionally good cow, and she sold milk at the rate of 6d. a gallon, amounting to £15 10s., fattening a calf which sold at £4 10s.; altogether the return was £20, besides what milk was consumed in the cottage.”

Another probable survival of the Earl of Winchilsea’s movement is thus described by Mr. Rider Haggard :—

“ The system of cottage holdings was introduced about a hundred years ago on the Burley estate” (Rutlandshire) “ and was copied by the late Lord Tollemache, who was brother-in-law of the late Mr. Finch. It is in force in the parishes of Burley, Eggleton, Hambleton and Greetham. In 1901 there lived in those parishes forty-three small occupiers, whose acreage varied from 5 acres to 40 acres, the holdings being all grass. Originally there were many more, the Hambleton cow pasture, which is 102

acres in estate, being divided into 80 cow commons. Some of the holders occupy two or more small fields, but the general custom has been for tenants to graze large fields in common, and to have separate small fields reserved for mowing hay in the winter. In the fields which are grazed in common, five roods have been taken as sufficient to keep a cow." ("Rural England," Vol. II. p. 260.)

CHAPTER XIII

STATISTICAL SUMMARY OF ENCLOSURE BY ACT OF PARLIAMENT.

IN this table the cross-heading A includes Acts up to and including the year 1801, in which year a general Act facilitating enclosure was passed ; cross-heading B, Acts from 1802-1845 ; cross-heading C, enclosures under the General Enclosure Act of 1845 and subsequent amending Acts. No Act or enclosure is included unless the enclosure was partly of arable common field, but in some few cases, as will be seen from the Appendix giving the chief particulars of each Act, the arable land formed only a trifling part of the area dealt with.

Where the area enclosed is not stated, and cannot even be approximately inferred from the wording of the Act, it is estimated on the assumption that the average area per Act where the area is not stated, is the same as for Acts relating to the same county where the area affected is stated, enclosures under the Act of 1845 being left out of account. This method, I believe, gives more satisfactory results than any other would ; but it must be confessed that in the case of Norfolk the Acts in which the area is not stated are so many, and those in which it is stated are so few, that the average obtained is not trustworthy. In this case I believe the figure arrived at is too large. The counties are arranged in order of prevalence of Parliamentary enclosures.

	Area stated.		Area not stated.		Total.		Percent- age of Area of County.
	Acts.	Acres.	Acts.	Acres.	Acts.	Acres.	
NORTHAMPTON.							
Period A	137	237,211	6	10,306	143	247,517	
„ B	40	66,807	7	12,023	47	78,830	
„ C	3	4,704	—	—	3	4,704	
Total	180	308,722	13	22,329	193	331,051	51·5

STATISTICAL SUMMARY OF ENCLOSURE. 141

	Area stated.		Area not stated.		Total.		Percent- age of Area of County.
	Acts.	Acres.	Acts.	Acres.	Acts.	Acres.	
HUNTINGDON.							
Period A	30	50,147	7	11,392	37	61,539	
" B	25	39,364	2	3,255	27	42,619	
" C	3	3,855	—	—	3	3,855	
Total	58	93,366	9	14,647	67	108,013	46·5
RUTLAND.							
Period A	20	33,857	2	3,323	22	37,180	
" B	2	2,700	—	—	2	2,700	
" C	6	7,344	—	—	6	7,344	
Total	28	43,901	2	3,323	30	47,224	46·5
BEDFORD.							
Period A	30	55,470	13	21,229	43	76,699	
" B	21	27,810	15	24,495	36	52,305	
" C	5	8,309	—	—	5	8,309	
Total	56	91,589	28	45,724	84	137,313	46·0
OXFORD.							
Period A	54	96,596	22	35,277	76	131,873	
" B	20	22,064	22	35,277	42	57,341	
" C	18	23,578	—	—	18	23,578	
Total	92	142,238	44	70,554	136	212,792	45·6
YORKS, EAST RIDING.							
Period A	108	227,009	6	12,148	114	239,157	
" B	25	42,277	7	14,173	32	56,450	
" C	4	5,193	—	—	4	5,193	
Total	137	274,479	13	26,321	150	300,800	40·1
LEICESTER.							
Period A	124	175,280	9	12,437	133	187,717	
" B	10	9,896	2	2,764	12	12,660	
" C	—	—	—	—	—	—	
Total	134	185,176	11	15,201	145	200,377	38·2

	Area stated.		Area not stated.		Total.		Percent- age of Area of County.
	Acts.	Acres.	Acts.	Acres	Acts.	Acres.	
CAMBRIDGE.							
Period A	20	45,230	3	5,789	23	51,019	
" B	21	33,885	55	106,128	76	140,013	
" C	9	8,298	—	—	9	8,298	
Total	50	87,413	58	111,917	108	199,330	36·3
BUCKINGHAM.							
Period A	47	71,323	23	35,834	70	107,157	
" B	20	33,090	10	15,580	30	48,670	
" C	6	7,014	—	—	6	7,014	
Total	73	111,427	33	51,414	106	162,841	34·2
NOTTINGHAM.							
Period A	64	112,880	18	29,217	82	142,097	
" B	17	18,596	7	11,362	24	29,958	
" C	3	3,269	—	—	3	3,269	
Total	84	134,745	25	40,579	109	175,324	32·5
NORFOLK.							
Period A	28	71,904	36	76,066	64	147,970	
" B	16	21,966	114	240,877	130	262,843	
" C	6	12,173	—	—	6	12,173	
Total	50	106,043	150	316,943	200	422,986	32·3
LINCOLN.							
Period A	175	354,048	15	29,240	190	383,288	
" B	53	90,398	11	21,443	64	111,841	
" C	2	1,331	—	—	2	1,331	
Total	230	445,777	26	50,683	256	496,450	29·3
BERKSHIRE.							
Period A	12	13,651	23	28,980	35	42,631	
" B	33	42,652	20	25,200	53	67,852	
" C	10	9,119	—	—	10	9,119	
Total	55	65,422	43	54,180	98	119,602	26·0

STATISTICAL SUMMARY OF ENCLOSURE. 143

	Area stated.		Area not stated.		Total.		Percent- age of Area of County.
	Acts.	Acres.	Acts.	Acres.	Acts.	Acres.	
WARWICK.							
Period A	85	116,919	6	7,909	91	124,828	
" B	12	10,950	8	10,546	20	21,496	
" C	3	3,235	—	—	3	3,235	
Total	100	131,104	14	18,455	114	149,559	25·0
WILTSHIRE.							
Period A	18	30,949	47	80,211	65	111,160	
" B	27	45,849	30	51,199	57	97,048	
" C	6	3,925	—	—	6	3,925	
Total	51	80,723	77	131,410	128	212,133	24·1
GLOUCESTER.							
Period A	53	78,645	30	37,724	83	116,369	
" B	18	20,616	30	37,724	48	58,340	
" C	11	4,419	—	—	11	4,419	
Total	82	103,680	60	75,448	142	179,128	22·5
MIDDLESEX.							
Period A	5	11,854	3	4,114	8	15,968	
" B	12	12,251	5	6,913	17	19,164	
" C	1	625	—	—	1	625	
Total	18	24,730	8	11,027	26	35,757	19·7
WORCESTER.							
Period A	29	36,942	10	11,317	39	48,259	
" B	9	6,066	24	27,161	33	33,227	
" C	7	4,009	—	—	7	4,009	
Total	45	46,017	34	38,478	79	85,495	16·5
DERBY.							
Period A	37	45,028	9	13,312	46	58,340	
" B	25	46,675	—	—	25	46,675	
" C	—	—	—	—	—	—	
Total	62	91,703	9	13,312	71	105,015	15·9

	Area stated.		Area not stated.		Total.		Percent- age of Area of County.
	Acts.	Acres.	Acts.	Acres.	Acts.	Acres.	
HERTFORD.							
Period A	11	20,524	4	6,103	15	26,627	
" B	8	8,464	5	7,628	13	16,092	
" C	17	10,775	—	—	17	10,775	
Total	36	39,763	9	13,731	45	53,494	13·1
YORKS, WEST RIDING.							
Period A	67	82,389	17	23,736	84	106,125	
" B	55	88,453	7	9,774	62	98,227	
" C	4	2,102	—	—	4	2,102	
Total	126	172,944	24	33,510	150	206,454	11·6
DORSET.							
Period A	9	13,704	8	8,533	17	22,237	
" B	23	20,426	8	8,532	31	28,958	
" C	6	3,786	—	—	6	3,786	
Total	38	37,916	16	17,065	54	54,981	8·7
SUFFOLK.							
Period A	4	6,400	6	9,876	10	16,276	
" B	14	13,356	24	39,505	38	52,861	
" C	5	2,450	—	—	5	2,450	
Total	23	22,206	30	49,381	53	71,587	7·5
HAMPSHIRE.							
Period A	12	15,459	23	25,649	35	41,108	
" B	13	12,856	8	10,664	21	23,520	
" C	4	1,512	—	—	4	1,512	
Total	29	29,827	31	36,313	60	66,140	6·4
SURREY.							
Period A	4	5,140	5	2,562	6	7,702	
" B	11	14,078	5	6,406	16	20,484	
" C	5	2,796	—	—	5	2,796	
Total	20	22,014	7	8,968	27	30,982	6·4

STATISTICAL SUMMARY OF ENCLOSURE. 145

	Area stated.		Area not stated.		Total.		Percent- age of Area of County.
	Acts.	Acres.	Acts.	Acres.	Acts.	Acres.	
YORKS, NORTH RIDING.							
Period A	24	33,257	9	15,279	33	48,536	
" B	14	31,171	3	5,093	17	36,264	
" C	2	1,034	—	—	2	1,034	
Total	40	65,462	12	20,372	52	85,834	6·3
HEREFORD.							
Period A	5	3,920	1	708	6	4,628	
" B	6	3,870	14	9,915	20	13,785	
" C	3	378	—	—	3	378	
Total	14	8,168	15	10,623	29	18,791	3·6
SOMERSET.							
Period A	12	16,225	3	2,644	15	18,869	
" B	23	14,623	4	3,525	27	18,148	
" C	—	—	—	—	—	—	
Total	35	30,848	7	6,169	42	37,017	3·5
STAFFORD.							
Period A	10	10,924	1	996	11	11,920	
" B	7	6,001	3	2,987	10	8,988	
" C	—	—	—	—	—	—	
Total	17	16,925	4	3,983	21	20,908	2·8
ESSEX.							
Period A	4	6,551	—	—	4	6,551	
" B	4	6,190	3	4,777	7	10,967	
" C	10	4,652	—	—	10	4,652	
Total	18	17,393	3	4,777	21	22,170	2·2
SUSSEX.							
Period A	1	1,400	—	—	1	1,400	
" B	18	13,537	4	3,145	22	16,682	
" C	2	248	—	—	2	248	
Total	21	15,185	4	3,145	25	18,330	1·9

	Area stated.		Area not stated.		Total.		Percent- age of Area of County.
	Acts.	Acres.	Acts.	Acres.	Acts.	Acres.	
NORTHUMBERLAND.							
Period A	4	9,657	—	—	4	9,657	
" B	4	12,691	—	—	4	12,691	
" C	—	—	—	—	—	—	
Total	8	22,348	—	—	8	22,348	1·7
CUMBERLAND.							
Period A	1	4,000	1	2,175	2	6,175	
" B	3	4,700	—	—	3	4,700	
" C	—	—	—	—	—	—	
Total	4	8,700	1	2,175	5	10,875	1·1
DURHAM.							
Period A	5	4,437	—	—	5	4,437	
" B	1	200	—	—	1	200	
" C	—	—	—	—	—	—	
Total	6	4,637	—	—	6	4,637	0·7
WESTMORELAND.							
Period A	—	—	—	—	—	—	
" B	4	3,237	—	—	4	3,237	
" C	—	—	—	—	—	—	
Total	4	3,237	—	—	4	3,237	0·6
CHESHIRE.							
Period A	—	—	—	—	—	—	
" B	2	3,326	—	—	2	3,326	
" C	—	—	—	—	—	—	
Total	2	3,326	—	—	2	3,326	0·5
MONMOUTH.							
Period A	1	780	—	—	1	780	
" B	—	—	—	—	—	—	
" C	3	513	—	—	3	513	
Total	4	1,293	—	—	4	1,293	0·4

	Area stated.		Area not stated.		Total.		Percent- age of Area of County.
	Acts.	Acres.	Acts.	Acres.	Acts.	Acres.	
SHROPSHIRE.							
Period A	3	1,670	—	—	3	1,670	
„ B	2	1,140	—	—	2	1,140	
„ C	—	—	—	—	—	—	
Total	5	2,810	—	—	5	2,810	0·3

Lancashire, Kent, Devon and Cornwall have no Acts for Enclosure of Common Fields.

CHAPTER XIV.

ENCLOSURE OF COMMON FIELDS WITHOUT PARLIAMENTARY SANCTION.

ON the map of England, in Chapter VII., enclosures of common field parishes by Act of Parliament before the General Enclosure Act of 1801 are shaded vertically, such enclosures from 1802 to 1845 are dotted, and subsequent enclosures under the General Enclosure Act of 1845 are black. In other words, all the shaded area represents the area of parishes which had arable common fields up to the year 1700, all the dotted and black area represents the area of parishes which had arable common fields up to 1801, and all the black area represents the area of parishes which had arable common fields up to 1845.

What about the area which is not shaded at all?

An inspection of the map yields certain striking results.

In the first place, we see that the shaded districts lie in a broad band across England from north-east to south-west, from the East Riding of Yorkshire to Dorset and the east part of Somerset.

Secondly, we see that there is a perfectly sharp line of demarcation between the shaded and the non-shaded area, running through Suffolk, Essex, passing through London, and along the border between Surrey and Kent. This line becomes indefinite as it passes through the Weald of Surrey and Sussex, but its termination can be traced in the part of Sussex which lies on the southern slope of the South Downs. In the white area to the south-east of this line there are but two shaded patches—the parishes of Iken and Orford, in Suffolk, situated close together, in the peninsula formed by the estuaries of the rivers Alde and Deben.

Thirdly, we can trace an equally sharp line of demarcation between the shaded and the non-shaded area in the south-west,

running from the Bristol to the English Channel, across Somerset and Dorset. South-west of this line there is no shaded patch—*i.e.*, there is no case of common field enclosed by Act of Parliament.

Fourthly, on the north-west side of the shaded belt, towards Wales and Scotland, there is no sharp line of demarcation between the shaded and the non-shaded area, but as one travels further and further from the central axis of the shaded area to the north-west, the shaded patches become sparser and sparser; but still some shaded patches are to be found in every English county on this side of the shaded belt, except Lancashire.

Fifthly, it is to be noticed that along the central axis of the shaded belt the vertical shading—indicating enclosure by Act of Parliament in the eighteenth century—greatly predominates, and most of all the shading is overwhelmingly vertical in the very centre of the shaded area. Dotted and black patches, indicating Parliamentary enclosure in the nineteenth century, and particularly black, indicating the latest group of Parliamentary enclosures, show more prominently in the edges or fringes of the coloured area. In other words, when the great movement of Parliamentary Enclosure began in the eighteenth century, its chief field was the very centre of the district over which it ultimately spread.

It is obvious that there must be certain broad historical reasons for these striking facts. The map, in fact, presents to us a series of definite puzzles for solution.

1. How and when was the south-eastern corner of England enclosed?

2. How and when was the south-western corner enclosed?

3. How and when was the great district in the north-west, in which Parliamentary enclosure is the exception, enclosed?

4. How and when were the numerous parishes within what we may call the Parliamentary Enclosure belt, which escaped Parliamentary enclosure, enclosed?

And lastly, there is the question which sums these up, and presents the problem on the other side—

5. Why were special Acts of Parliament necessary for the

enclosure of some three thousand of the English parishes, in the geographical position indicated by the map?

And it is important that it should be clearly understood that this is the more natural way of putting the question, because the surprising fact is not that the common field system should gradually and quietly disappear in parish A, but that it should persist in parish B, until ended by the very expensive and troublesome measure of a special Act of Parliament.

In order to proceed as far as possible from the known to the unknown, we will first consider the various methods of common field enclosure operating within the belt of Parliamentary Enclosure of common fields. But before beginning this enquiry, attention may be drawn to a ray of light which the map throws upon the social history of England in the Tudor period. The reader of the history of that period is tempted to suppose that the districts from which the greatest complaints, and still more riots and insurrections, arose against enclosures, were those in which enclosure was proceeding most rapidly. Now, the most formidable of these popular agitations began in the reign of Edward VI. in Somersetshire, and spread northwards and eastwards, growing in intensity, till it reached its climax in Ket's rebellion in Norfolk.¹ The earlier complaints also come from counties within the Parliamentary Enclosure belt—Oxford, Buckingham, Wiltshire and others. The map suggests that a possible interpretation of these popular movements is, that an industrial and economic change involving normally the enclosure of common fields was in the fifteenth and sixteenth centuries gradually spreading over the southern and midland counties; that in some parts it met with little or no resistance; but that in other parts popular resistance was roused to some features of this change, including the enclosure of arable fields, and

¹ "Can it be denied that the fyrst rysynge this yeaer was in Somersetshire, ffrom Somersetshire it entred into Gloucettershire, Wylshire, hampshire, Sussex, Surrey, Worcestershire, Essex, hertfordshire, and dyuers other places?" (John Hale's Defence, "The Commonweal of this Realm of England," Miss Lamond's edition, p. lviii.) This is to prove that the rising was not caused by the Enclosure Commission of 1549. The Commissioners were sent to Oxford, Berkshire, Warwick, Leicester, Buckingham, and Northampton.

that popular resistance was in a very great degree successful in causing the postponement of such enclosure. Briefly, a special outcry against enclosure in a particular locality shows, not necessarily that enclosure was proceeding with special rapidity there, but possibly that there it was specially obnoxious; and being there specially obnoxious, proceeded more slowly than elsewhere.

ENCLOSURE BY PRINCIPAL LANDLORD.

But to return to our own subject. We have shown that enclosure by Act of Parliament was greatly to the landlord's interest; but it is perfectly obvious that the landlord's interest was much more served by an enclosure without all the expense, loss of time, labour and anxiety involved in Parliamentary proceedings. Obviously, therefore, if one landlord could acquire all the open and commonable land in the parish, he would enclose without an Act of Parliament. The only difficulty in his way would be in arranging leases so that they should all fall in simultaneously, or, failing this, in overcoming the resistance of any tenant whose lease gave him the power of resisting, if he were unwilling to agree. We have noticed that even in recent years the common fields of Yelden in Bedfordshire have disappeared in this way; that the Duchy of Cornwall in 1876 bought out all the copyholders holding lands in Fordington Field; that Earl Manvers is similarly acquiring by degrees all the common rights in the common fields of Laxton, and the Ecclesiastical Commissioners are endeavouring in this way to procure the enclosure of Elmstone Hardwicke; that Stratton and Grimstone were thus enclosed since 1900, and that the common fields of several Berkshire parishes have thus disappeared within the last half-century. The same process can be watched on a much larger scale with regard to common rights over commons proper. The buying up of the rights of commoners over Dartmoor by the Duchy of Cornwall is one striking example; similar purchases of common rights over the

Wiltshire downs on a very large scale have come into notice through the approach to Stonehenge being affected.

The enclosure of common fields in this way is proceeding slowly merely because the remains of common fields are now so small.

And it is obvious that through the last two hundred years the restraints of law and public opinion upon the freedom of the country squire or great landowner, in doing as he likes with the villages under his control, have been gradually and continuously strengthened. In looking back over the nineteenth and eighteenth centuries, we are looking back at a greater and greater proportion of local autocratic power accompanying any given degree of local pre-eminence in wealth and landed property.

If we look back to the beginning of the eighteenth century we find the principles generally accepted by the landowning class with regard to the general management of their estates, and particularly with regard to common fields, thus clearly laid down by Edward Lawrence in "The duty of a Steward to his Lord":—

Article XIV. "A Steward should not forget to make the best Enquiry into the Disposition of any of the Freeholders within or near any of his Lord's Manors to sell their Lands, that he may use his best Endeavours to purchase them at as reasonable a price as may be for his lord's Advantage and Convenience . . . especially in such Manors where Improvements are to be made by inclosing Commons and Common fields . . . If the Freeholders cannot *all* be persuaded to sell yet at least an Agreement for Inclosing should be pushed forward by the Steward" (p. 9).

"The Steward should not suffer any of the Lord's lands to be let to Freehold Tenants within or near his Lord's Manor" (p. 34).

"The Steward should endeavour to lay all the small Farms, let to poor indigent People, to the great ones" . . . but "It is unwise to unite farms all at once, because of the odium and increase of Poor-rates. It is much more reasonable and popular to stay till such farms fall into Hand by Death" (p. 35).

And to facilitate this process, "Noblemen and Gentlemen should endeavour to convert copyhold for lives to Leasehold for lives" (p. 60).

The significance of this last recommendation may be illustrated by the passage in William Marshall's account, in "Agriculture of Gloucestershire," published about sixty years afterwards, of the Cotswold Hills:—

"Thirty years ago this district lay almost entirely in an open state; namely in arable common field, sheep-walk, and cowndown. At present it may be said to be in a state of inclosure, though some few townships yet remain open.

"The difficulties of Inclosure were not, in this case, numerous or great. The sheep-walks and cowndowns were all of them stinted by 'yardlands' in the arable fields: there was not, perhaps, one unstinted common on these hills. They were, formerly, many of them, or all of them, occupied by leasehold tenants for three lives renewable. A species of tenancy I have not met before. Many of these leaseholds had fallen in. The removal of those which remained, was" (*sic*: he means, of course, "removed") "the main obstacle of inclosure."

Because the number of Acts for Enclosure gradually increases through the eighteenth century, and reaches its maximum at the opening of the nineteenth century, it has been hastily assumed by some that the process of enclosure was similarly accelerated. But it is on *a priori* grounds at least as probable that there was no acceleration in the rate of extinction of common fields, only a gradual change in the prevailing method of procedure.

Thus very few Acts of Enclosure are extant previous to 1727, the year in which Edward Lawrence recommends to Stewards and Landlords a vigorous enclosure campaign. That that campaign was being carried on at the time can be shown by two contemporary extracts from writers on opposite sides. The Rev. John Laurence of Yelvertoft, in the "New System of Agriculture," 1726, writes:—

"The great quantities of ground that have been of late and are daily inclosing, and the increase of Rent that is everywhere

made by those who do inclose, sufficiently demonstrate the benefit and use of Inclosures. In the Bishopric of Durham nine parts in ten are already inclosed ”¹ (p. 45).

John Cowper, in “Inclosing Commons and Common fields is contrary to the interest of the Nation ” says:—“I myself within these 30 years past ” (*i.e.*, 1702—1732), “have seen above twenty Lordships or Parishes inclosed . . . I have been informed by an eminent Surveyor that one third of all the land of England has been inclosed within these 80 years.”

Perhaps what the eminent Surveyor said to John Cowper is not very convincing evidence. But in considering the estimate of the amount of enclosure in the “last 80 years,” *i.e.*, from 1652, the first year of peace after the Civil War, to 1732, the time when John Cowper wrote, we have to bear in mind, firstly, that there was an important enclosure movement going on in the Commonwealth period; and secondly, that in 1660, with the Restoration, the country gentry came by their own again. The King’s ministers during the reigns of Charles II., James II., William III. and Anne would scarcely have dared, even if they had desired, to check any proceedings on the part of landowners, with the object of raising rents. The whole policy of Parliament was, in fact, in sympathy with this object, as may be seen from all the legislature affecting agriculture.

For the first part of this period there is further evidence of the progress of enclosure in John Houghton’s “Collection for the Improvement of Husbandry and Trade.” In repeated issues he strongly advocates Enclosure; in that for September 8, 1681, he says: “Oh that I had sufficient influence to put it ” (*i.e.*, a General Enclosure Act) “to the trial, if it did not succeed I’d be content not to be drunk this seven years ” . . . “Witness the many enclosures that have of late been made, and that people are daily on gog on making ” (pp. 15, 16). It will be remembered that a General Enclosure Act for Scotland was passed in 1695.

¹ This statement is confirmed by the Board of Agriculture reporter: “In this county the lands, or common fields of townships, were for the most part inclosed soon after the Restoration.” (Joseph Granger, “Agriculture of Durham,” 1794.)

To sum up, it is clear that the Parliamentary enclosure of a given parish indicates that the lord of the manor, or principal landlord, had not secured such a complete or preponderating influence over the parish as to enable him to effect an enclosure without an Act of Parliament.

ENCLOSURE BY YEOMEN.

And yet, on the other hand, it does not appear that the absence of any lord of the manor, or of any single landowner superior in wealth to the others in the parish was favourable, through the seventeenth, eighteenth and nineteenth centuries, to the continuance of common fields, except where many of the properties were extremely small.

We have seen that the Ecclesiastical Commissioners, in Elmstone Hardwicke, while desiring themselves to enclose the parish, discourage enclosure by the tenants on their own account, by raising the rents to a prohibitive extent. Similarly Edward Lawrence in 1727, while urging, as we have seen, the steward to procure a general enclosure of his lord's manor, declares that it is the duty of the steward, particularly if his lord is the owner of the Great Tithe, to prevent gradual enclosure by yeomen—"He should be ever on his watch to prevent (if possible) the Freeholders inclosing any part of their land in the common fields (Article xxiv.)." "Partial enclosure should never be permitted without a general agreement to do the whole."

The objection of the Tithe Owner to enclosures in the common fields was that by increasing the pasture, and decreasing the arable area, they diminished the produce of grain and so diminished the tithe. John Houghton (September 16, 1681, p. 16) also refers to the objection of the tithe owning clergy to enclosure. And this objection was probably one of the strongest forces against enclosure at that time.

Again, going back a century and a quarter, John Norden's "Book of Surveying," published about 1600, in one place recommends general enclosure, on the ground that "one acre enclosed is woorth one and a half in Common, if the ground be

fitting thereto" (Book III., p. 97), in another declares "Also enclosures of common fields, or meddowes in part, by such as are most powerful and mighty, without the Lord's licence, and the Tenants' assents, is more than may be permitted" (*ibid.*, p. 96).

The reason of course is, firstly, that the holder of lands in common fields or common meadows, who fenced his holding, or parts of it, thereby prevented the other holders from exercising their rights of pasturing their cattle upon the fenced portions, without giving up his recognised right to pasture cattle on his neighbours' holdings, very likely indeed turning out all the more cattle in the summer and autumn, because better supplied with winter feed; and, secondly, because the shade of his hedges, if he set quickset hedges, injured his neighbours' crops. In "Select pleas in the Manorial Courts" we find numerous cases of complaints against manorial tenants for attempting to make hedges, banks, or such barriers.

At Bledlow, in Northamptonshire, "it is presented that John Le Pee has unlawfully thrown up a bank" in 1275 (p. 23). In Hemingford (Huntingdon) that "William Thomas Son has planted willows in the bank unlawfully" in 1278 (p. 90), and in the same manor "Elias Carpenter has wrongfully planted trees on a boundary" (p. 92). In Weedon Beck (Northamptonshire) in 1296 "Walter Mill complains of John Brockhole and says that he has raised a wall and hedge between their tenements to his damage."

One is tempted to associate the early and complete enclosure of Kent, without Acts of Parliament, with the proverbial wealth and importance of the Kentish yeomen, and the custom of Gavelkind (*i.e.*, the equal inheritance of landed property by all sons), which necessarily tended to multiply small properties.

William Marshall's description of the enclosure of the Vale of Pickering, the most fertile part of the North Riding of Yorkshire, occupying the southern slopes of the Yorkshire Wolds, shows a similar association. In "Rural Economy of Yorkshire," published in 1788, we read:—"A century ago the marginal townships lay perhaps entirely open, and there are vestiges of common fields

in the area of the vale. The West Marshes, church property, have been longer under inclosure; and the central townships were probably inclosed long before those of the margin; the soils of that part being adapted to grass; and while the surrounding country lay open, grass land was of singular value. At present the entire vale may be said to be in a state of inclosures (p. 17).

“Lands are much in the hands of small owners, in general, in the occupation of yeomanry; a circumstance, this, which it would be difficult to equal in so large a district” (p. 19).

He notices (p. 20) that it was the custom to divide lands among all the children, and (p. 24) that the custom of sale of tenant right existed.

“In the present century, more especially in the last fifty years, enclosure has made a rapid progress. . . . In my own remembrance more than half the vale lay open” (p. 50).

The township of Pickering itself lay open at the beginning of the century. It then had 2376 acres of common field arable, stinted pastures, and 3700 acres of common. “The common fields and common meadows have been gradually contracting by amicable changes and transfers, and are now, in a manner, wholly inclosed. The stinted pastures have, at different times, been inclosed ‘by commission,’ namely, by the unanimous reference to arbitrators.”¹

In general, it may be said, that the Parliamentary enclosure of a given parish indicates that the manorial authority was exercised during a long period antecedent to the enclosure, to prevent gradual enclosure by individual tenants; and that the existence of important rights and properties belonging to the lord of the manor prevented a common agreement to enclose by

¹ An older description of piecemeal enclosure is given by John Houghton: “Would they who plough in champain grounds but change their little parcels; would they who have 6 or 8 acres together make a ditch of 6 or 7 foot wide and deep, and fill it if they would with water, and carry away the bank that it might not be thrown in again, hedges might chance to thrive, and in 2 years (tho’ they to please the people might at certain times lay it open) they would raise more money than they use to do in six.” (Collections, September 16th, 1681, p. 16.) This gives me a pretty fair idea both of the profit and of the unpopularity of such enclosure at the time.

the actual cultivators of the soil from being reached and put into execution.

It may also be noticed that in a parish or township where there is no one principal landlord, but a number of landowners owning moderate properties, there is comparatively little likelihood of the net profit of an Enclosure Act seeming to any one owner worth the trouble of initiating a movement to promote one; and a comparatively greater likelihood of some owner or owners being found disposed, from private grudges or on public grounds, to oppose the proceedings.

This distribution of property in a common field parish increases the probability that enclosure will proceed in a piecemeal fashion, instead of by an Act.

ENCLOSURE UNDER THE GENERAL ACTS OF 1836 AND 1840.

In 1836 a general Act (c. 115) was passed "to facilitate the Inclosure of Open and Arable Fields in England and Wales." By this Act two-thirds in number and value of the proprietors of lands and common rights in Arable Common Fields could appoint Commissioners for Enclosure, provided such fields were not within ten miles of the centre of London, or three miles from the centre of some town of over 100,000 inhabitants, or within certain smaller distances of smaller towns. Enclosure so effected was only recorded locally. Awards had to be deposited in the parish churches; but no confirming Act was needed. If seven-eighths in number and value of the proprietors were agreed upon enclosure, it was not necessary for them even to appoint Commissioners, if they could come to an agreement as to the redistribution of properties.

In 1840 an amending Act (c. 31) was passed, providing that persons who took possession of the allotments awarded them in enclosures under the Act of 1836 must be deemed to have waived the right of appeal from the award. The scope of the Act of 1836 was also extended to Lammas meadows.

As these Acts were in operation from 1836 to 1845, the enclosures effected by special Acts of Parliament during this

period must have been greatly outnumbered by those effected during that period without being recorded by the central Government. Between 1845 and 1852 the enclosure of lands which were neither commonable all the year round nor subject to any common rights not regulated by a stint, could be effected by the Enclosure Commissioners without being reported to Parliament; but after 1852 the Enclosure Commissioners had to report all their proceedings.

ENCLOSURE IN CORN-GROWING AND PASTORAL DISTRICTS.

The arable common fields, and in consequence the commonable meadows with intermixed ownership, which were situated in districts predominantly pastoral, tended, other things being equal, to be divided and enclosed earlier than the common fields in the predominantly corn-growing districts. For this there are various reasons:—

Firstly, as may be seen from the maps of Castor and Ailesworth, of Laxton, of Braunton (p. 250), or of any maps of any common-field parishes, piecemeal enclosure tends to begin in the arable fields (*a*) close to the village, and (*b*) on the outermost margin of the fields. The greater the extent of the fields, the longer, *ceteris paribus*, will it be before piecemeal enclosure completely obliterates them.

Secondly, enclosure in a pastoral district does not arouse the same resentment and popular resistance that it does in a corn-growing district. This is easily seen from all the controversial writings of the whole period during which enclosure has been a matter of controversy, up to about the middle of the nineteenth century. It was not enclosure as enclosure that offended, but enclosure as causing, or as being intended to result in, the laying down of arable land in grass; as being, in the words of Joseph Bentham of Kettering, “the inhuman practices of madded and irreligious depopulators”¹ which robbed the king of subjects and the country of corn and cattle. Those who enclosed were “monsters of men, dispeoplers of towns, ruiners

¹ “The Society of the Saints,” p. 67.

of the commonwealth as far as in them lyeth, occasioners of beggars and beggery, cruell inclosiers, whose Adamantine hearts no whit regard the cries of so many distressed ones.”¹ Such denunciation would be out of place, and the passions which gave rise to it would never have arisen, in a predominantly pastoral district, because there would be in such a district comparatively few persons thrown out of employment even if the enclosure were of the arable fields only; and because it is scarcely possible that while enclosure of the arable fields was going on, there would not be simultaneous enclosure of waste land, which would have to be repeatedly ploughed and tilled even if the intention were to ultimately convert it into permanent pasture. In other words, while enclosure in a predominantly corn-growing district is associated with “depopulation,” in a pastoral district it is associated with increased employment, increased local population, a larger production of food, and on the whole increased local prosperity. Thus, though there was a rebellion in Devon and Cornwall in 1549, the same year as Ket’s rebellion, enclosure was not one of the complaints of the rebels. And this was not because enclosure had not begun in Devon and Cornwall, because, as a matter of fact, enclosure had advanced further in Devon and Cornwall than in most other counties. The attitude of the Cornishmen is thus expressed by Carew:—“They fal everywhere from Commons to Inclosure, and partake not of some Eastern Tenants envious dispositions, who will sooner prejudice their owne present thrift, by continuing this mingle-mangle, than advance the Lords expectant benefit, after their terme expired.”²

Thirdly, there was, during one period in the sixteenth century, a law specially guarding the corn-growing districts from enclosure, from which other districts were exempt.

The Statute 7 Henry VIII., c. 1, was the Depopulation Act in force for the 20 years 1516—1536. It derives special importance from the Inquisition into Enclosures which followed its enactment, in 1517. It applies only to parishes “Whereof the more

¹ “The Society of the Saints,” p. 98.

² Carew, “Cornwall” (1600), p. 30.

LELAND'S ITINERARY

■ Moor, Fen, Marsh, Forest or Heath.
 ▨ Enclosed.
 ▩ Champion.
 ▧ Cultivated and probably open.
 — Leland's route.

Scale 1:5,000,000 or 1 inch = 79 Stat. miles.

10 0 20 40 60 100

GATESHEAD
 DURHAM
 Sunderland
 Bishop Auckland
 Barnard Castle
 Richmond
 Whitby
 Northallerton
 Scarborough
 Kendal
 Lancaster
 Rison
 Malton
 Knarborough
 LEEDS
 Wakefield
 Preston
 Thorne
 Manchester
 Rotherham
 Doncaster
 Worksop
 Northwich
 Mansfield
 Lincoln
 Southwell
 Slough
 Whitchurch
 NOTTINGHAM
 Loughborough
 Shrewsbury
 Lichfield
 Stamford
 Leicestershire
 Leicester
 Birmingham
 Coventry
 Warwick
 Worcester
 Evesham
 Gloucester
 Cheltenham
 Stroud
 Gloucester
 Bristol
 Minehead
 Wells
 Frome
 Bath
 Marlborough
 Salisbury
 Winchester
 Southampton
 Portsmouth
 Bideford
 Barnstaple
 Torrington
 Exeter
 Bodmin
 Totnes
 Dartmouth
 Plymouth

- [illegible]

[illegible]

part was or were used and occupied to tillage and husbandrie"; and it required the land to be tilled "after the maner and usage of the countrey where the seyd land lyeth." This restriction drops out of the next Depopulation Act, 27 Henry VIII., c. 22, passed in the year 1536.

In the year 1536 Leland, the King's Antiquary, began his Itinerary, which lasted till 1542. Whether in consequence of special instructions or not, he almost everywhere notes the condition of the country he traverses with regard to enclosure. A summary of his observations is shown in the form of a map; Devon, Cornwall, West Somerset, South Wales, Hereford, Worcester, the north-west of Warwick, South Lancashire, the country round Southampton, and near Hampton Court, with parts of Yorkshire, are shown to be the most enclosed districts which are described; and the districts described by Leland as champaign are those which were later largely enclosed by Act of Parliament.

The general movement of agricultural progress, it may safely be assumed, up to Leland's time, was from the south-east of England northwards and westwards. The extreme south-east corner was certainly very early enclosed, as one would naturally expect, but we also find remote western districts, where one would naturally expect to find old customs linger comparatively late, precede the central districts in the abandonment of the "village community," by many years.¹

Whether much of the enclosure which Leland saw in 1536 had been the work of the previous twenty years, it is of course impossible to say; but making any reasonable allowance for progress in hedging and ditching in the western counties where

¹ How long the enclosure of certain western counties preceded the enclosure of the east midlands, is shown by comparing the two following extracts. Of the former, Joseph Lee, in "A Plea for Regulated Inclosure," published 1656, asks, "Are not many places in England, Essex, Hereford, Devonshire, Shropshire, Worcester, wholly enclosed?" (p. 31). Of the latter the "General Report on Enclosures," published 152 years later, "A village of farmers and labourers surrounding a church and environed by three or four and in a few cases by five open fields, form the spectacle of Cambridge, Huntingdon, and Northampton shires, as much as on the Loire and on the plains of Moscow" (p. 25).

agriculture was mainly pastoral during those twenty years, and assuming that the Act of 1516 had effectually stopped enclosure in that period in the corn-growing districts, one can hardly resist coming to the conclusion that if Leland had made his journey in 1516 he would then also have found enclosure most advanced in those districts which were most enclosed in 1536.

What we have, then, to ask is whether the priority of enclosure in the western counties is to be attributed entirely to the fact of their being devoted more to grass and less to tillage, or whether there was some difference in the primitive village community of the west which caused cultivated land to pass more easily into the condition of exclusive ownership and separate use. Obviously we must look for the answer to this question beyond the boundaries of England. To understand the differences between the village life of those parts of England which were once the Danelagh, Mercia and Wessex, from those which were then West Wales and Strathelyde, which may be regarded as at least semi-Celtic, we must examine the purely Celtic type of village community.

But it must also be noticed that there is one characteristic feature of the typical English village community, namely the importance attached to the right of common pasturage on the fallow field, and in the other arable fields after harvest, which would probably never have developed in any part of the country where only a small proportion of the land was ploughed. There would be too little profit and too much inconvenience attached to the exercise of the right for it to have a chance of being established, or if established, of persisting.

Lastly, it seems to me impossible to account for the perfect definition of the two boundaries between parishes early enclosed, without special Acts, and parishes enclosed late by special Acts, the one in the south-east, passing through Suffolk, Essex, and between Surrey and Kent, and the other in the south-west, passing through Somerset and Dorset, except on the assumption that the enclosure movement beginning in these two corners of England, was suddenly checked when it had reached the

limits indicated, by the Tudor series of Depopulation Acts, and by the Inquisitions and other measures taken to enforce them. These Acts specially stipulated for the continuance of the ancient customary methods of tillage. A summary of their provisions which affect enclosure will be found in Appendix D.

CHAPTER XV.

RUN-RIG AND COMMON FIELD.

IT is a familiar fact that the early open field system of agriculture of Scotland, Wales, and Ireland, known as run-rig or rundale, differed in some important features from the common field system of England.

The mere fact suggests a series of questions with regard to the relationships between common field and run-rig; whether, for instance, the more complex common field system was evolved from the more simple and primitive run-rig system; or supposing the two not connected, whether a boundary can be defined on one side of which the early agriculture was of the English type and on the other of the Celtic type; and again, if so, which parts of England lie on the Celtic side of the boundary, and which, if any, of Wales and Scotland lie on the English side.

Obviously before considering such questions it is necessary to have a clear grasp of the nature of run-rig, and of the differences between it and the English system.

In the year 1695 the Scotch Parliament passed an Act allowing anyone "coterminous heritor" owning a share in a "commonty" to have his portion separate from the rest, and to enclose it; and a series of cases established a defined system of computing the share of the "commonty" to which the lord of the manor as such was entitled in lieu of manorial rights. This caused the process of the separation of intermixed properties in open fields to proceed without the intervention of special Acts of Parliament, except for Royal burghs. Also while in England under Enclosure Acts or agreements to enclose the three processes of (a) the separation of intermixed and intercommonable properties, (b) the separation of intermixed and intercommonable

holdings, and (c) the hedging or fencing of the separated properties, were accomplished by one continuous series of actions on the part of those concerned, in Scotland it was otherwise. The separation of properties where necessary was first accomplished, and for long afterwards the system of run-rig was followed by groups of tenants on the same estate. After run-rig had been abandoned, the separate holdings remained open and unenclosed, and the process of building dykes or planting hedges was carried out at a later date, and by slow degrees.

The abandonment of run-rig was general, according to the reports to the Board of Agriculture, in the lowlands of Scotland about the year 1730. In the county of Perth up to the year 1744 "the land was always occupied in run-rigg, either by the different tenants on the same farm, and sometimes by coterminous heritors. The houses were in clusters for the mutual protection of the inhabitants." (James Robertson, D.D., "Agriculture of the Southern District of Perth," 1794, pp. 22, 23.) In the northern and Highland counties the transition was naturally later. Sir John Sinclair ("General View of the Agriculture of the Northern Counties and Islands of Scotland") describes the cultivated land of the Islands as being open almost everywhere, except in the case of the "mains" or manor farms, the glebe lands, and the farms of a few principal tacksmen. Of Caithness he says, "The greater part of the arable land in this county is occupied by small farmers who possess it in *run-rig*, or in *rig and rennal*, as it is here termed, similar to the common fields of England, a system peculiarly hostile to improvement" (p. 207). But in the Orkneys "Much of the land that formerly lay in the state known in Scotland under the name of run-rig land has been divided, but much still remains in the same situation" (p. 227); and the process of enclosing had begun even in the Shetlands (p. 252).

Turning westwards, we find that in the inner Hebrides 1850 was the date at which the run-rig system finally died out, in a manner and under conditions which will demand further attention. But it survived in the Outer Hebrides to a considerably later date. A very full and interesting description by Mr.

Alexander Carmichael is given in Skene's "Celtic Scotland," Vol. III. chapter x.

"Old systems are tenacious. They linger long among a rural people and in remote places. Of these is the land system of run-rig (Mor Barann) which characterises more or less the land system of the Western Isles. The outer Hebrides are called the Long Island. They are a series of islands 119 miles in length, and varying from half-a-mile to twenty miles in breadth. This kite-like chain of forty inhabited and upwards of a hundred and fifty uninhabited islands contains a population of 40,000. Much of this land is held by extensive tacksmen on leases (Fir Baile), and there being no intermediate tenantry, the rest of the land is occupied by small tenants at will without leases. These number 4,500, the majority of whom fish as well as farm.

"The country is divided into townlands of various extent. The arable land (Fearann Grainsich) occupied by the small tenants of these townlands is worked in three ways—as crofts wholly, as crofts and run-rig combined, and as run-rig wholly. In Lewis and Harris the arable land is wholly divided into crofts; in Uist and Barra the arable land is divided in part into crofts, and in part worked in run-rig; while in the townlands of Hosta, Coolas Paipil, and the island of Heisgeir in North Uist, the arable land is worked exclusively upon the run-rig system of share and share alike. The grazing land of the tenants of each townland throughout the Long Island is held in common (in Lewis called Comhpairt).

"The soil varies from pure sand to pure moss. Along the Atlantic there is a wide plain of sandy soil called *Machair*. This merges into a mixture of sand and moss (Breacthalamh, or mottled soil), which again merges into pure moss (Mointeach) towards the Minch. As the soil is dry and sandy, if the summer is dry the crop is light. On the other hand, if the summer is moist the crop is heavy and good. In order that all may have an equal chance, the *Machair* belonging to them is equally divided among the tenants of the township. Obviously the man who is restricted to his croft has fewer advantages than the man who, together with his croft, has his share of the *Machair*,

and still fewer advantages than the man who has, rig for rig with his neighbours, the run of the various soils of his townland, which gives name to the system. Consequently a wet or dry season affects the tenant of the croft system more than the tenant of the combined system, and the tenant of the combined system more than the tenant of the run-rig system.

“The townland of Hosta is occupied by four, Ceolas Paipil by six, and the island of Heisgeir by twelve tenants. Towards the end of autumn, when harvest is over, and the fruits of the year have been gathered in, the constable calls a meeting of the tenants of the townland for Nabachd (neighbourliness). They meet, and having decided upon the portion of land to be put under green crop next year, they divide it into shares according to the number of tenants in the place, and the number of shares in the soil they respectively possess. Thereupon they cast lots, and the share which falls to a tenant he retains for three years. A third of the land under cultivation is thus divided every year. Accordingly the whole cultivated land of the townland undergoes revision every three years. Should a man get a bad share he is allowed to choose his share in the next division. The tenants divide the land into shares of uniform size. For this purpose they use a rod several yards long, and they observe as much accuracy in measuring their land as a draper in measuring his cloth. In marking the boundary between shares, a turf (*Torc*) is dug up and turned over the line of demarcation. The *torc* is then cut along the middle, and half is taken by the tenant on one side, and half by the tenant on the other side, in ploughing the subsequent furrow; similar care being afterwards exercised in cutting the corn along the furrow. The tenant's portion of the run-rig is called Cianag, and his proportion of the grazing ground for every pound he pays Coir-sgoraidh.

“There are no fences round the fields. The crop being thus exposed to injury from the cattle grazing along the side, the people have a protecting rig on the margin of the crop. This rig is divided transversely into shares, in order to subject all tenants to equal risks. . . . Occasionally, and for limited bits

of ground, the people till, sow, and reap in common, and divide the produce into shares and draw lots. This is called *Comachadh*, promiscuous. The system was not uncommon in the past, though now nearly obsolete.

"In making their own land arrangements for the year, the tenants set apart a piece of land towards the support of the poor. . . .

"In reclaiming moor-land the tenants divide the ground into narrow strips of five feet wide or thereby. These strips, called lazy-beds (*Feannagan*, from *feann*, to scarify), the tenants allot among themselves according to their shares or crofts. The people mutually encourage one another to plant as much of this ground as possible. In this manner much waste ground is reclaimed and enhanced in value, the ground hitherto the home of the stonechat, grouse, snipe and sundew, is made to yield luxuriant crops of potatoes, corn, hay and grass. Not unfrequently, however, these land reclamations are wrested without acknowledgment from those who made them.

"The sheep, cattle and horses of the townland graze together, the species being separate. A tenant can only keep stock conformably to his share in the soil. He is however at liberty to regulate the proportions of the different kinds, provided that his total stock does not exceed his total grazing rights. He can keep a greater number of one species and a corresponding smaller number of another. Or he can keep a greater number of the young, and a corresponding less number of the old of the same species, or the reverse. About Whitsuntide, when the young braird appears, the people remove their sheep and cattle to the grazing ground behind the arable land. This is called clearing the townland. The tenants bring forward their stock (*Leibhidh*) and a souming (*Sumachadh*) is made. The *Leibhidh* is the tenant's stock, the *Sumachadh* the number he is entitled to graze in common with his neighbours. Should the tenant have a croft, he is probably able to graze some extra stock thereon, though this is demurred to by his neighbours. Each 'penny' of arable lands has grazing rights of so many soums. Neither, however, is the extent of land

in the penny, nor the number of animals in the soum uniformly the same."

A soum consists of a cow and her progeny; in some places the cow and her calf only: in some a cow, her calf, her one-year-old progeny (called a *stirk*) and her two-year-old *quey*; in other places again, the cow, calf, *stirk*, *quey* and a three-year-old heifer. At four years old the heifer becomes a cow, and so originates a fresh soum.

In making souming calculations, it is assumed that one cow is equal to two *queys* or to four *stirks* or to eight calves, or to one heifer and one *stirk*. Also one cow is equal to eight sheep, or to twelve hogs (one-year-old sheep) or to sixteen lambs or to sixteen geese. One mature horse is equal to two cows; also to eight foals, or to four one-year-old colts or fillies, or to two two-year-olds, or to one three-year-old and one colt or filly. The cow is entitled to her calf; and if one tenant has two cows without calves they are entitled to take one *stirk* instead.

Those tenants who are found at the souming to have overstock must either buy grazing from a tenant who has understock or may be allowed by the community to let the overstock remain on the grass till he can dispose of it. In that case payment must be made, according to a recognised code, into a common fund which is used to buy bulls or tups or for some other common purpose. The souming is amended at Lammas, and again at Hallowtide.

In Lewis and Harris similar arrangements with regard to stock obtain among the *crofters*, the amount of stock allowed to each crofter being regulated according to the rent paid.

During the early summer the herds are put at night into enclosures, according to the species, and two tenants, chosen in rotation, keep watch to prevent them from straying over the open fields. If they escape, the watchmen are fined and have to make any damage good, but the fines, and the amount assessed for damages, both go into the common fund.

Early in June, the tillage being finished, the people go to the hill grazing with their flocks. The scene is vividly described by Mr. Carmichael, the general excitement, the men shouting

directions, the women knitting and chatting, the children scampering about. Sheep lead the procession, cattle come next, the younger ones preceding the older, the horses follow. Implements and materials are carried to repair the summer huts. When the grazing ground is reached the huts are repaired, fires lit, and food cooked. The people bring forward their stock into an enclosure, and the constable and another man stand at the gate of the enclosure and count each man's stock separately to see that he has brought only his proper souming. Then the cattle are turned out to graze, and the "Shealing Feast" is celebrated by the singing of hymns and the eating of cheese. The summer huts are of a beehive shape, and are sometimes constructed of stone, and sometimes of turf and frail materials.¹

Each tenant under the run-rig system is responsible for his own rent only. Formerly the rent was paid partly in money, partly in meal, partly in butter and cheese, and partly in cattle.

The common functionaries, the shepherd, cattleherd and marchkeeper, are paid by their co-tenants for their services in seaweed, land and grazing. The business of the marchkeeper is to watch the open marches of the townland and prevent trespass. He may also have the duty of watching the shore to see when the seaweed is cast upon it. Then he erects a pole with a bunch of seaweed at the end, and the people come down to the shore to collect the weed for manure. No tenant is permitted to take seaweed till his neighbours arrive, unless the custom prevails of collecting the weed in common, dividing it into shares and casting lots.

When required by the proprietor or the people, the constable convenes a meeting of the inhabitants. At such meetings the questions in dispute are settled, after full discussion, by votes; lots are drawn if the votes are equal.

"The closer the run-rig system is followed, the more are

¹ The ruins of beehive huts all over Dartmoor, and of enclosures like Grims-pound, are conceivably evidence of similar customs in Devonshire. Now, however, the care of the cattle pastured on Dartmoor by the occupiers of adjacent farms, is a distinct occupation. Those who follow it are called "Moor-men."

the unwritten customs and regulations observed. The more intelligent tenants regret a departure from them. . . .

“The houses of the tenants form a cluster. In parts of Lewis the houses are in a straight line called *Straid*, street, occasionally from one to three miles in length. They are placed in a suitable part of the townland, and those of the tenants on the run-rig system are warm, good and comfortable. These tenants carry on their farming operations simultaneously, and not without friendly and wholesome rivalry, the enterprise of one stimulating the zeal of another. . . .

“Not the least pleasing feature in this semi-family system is the assistance rendered by their neighbours to a tenant whose work has fallen behind through accident, sickness, death, or other unavoidable cause. . . .

“Their mode of dividing the land and of equalising the stock may seem primitive and complex to modern views, but they are not so to the people themselves, who apply them amicably, accurately and skilfully. The division of the land is made with care and justice. This is the interest of all, no one knowing which place may fall to himself, for his neighbour's share may become his own three years hence.

“Whatever may be the imperfections, according to modern notions, of this very old semi-family system of run-rig husbandry, those tenants who have least departed from it are the most comfortable in North Uist, and, accordingly, in the Outer Hebrides.”

Mr. Carmichael informs me that the whole of this description held good at least up to May, 1904.

The brief descriptions and other references to the run-rig system of the agricultural writers whom Sir John Sinclair and Arthur Young enlisted in the service of the Board of Agriculture at the end of the eighteenth, and the beginning of the nineteenth century, are sufficient to show that in all essential features it was fundamentally identical in different parts of Scotland. Sir John Sinclair's own description is meagre and unsympathetic: “Were there twenty tenants and as many fields, each tenant would think himself unjustly treated unless he had a proportionate share in each. This causes treble labour, and as they

are perpetually crossing each other, they must be in a state of constant quarrelling and bad neighbourhood. In order to prevent any of the soil being carried to the adjoining ridge, each individual makes his own ridge as high as possible, which renders the furrow quite bare, so that it produces no crop, while the accumulated soil in the middle of the ridge is never stirred deeper than the plough. The proprietors begin to see the inconveniences of this system, and in general intend to remedy it, by dividing the land into regular farms."¹

This is obviously a description of run-rig in a state of decrepitude; the communal spirit has died out of it, and apparently the practice of periodic redivision of the land has fallen into desuetude. In another passage² we find a variation of the method of guarding the crops which again, when compared with Mr. Carmichael's description of the "promiscuous rig," appears to show the decay of the system. "The tenants have a miserable sort of fence, made of turf, which separates their arable land from the adjoining waste; but it requires constant repairs, and when the corn is taken off the ground, is entirely neglected, and the country becomes one immense common, over which immense numbers of cattle are straggling in search of food, greatly to the injury of the soil."

William Marshall, the rival as an agricultural writer and bitter critic of Arthur Young, supplied the "General View of the Agriculture of the Central Highlands of Scotland." He supplies us with one significant hint, if we need it, with regard to the fundamental basis of run-rig: "Not the larger farms only, but each subdivision, though ever so minute, *whether 'plow-gait,' 'half-plow,' or 'horse-gang,'* has its pittance of hill and vale, and its share of each description of land, as arable, meadow, green pasture and muir" (p. 29). By the way, even smaller farms than the "horse-gang," i.e., one quarter of the arable land which could be ploughed by a four-horse plough,

¹ "General View of the Agriculture of the Northern Counties and Highlands of Scotland," p. 205.

² *Ibid.*, p. 207. This passage and the next occur in the description of Caithness, but they appear to be intended to apply to the whole district.

together with the corresponding proportion of meadow, pasture and moor, were to be found on the Royal burghs where inter-mixed ownership was exempt from the operation of the Act of 1695. On these the smallest farms consisted of a "horse's foot" of land, *i.e.*, one sixteenth part of a "plow-gait."

Dr. James Robertson defines run-rig as "Two or three or perhaps four men yoking their horses together in one plough, and having their ridges alternately in the same field, with a bank of unploughed land between them, by way of march."¹

James McDonald, writing in 1811 a later report on the Agriculture of the Hebrides, published in 1811, gives an account of the beginning of the disappearance of run-rig in those islands. "Mr. Maclean of Coll insisted upon some of his tenants dividing among them the land which they formerly held in common, or run-rig, and which they were accustomed for ages to divide annually by lot, for the purposes of cultivation. They obeyed with great reluctance, and each tenant had his own farm to himself. Three or four years' experience has convinced them now that their landlord acted wisely. . . . The same thing happened on various other estates, and especially in Mull, Tyree and Skye" (p. 133). But the general disappearance of run-rig in these islands took place about the middle of the nineteenth century, and was the consequence of the temporary prosperity produced by the rise of the kelp industry. This led to extreme subdivision of holdings by sub-letting, the body of small crofters so created relying in the main upon the kelp industry for a livelihood, and using their crofts as a subsidiary means of subsistence (Skene, "Celtic Scotland," Vol. III., ch. x.).

It is clear that the two essential features of run-rig are (1) that it is based upon co-aration, several farmers yoking their horses to one plough, and tilling the land in partnership; just as the English common-field system was also based upon co-aration, with the difference that in England, in general, at the time that co-aration was practised, the plough was generally drawn by eight oxen instead of by four horses.

¹ "Agriculture of the Southern Districts of Perth" (1794).

(2) That run-rig has a special distinctive feature in the periodical division and re-division of the land, and that in the Hebrides, at least, this feature survived after co-aration had become obsolete.¹ In this respect the Scotch agricultural community resembles that of Great Russia, where also the periodical re-division of the open fields, so as to make the shares proportional to the working power of each family, persists after co-aration has disappeared.

That throughout the British Isles, and indeed throughout Northern Europe, the earliest tillage of the soil by ploughs was accomplished by the method of co-aration, scarcely admits of doubt; nor is it easy to doubt that before the possibility of improving the crop by manure was discovered, there was no permanent occupation by one of the partners in the ploughing, of any particular set of strips so ploughed.

But it is also obvious that whereas we know that in some places, as in the Hebrides and in Russia, the idea of common occupation of the land persisted, after co-aration had ceased, and displayed itself in the form of periodic or occasional re-division of the arable land, it is equally possible for the permanent occupation of certain strips of land to be definitely allotted to some individuals, while the practice of co-aration is still persistent among other individuals of the same community. In the latter case when individual cultivation begins, the peasant who drives his own plough team, drives it over the same set of strips of land as had previously been ploughed by the common plough; he feels more than ever that they are his own, and that he must guard them against encroachment; though, perhaps, he is not averse, when occasion offers, to widen his strips at the expense of his neighbours. The consequence is that by the time individual cultivation has entirely superseded co-operative ploughing in any particular village, freeholds and copyholds are definitely arranged as we know them in the English common fields.

¹ Mr. A. N. Palmer, in his important work, "A History of Ancient Tenures of Land in the Marches of N. Wales," expresses the opinion that co-aration and the shifting of land disappeared simultaneously in North Wales, and had come to an end by the reign of Henry VI. (p. 36, note).

Particularly is this likely to be the case if a long interval of time elapses between the first beginning of individual ploughing and the last disappearance of combined ploughing.

If on the other hand the practice of periodic re-allotment of the land persists up to the time when co-aration ceases, it will obviously be natural for the peasants when they dissolve their plough-partnership, to allot their land to one another with some regard for convenience as well as equity. They will naturally—as Sir John Sinclair noticed they did—allot to each household a share in each particular sort of soil which had previously been cultivated in common, but each man's share in each field is likely to be allotted to him in one piece, or at least in a few, and not in a number of strips intermixed with those of his neighbours. Then when at a later period hedging and ditching begin, each man has his land in a form convenient for enclosure; and by enclosing it he forms a series of irregular fields, roughly square, or when oblong, with the length not many times exceeding the width. No throwing of the parish into the melting pot, either by a private Act of Parliament or by a voluntary submission to a Commission, was necessary in order to effect enclosure.

On the one hand, then, it is obvious that the great inequality of the holdings held by servile and semi-servile tenures from the time of Domesday onwards, was favourable to the creation of the conditions necessary to make piecemeal enclosure difficult. The *socmanni* or *francigenae*, who held a whole carucate or ploughland apiece, presumably also had, as a rule, a whole ploughteam, and were able to plough for themselves, while their neighbours, who held yardlands and half-yardlands, *i.e.*, one-quarter or one-eighth of a ploughland, could only have their lands ploughed by the common village ploughs. As soon as the *socmanni* and *francigenae* began to permanently improve the soil, as for instance by marling, the beneficial results of which were believed in the eighteenth century to last for at least twelve years, they would naturally become a practically insuperable obstacle not only to any re-division of the land, but also to any minor variation in the exact position of the ridges

which comprised the different holdings. Once one such holding was definitely located, the fixing of all other holdings which were intermixed with it would follow: every increase of certainty would be an encouragement to any given tenant to improve his land, and every expenditure of effort by a tenant on permanent improvement would be an additional motive to him to resist any changes in the position of his ridges.

On the other hand, in the case of land first brought into cultivation at a later date, when servile tenures had become obsolete, by "tenants at will" of the lord of the manor, the assured continued occupation of a defined set of ridges in land so reclaimed would not arise, even if the original tenants practised co-aration; and if the original cultivators worked independently, of course no intermixture of holdings would ever arise on such holdings.

Hence the very close connection between copyholds, *i.e.*, the commuted servile tenures, and common fields, which was observed as long as common fields were numerous.

To sum up, it is clear that on *a priori* grounds there are certain defined conditions in which alone we can expect to find the peculiarly English type of open-field arable, the type which most obstinately resists dissolution, persisting until destroyed by (a) the absorption of all properties into the hands of a single owner, or (b) a general valuation and redistribution of properties and holdings. These are that the land must originally have been tilled by the method of co-aration, and that co-aration must have persisted until after some at least of the holdings had become a definite set of strips of land, the position of which was not shifted from year to year. These conditions, as Seebohm shows, are the characteristics of the typical English village community. But they are not to be found in open arable fields of the Celtic type of run-rig; and they are not to be expected in lands first brought into cultivation after the disappearance of serfdom.

We may therefore expect to find enclosure of arable land proceeding easily, without the necessity for special Acts of Parliament, and at a comparatively early stage of social

evolution, on the one hand in Devon and Cornwall, the counties bordering on Wales, and in Cumberland, Westmoreland and Lancashire; and on the other hand in districts like the Weald of Surrey, Kent and Sussex.

That this inference agrees with the facts will be shown in detail.

Traces of run-rig, however, both in the form of characteristic terms, and of records of local custom, are not confined entirely to the counties within or near the borders of Wales or West Wales. The Act (1770 c. 59) for Matton in Lincolnshire has for its object to enclose certain commons and "forty-five acres or thereabouts of antient Toftheads and small Inclosures called the Town Rig." To the Act for Barton in Westmoreland (1819 c. 83), which encloses "certain open common fields or town fields," which mentions "the dales or parcels of land in the said common fields or town fields," there is a parallel in the Act (1814 c. 284), for Gateshead in Durham to enclose "certain common or town fields, and other commonable lands and grounds." These phrases are all reminiscent of the fact that lands held, or which had previously been held, in run-rig in Scotland, or in rundale in Ireland, are known as town lands.¹

Much more striking, however, is the local custom at Stamford, described in the following passage by Arthur Young: "Lord Exeter has property on the Lincoln side of Stamford, that seems held by some tenure of ancient custom among the farmers, resembling the *rundale* of Ireland. The tenants divide and plough up the commons, and then lay them down to become common again; and shift the open fields from hand to hand in such a manner, that no man has the same land two years together; which has made such confusion that were it not for ancient surveys it would now be impossible to ascertain the property" ("General View of the Agriculture of Lincolnshire," p. 27).

¹ "The Town Fields" indifferently with "The Common Fields" is the name by which the ancient arable area of Wrexham is called in old deeds, and the same name is applied to the ancient common fields in many places in North Wales. (See A. N. Palmer, "History of Ancient Tenures of Land in the Marches of North Wales," pp. 1, 2.)

William Marshall's comment is perhaps worth adding: "In regard to commons, a similar custom has prevailed, and indeed still prevails, in Devonshire and Cornwall; and with respect to *common fields*, the same practice under the name of 'Run-rig' formerly was common in the Highlands of Scotland, and, perhaps in more remote times, in Scotland in general."

Lastly, it is to be noticed that there is no mention in any description of run-rig of the arable fields being used as a common pasture after harvest, or during a fallow year. We shall find later the same absence of this custom characteristic of English Common Field, from open arable fields in Cumberland, Westmoreland, Lancashire, Wales and Devonshire; *i.e.*, from the Celtic part of England and Wales. This may, of course, be a mere coincidence, and the true explanation may in each be that the stubble was not needed for pasture. But in any case the absence of rights of pasture over arable fields removes a great obstacle to piecemeal enclosure.

EVERY YEAR LANDS.

In the chapter on Norfolk agriculture it is shown that the distinction between Infield and Outfield, which was characteristic of the agriculture of the Lothians, was also characteristic of the agriculture of Norfolk; and that a great part of the uninclosed intermixed arable land was not subject to rights of common, and was made to bear a crop every year, such land being known as Every Year lands, Whole Year lands, or Infields.

Here again we were obliged to look to Scotland for further light upon the customs of an English county, but in this case we cannot attribute the resemblance between the customs of Norfolk and the east of Scotland to a common Celtic influence. The hypothesis would be a difficult one, and a different explanation presents itself.

Seeböhm points out that the ancient characteristic agriculture of Westphalia, East Friesland, Oldenburg, North Hanover, Holland, Belgium, Denmark, Brunswick, Saxony and East Prussia, a vast area comprising all districts from which the

Anglo-Saxon conquerors of Britain are believed by any historians to have come, is that known among German scholars as "Einfeld-wirtschaft," the "one field system." Crops, usually of rye and buckwheat, are continually grown year after year, in the strips in the open fields, the fertility being maintained by marling and the application of peat manure.¹

It is therefore natural to attribute the whole year or every year lands of Norfolk, and the infields of Scotland, alike, to the influence of Saxon, Anglian or Danish conquest and settlement. If it is asked why the same agricultural feature was not more widely produced, the obvious answer is that when people of different races are mixed together in the occupation of the same villages, it is by no means certain that the agricultural customs which will afterwards prevail will be those of the conquerors, or of the race which is in the majority. The customs of the first occupiers had been modified by the environment, and had to some extent modified the environment, till something like harmony was created. After a conquest by another race, if any of the conquered race remain, the *easiest* course is to continue the existing mode of husbandry. It is more likely that the customs of the conquered race should remain as the basis of the future practice, though altered to some extent in form and more in spirit, than that the previous customs of the conquerors, which they had followed in other circumstances on a different soil and amidst other surroundings, should be imposed on the conquered people.

The following are the Acts for places outside Norfolk which specify the existence of Whole Year lands, Every Year lands, or Infields.

1740, c. 19. Gunnerton, *Northumberland*. This Act is to enclose 1300 acres of Ingrounds, and 1000 acres of Outgrounds.

1752, c. 27. Enclosing Wytham on the Hill, Infield, *Lincolnshire*.

1761, c. 32. Enclosing Norham Infields. Norham was nominally in *Durham*, but it is on the Scottish border.

¹ "The English Village Community," p. 372.

1807, c. 18. Herringswell, *Suffolk*. "Divers old inclosed meadow and pasture grounds, and old inclosed whole year or every year arable lands, open or common fields, half year or shack lands, common meadows, heaths, warrens, fens, commons, and waste grounds."

1811, c. cexix. Great Waddingfield c. Chilton and Great Coniard, *Suffolk*, "divers open fields called Whole Year lands and Half Year lands."

1813, c. 29. Icklingham, *Suffolk*. "Open and Common fields, Infields or Every Year lands, Common Meadows, Heaths, Commons and Wastes."

1819, c. 18. Yelling, Huntingdon, "Whole year lands."

Further, Arthur Young ("Agriculture of Suffolk," appendix, p. 217) tells us that the parish of Burnham, near Euston, in Suffolk, contained in 1764—

Infield arable, inclosed ...	...	...	381 acres,
Outfield arable ...	...	...	2626 „
Meadow and Pasture ...	...	...	559 „
Heath or Sheep-walk ...	...	...	1735 „
Total			<u>5302</u>

And William Marshall ("General View of the Agriculture of the Central Highlands of Scotland," 1794, p. 38) remarks: "The every year lands as they are called, of *Gloucester*, may be said to be clean compared with those of Breadalbane." Now, William Marshall knew the agriculture of Gloucestershire well; and he was an extremely accurate observer, and more interested in the local variations of common field cultivation than other agricultural writers of his time; his authority may therefore be considered good enough to establish the existence of lands known as every year lands in Gloucestershire.

It is also to be noticed that Acts of Enclosure for Gloucester and Oxford frequently specify, not "open and common fields" but "an open and common field," perhaps of between two and three thousand acres; and further, as we have previously noted,

the Board of Agriculture reporter for Oxfordshire says: "In divers uninclosed parishes the same rotation prevails over the whole of the open fields; but in others, the more homeward or bettermost land is oftener cropped, or sometimes cropped every year." Of Gloucestershire, William Marshall says: "In the neighbourhood of Gloucester are some extensive Common fields which have been cropped, year after year, during a century, or perhaps centuries, without the intervening of a whole year's fallow. Hence they are called Every Year's land. Cheltenham, Deerhurst, and some few other townships, have also their Every Year's lands." On these lands no regular succession of crops is observed, except that "a brown and a white crop—pulse and corn—are cultivated in alternacy" ("Rural Economy of Gloucestershire," Vol. I., p. 65).

It may be suggested, further, that a four-year course, such as we have seen was customary in many places, might possibly have originated from the custom of cropping the land every year. The difficulties of maintaining the fertility of the land, and of keeping it clean, under perennial crops, might very well have been found insuperable before the introduction of turnip culture, and the natural remedy, suggested by the two- or three-year course in neighbouring parishes, would be a periodic fallow. It is, however, so far as any evidence that can be supplied from the eighteenth and nineteenth centuries goes, equally possible that the four-year course was a modification of the three-year course, or that the two-, three- and four-years systems are all equally ancient; and that the varying customs, not only of systems of tillage, but also of occupation of meadow land and regulation of common of pasture, as found in different parts of the country, have grown up in each district as the result of the inter-action of Keltic, Anglo-Saxon, and Norse tradition.

If we take this view, which appears to me antecedently probable, we can see in the Midland or Mercian system a complete blend of Anglo-Saxon and Keltic custom, in which the specific features of both of the original strains are lost, and an intermediate, but perfectly distinct, type of village community resulted. The Wessex system, both in its feature of lot or rotation meadow,

and in the customs of individual cultivation of land for common benefit, as in the sowing of clover by each occupier to be fed on by the village flock, compared with the Mercian system, shows a much closer affinity with Keltic run-rig; while the Norfolk customs are quite easily accounted for as the result of a fresh infusion of Teutonic tradition, re-introducing the original one-field system into villages where that system had previously been blended with Keltic custom.

CHAPTER XVI.

COMMON FIELDS IN NEW ENGLAND.

A CERTAIN amount of light upon the question when the common field system lost its vitality, its advantages being completely overshadowed by its disadvantages, so that only the obstructive forces which we have considered prevented its disappearance, is furnished by the fact that the original settlers of New England, who presumably derived their ideas of agriculture from the eastern counties of England, reproduced in America a form of the English village community. No doubt their poverty and early difficulties compelled them to revert to a further degree of dependence on mutual help, and so perhaps the form of community which they there established may have been of a more primitive type than that which they had left behind, and allowance must be made for this possibility; and also for the possibility of effects of the sojourn of the Pilgrim Fathers in Holland.

The following accounts of the New England common fields are taken from two papers by Mr. Herbert B. Adams:—

“Vestiges of the old Germanic system of common fields are to be found in almost every ancient town in New England. In the town of Plymouth there are to this day some 200 acres of Commons known as Town Lands. This tract is largely forest, where villagers sometimes help themselves to wood in good old Teutonic fashion. . . . In the old town of Sandwich, near Cape Cod, at the point where the ship canal was projected in 1880, there is a little parcel of 130 acres known as the Town Neck. This is owned by a company of twenty-four proprietors, the descendants and heirs of the first settlers in the town, and this tract is managed to this day as a common field. Originally the Town Neck with other common lands belonged to the whole town. In

the MS. town records of Sandwich I find under date May 22, 1658, this vote: 'If any inhabytant wanteth land to plant, hee may have some in the Towne Neck, or in the Common for six yeare and noe longer.' Later, in 1678, April 6, townsmen are given liberty to improve Neck lands 'noe longer than ten yeares . . . and then to be at the townsmen's ordering again.' In the year 1695, the use of the Town Neck was restricted to the heirs of the original proprietors, and the land was staked out into 38 lots. The lots were not fenced off, and the whole tract continued to lie under the authority of the entire body of proprietors, like the arable fields of a German village community. In 1696, April 4, it was agreed that the Town Neck should be improved for the future by planting and sowing as a common field, until the major part of those interested should see cause otherwise to dispose or improve the same. The common fence was to be made up, and a gate to be provided by the first of May. A field driver or hayward was to keep the Town Neck clear of creatures and to impound for trespass. In 1700 it was voted that the Neck be cleared of creatures by the 16th of April, and that no part of the land be improved by tillage other than by sowing.

"And thus from the latter half of the 17th century down to the present day (May 9, 1881) have the proprietors of Sandwich Town Neck regulated the use of their old common field. Every year they have met together in the Spring to determine when the fences should be set up and how the pasture should be stinted. The old Commoners' records are for the most part still in existence as far back as the year 1693, and before this time the town records are full of agrarian legislation, for the Town Neck was then virtually town property. There arose in Sandwich and in every New England village community the same strife between old residents and new comers, as between the Patricians and Plebeians of ancient Rome. The old settlers claimed a monopoly of public land, and the new comers demanded a share. In most old New England towns the heirs of original settlers or of citizens living in the community at a specified date retained a monopoly of the common lands for many years until

finally compelled by force of public opinion to cede their claims to the town. In Sandwich, however, a vestige of the old system has survived to this day. Every Spring, for many years, has appeared a public notice (I saw one in the *Seaside Press*, May 8, 1880) calling together the proprietors of the Town Neck at some store in the village to choose a moderator and a clerk, and to regulate the letting of cow rights for the ensuing year. . . .

"There were for many years in the town of Salem certain common fields owned by associated proprietors just as in the case of Sandwich Town Neck. Such were the north and south fields in Salem. The old Commoners' records of the south fields are still preserved in the library of the Essex Institute, and date as far back as 1680. Under the date of October 14th of that year, I find the following: 'Voted that the proprietors have liberty to put in cattle for herbage—that is to say 6 cows, 4 oxen, 3 horses or yearlings, or 24 calves to 10 acres of land, and so in proportion to greater or less quantities of land; and no person shall cut or strip their Indian corn stalks after they have gathered their corn, on penalty of forfeiting herbage.'

"The so-called great pastures of Salem, some 300 acres, are to this day owned and managed by a small company of proprietors in common, of whom Dr. Wheatland of the Essex Institute has been for some years the clerk. He has in his hands the records of the proprietary, extending back for many years.

"These records are full of old time regulations in regard to common fencing, common pasturage, cow commons, sheep commons and the like." ("The Germanic Origin of New England Towns" p. 33.)

Perhaps still more conclusive are the following decrees of the legislative body of Massachusetts, which Mr. Adams quotes. In the spring of 1643 the Massachusetts General Court ordered "For preventing disorder in corn feilds w^{ch} are inclosed in common . . . that those who have the greater quantity in such fields shall have power to order the whole, notwithstanding any former order to the contrary, & that every one who hath any

part in such common feild shall make and maintaine the fences according to their severall quantities."

But in the autumn of the same year, the Act was passed:—
"Whereas it is found by experience that there hath bene much trouble and difference in severall townes about the Manner of planting, sowing, & feeding of common corne ffeilds & that upon serious consideration wee find no general order can provide for the best improvement of every such common feild, by reason that some consists onely of plowing ground, some haveing a great part fit onely for planting, some of meadowe and feeding ground; also so that such an order as may be very wholesome & good for one feild may bee exceeding preiudicall & inconvenient for another, it is therefore ordered, that where the commoners cannot agree about the manner of improvement of their feild, either concerning the kind of graine that shalbee sowed or set therein, or concerning the time and manner of feeding the herbage thereof, that then such persons in the severall townes that are deputed to order the prudenciall affaires thereof, shall order the same, or in case where no such are, then the maior portion of the freemen, who are hereby enioyned wth what convenient speed they may to determine any such difference as may arise upon any information given them by the said commoners; & so much of any former order as concerns the improvement of common feilds & that is hearby provided for, is hearby repealed." ("Village Communities of Cape Ann and Salem.")

CHAPTER XVII.

THE PROGRESS OF ENCLOSURE WITHOUT PARLIAMENTARY SANCTION.

A. FROM 1845 ONWARDS.

ANY statistical account of enclosure without Parliamentary sanction must necessarily be vague in comparison with the statements which it is possible to make of enclosure by Act of Parliament, and must consist of inferences from evidence of varying value. And, naturally, the evidence in general becomes scantier in proportion as the period investigated is more remote.

The Tithe Commutation maps and awards afford the richest mine of information for the period since 1836. We have seen that according to the analysis of them published by the Copyhold, Enclosure and Tithe Commission in 1873, they indicated the existence at that date of 264,307 acres of common fields. We have already seen how untrustworthy this estimate is if taken for a basis for calculating the area of existing common fields, how inaccurate it was even at the date at which it was published. But one great source of inaccuracy in it, as we have seen, is the assumption that no enclosure, other than by Act of Parliament, took place after the date of Tithe Commutation. If we could eliminate all other errors, and also get a perfectly accurate statement of the area of existing common fields, we should then know how much enclosure of common fields has taken place without Parliamentary intervention since the date of Tithe Commutation. This date, of course, is different in different parishes, but the average date is about 1845.

To eliminate all other errors it would be necessary to go over all the work again, a task which would take a single investigator

several years of continual labour, and would not then be accomplished unless the investigator were himself infallible. We must therefore be content with an approximate correction.¹

The tithe maps and awards deposited with the Tithe Commission cover about three-quarters of the area of England and Wales. The amount of common field in the other quarter is estimated on the assumption that in each county the part for which there are no tithe awards in the custody of the Tithe Commission contained the same proportion of common field as the part for which title awards existed. The common fields thus estimated amount to about two-fifths of the total estimate. If the particulars given in the return for the different counties were added up, we should get the statement:—

	Common Field Lands. Acres.
Areas ascertained from the tithe documents	163,823
Estimated additional areas	100,484
	264,307

We have seen that assuming the total of 163,823 acres is correctly “ascertained,” the estimate of 100,484 acres for the other parishes is very excessive, because the most frequent reason for no title documents existing in the custody of the Tithe Commission is that the commutation of tithes was effected before 1836 by a local Enclosure Act, which swept away the common fields.

In consequence, counties which were mainly enclosed by Acts of Parliament are very partially covered by the tithe documents; counties which have few or no Acts for enclosure

¹ There are no less than 11,783 separate sets of awards and apportionments, each with its map. The maps vary in size from about six or seven to over a hundred square feet each. The apportionments are bulky rolls of parchment.

of common fields are nearly entirely so covered. For example, we have—

—	Percentage of Area enclosed by Acts.	Area Covered by Tithe Documents.	Area not so Covered.
COUNTIES OF PARLIAMENTARY ENCLOSURE.			
Northampton	51·5	148,066	485,220
Rutland	46·5	37,728	54,968
Huntingdon	46·5	83,856	146,630
Bedford	46·0	104,357	191,159
Oxford... ..	45·6	214,889	252,417
East Riding, Yorkshire	40·1	263,473	479,228
Leicester	38·2	158,889	352,539
COUNTIES WITH LITTLE OR NO PARLIAMENTARY ENCLOSURE.			
Devon	<i>Nil.</i>	1,611,710	46,039
Cornwall	<i>Nil.</i>	851,486	6,122
Kent	<i>Nil.</i>	973,726	29,246
Shropshire	0·3	788,108	64,385
Monmouth	0·4	329,430	16,292
Cheshire	0·5	599,904	115,931

Fortunately there is another possible way of calculating the probable area of common field land which would have been found in the parishes not covered by tithe documents, if it had been investigated at about the same date.

Out of the seventy-five parishes enclosed by Act of Parliament since 1850—*i.e.*, at a later date than almost all of the tithe documents—the Tithe Commission had the maps and awards of seventy-one—all, that is, but four. Common fields subsequently enclosed were to be found in these two classes of parishes in the proportion of 71 to 4; it is a fair inference that the total area of common fields, whether subsequently enclosed or not, was distributed in the same proportion.

On this assumption we should have the following calculation :—

					Common Field Lands. Acres.
Areas ascertained from the tithe docu-					
ments	...	...	...	...	163,823
Estimated additional areas...			...	...	9,229
Total					<u>173,052</u>

No probable error in the additional estimate in this calculation would have an appreciable effect on the total.

Next, as we have noticed above, the “areas ascertained” require correction. This it is much more difficult to supply satisfactorily; all that we can do is to determine—(1) whether the number given is likely to err by excess or by defect; (2) whether the error is likely to be large.

The main purpose of the return was to establish the total amount of waste land subject to common rights, and the proportion of such land likely to be capable of cultivation. This part of the work was done with great care, and particularly with great care not to include any land which was not certainly subject to common rights. The final figure arrived at was certainly considerably in defect through the documents on which it was based failing to mention common rights in all cases where they existed.

The part of the return relating to common field lands, on the other hand, was considered of less importance; the explanatory letter says with regard to them :—

“The common field lands are generally distinguishable by the particular manner in which they are marked on the tithe maps, and their extent has been estimated by these maps.” This means that areas on the tithe maps subdivided by dotted lines were assumed to be common field lands. This method had the advantage of comprehensiveness—it is probable that scarcely any common field land escaped notice, if there were a tithe map for the parish in which it existed. I have only detected one error

of omission. The common fields of Eakring were very considerably in excess of the 54 acres at which they were estimated. But on the other hand it has the disadvantage of including with common field lands numerous cases of properties or holdings which were inadequately divided from one another by fences or hedges, but which were not common fields. But it is very hard to say precisely what percentage ought to be deducted to allow for this error. Generalising from all the cases in which I have been able to put estimates for particular parishes to a test, I should say that more than one-sixth, but less than one-third of the total should be deducted. Taking the larger fraction, so as to leave the remainder under-estimated, rather than over-estimated, we have—

	Acres.
Area of common field lands, by estimate	
above	173,052
Less one-third	57,684
	115,368
Parliamentary enclosure since 1873 has	
reduced the area of common fields by	14,842
	<u>100,526</u>

The final remainder represents our corrected estimate of the area of common fields arable and commonable meadows of intermixed ownership which would now exist if there had been no enclosure except by Act of Parliament since about the year 1845. The total area of such fields and meadows actually existing almost certainly does not exceed 30,000 acres. We therefore may conclude that not less than 70,000 acres have been enclosed as the result of the consolidation of farms and properties and voluntary agreements and exchanges, since about the year 1845, and that not more than 100,000 acres have been thus enclosed.

The total area of common fields enclosed by Acts since 1845, together with such meadows and commons as were enclosed together with common arable fields, is 139,517 acres.

It would therefore appear that such voluntary methods of enclosure have accounted in this period for an area something between half as large an area as Enclosure Acts and five-sevenths of that area.

The proportion of villages in which common fields have been entirely got rid of by voluntary enclosure during the same period would of course be smaller ; because wherever common fields exist they are subject to continual diminution by gradual enclosure ; and the final application of an Act of Parliament may be merely the *coup de grace*. Curiously, also, it may happen that a practically complete enclosure may be effected, and years later resort be had to an Act, as in the cases of Hildersham (Cambridge), and Sutton (Northampton).

B. BEFORE 1845.

The agricultural survey of Great Britain carried out by the Board of Agriculture in 1793 furnishes us with much information about the state of enclosure of some counties, and with scraps of information about others. Where the information is fullest it may take the form of estimates of the total area enclosed or open, or the form of information with regard to particular villages. By correlating the information thus supplied with that furnished by the Acts themselves, and from other sources, we can in some cases obtain a fairly full account of the enclosure history of a county.

BEDFORDSHIRE.

The "General Report on the Agriculture of Bedfordshire" gives the following estimate of the condition of the county (p. 11) :—

	Acres.
Enclosed meadow, pasture and arable ...	68,100
Woodland	21,900
Common fields, common meadows, commons and waste	217,200
Total ...	<u>307,200</u>

The area of Bedfordshire being 298,500 acres, a slight deduction should be made from the figures under each head. But this does not affect the two striking points about the estimate : (1) that over two-thirds of the area of the county was open, and (2) that the open and commonable land amounted to over 200,000 acres.

The author proceeds : " Every parish which is commonly understood to be open consists of a certain proportion of antient inclosed land near the respective villages, but that proportion, compared with the open common field in each respective parish, does not on an average exceed one-tenth of the whole " (p. 25).

He further says that Lidlington, Sundon and Potton had been recently enclosed. Each was enclosed by Act of Parliament.

We can deal with the above information in two ways : (1) by translating it into terms of parishes, and (2) by dealing with it in terms of acres.

In Bedfordshire very little common indeed existed apart from the open field parishes. This is proved by the fact that from 1700 to 1870 there were only three enclosures of commons, apart from arable common fields, comprising an area of 867 acres, and that the tithe maps only indicated 507 acres more of commons in parishes where there were no common fields. We may safely assume that at least 200,000 acres out of our author's 217,200 acres of open land belonged to open field villages, and that these villages also had, in accordance with his estimate, 20,000 acres of old enclosures, the area of all the open fields parishes in 1764 was, according to the estimate, about 220,000 acres ; that of the enclosed parishes about 87,200 acres. If the numbers of the parishes enclosed and open were about in the same proportion, out of the one hundred and twenty-one parishes in Bedfordshire, there should have been eighty-seven open and thirty-four enclosed.

From the list of Parliamentary enclosures in the appendix, it will be seen that seventy-three parishes were enclosed by Acts passed in 1793 and later. There were also seven other parishes in which the tithe documents indicate common fields surviving

up to the date of Tithe Commission, making a total of eighty parishes, which we have previously accounted for.

It would follow that about seven parishes were enclosed in Bedfordshire between 1794 and 1845 without any Act. This is in accordance with what we might reasonably expect.

Of the thirty-four parishes which by this argument were enclosed in 1790, seventeen had been enclosed by Acts passed between the years 1742 and 1783, leaving a remainder of seventeen parishes. There is obviously a strong probability that the majority of these were enclosed in the eighteenth century.

But in this calculation I have treated the 21,900 acres of woodland as though it were part of the enclosed parishes. If it be considered to belong indifferently to open and enclosed parishes, the above calculation must be modified. We then have ninety-four parishes open in 1793, and twenty-seven enclosed; fourteen out of the ninety-four would be enclosed without Parliamentary sanction between 1793 and 1845, leaving only ten parishes so enclosed at some unknown date earlier than 1793.

By dealing with the Bedfordshire estimate on the basis of acreage instead of parishes, I arrive at the following statement of the history of the enclosure of Bedford:—

	Acres.
Ancient woodland and waste, which passed directly into individual use, and ancient roads, &c.	43,000
Common fields, meadows and pastures enclosed before 1742	33,000
Ditto enclosed from 1742—1793 by Acts of Parliament	23,883
Ditto „ „ „ „ not by Acts	26,000
Ditto „ „ 1793—1900 by Acts ...	114,430
Ditto „ „ „ „ not by Acts	58,000
Total	<u>298,313</u>

Arthur Young, in June, 1768, travelled through Bedfordshire to St. Neots, and then close to the boundary between Bedford

and Huntingdon to Kimbolton and Thrapston in Northamptonshire. He found from Sandy to St. Neots the country chiefly open, and that it continued so to Kimbolton and Thrapston; though with regard to the two latter places he mentions enclosed pastures ("Northern Tour," 2nd Ed., Vol. I., pp. 55—59). This, so far as it goes, tends to confirm our conclusions.

I am anxious not to lay any undue stress on the above arithmetical calculations; but I think it is quite clear that up to the year 1742 the condition of the county of Bedford was that indicated by Leland's description.

Leland passed through Bedfordshire in his "Itinerary." From Vol. I., fols. 116—120, we find that from Higham Ferrers in Northamptonshire, about 2 miles from the Bedfordshire boundary, to Bedford (14 miles) was "champaine" from Wellington village, near Bedford, to Antchille Castle (Amptill), "12 miles almost al by Champayn Grounde, part by corne and part by Pasture, and sum baren hethy and sandy grounde." Then "From Antchille to Dunstable X m. or more. First I passed partely by woddy ground and Enclosures. But after most parte by champaine Grounde. . . . And thens to Mergate al by Champaine a vj miles." And so out of Bedfordshire. A small part of the county was ancient woodland, a smaller part was cultivated land reclaimed from the forest state, which had never passed through the common fields system of cultivation, but almost all was in the condition of the typical open field parish, common field arable, commonable meadows, and common pastures, with a certain amount of enclosure round the villages. It would appear that during the 200 years following Leland's journey only an insignificant amount of progress in enclosure took place in Bedfordshire. This conclusion is not contradicted, but on the other hand it is not strikingly confirmed by Walter Blyth ("The English Improver," 1649), who enumerates as unenclosed "the south part of Warwick and Worcestershire, Leicester, Notts, Rutland, some part of Lincoln, Northampton, Buckingham, some part of Bedfordshire, most part of the Vales of England, and very many parcels in most counties."

One further point may be noticed. In Bedfordshire the

percentage of the total area enclosed by Act of Parliament is exceptionally high—46·0 per cent. We find that when we make allowances for (1) contemporary voluntary enclosure, (2) for ancient woodland and for some land passing directly from the forest state into that of separate ownership and occupation, (3) for some ancient enclosing of land in the immediate vicinity of villages, there is little or no other enclosure remaining to be referred to the period before Parliamentary enclosure began—in this case the year 1742.

NORTHAMPTON, RUTLAND, S.E. WARWICK AND LEICESTER.

These four counties may be said to form a definite group, so far as their enclosure history is concerned. The main facts of their Parliamentary enclosure are shown in the following table :—

—	Acreage Enclosed		Percentage of Total Area.
	By 18th Century Acts.	By 19th Century Acts.	
Warwick	124,828	24,731	25·0
Leicester	187,717	12,660	38·2
Rutland	37,180	10,044	46·5
Northampton...	247,517	85,251	51·8

Like Bedford, they are all counties with a high proportion of enclosure by Act of Parliament ; but they differ from Bedford in that their enclosure was much more preponderatingly effected in the eighteenth century. The proportion of eighteenth-century Acts is particularly high in Leicester, but the proportion of Acts earlier than 1760 is higher in Warwick than in any other county—twenty-nine out of 114. These counties comprise the district in which the greatest amount of agitation arose against enclosure in the seventeenth century, and that in which the effect of


EAST MIDLANDS

SECTION I.

-  Enclosed before the General Enclosure Act of 1801.
-  " between 1802 and 1845.
-  " under general enclosure Act of 1845.

Scale 1:1,000,000 or 1 inch = 15.78 Stat. miles.

5 0 5 10 15 20



EAST MIDLANDS

SECTION 2.

-  Enclosed before the General Enclosure Act of 1801.
 " between 1802 and 1845
 " under general enclosure Act of 1845.

Scale 1: 1,000,000 or 1 inch = 15.78 Stat miles.

5 0 5 10 15 20



enclosure in causing depopulation through decay of tillage was most marked in the eighteenth century.

NORTHAMPTONSHIRE.

Northamptonshire has 51·5 per cent. of its area covered by Acts of Parliament for the enclosure of whole parishes, a larger proportion than any other county. There have been passed in addition an important Act for extinguishing foreign rights in Rockingham Forest in 1796, an Act in 1812 for draining and enclosing Borough Fen, and creating a new parish to be called Newborough, and three other Acts for enclosing commons or wastes ; the whole area affected by the five Acts being perhaps 15,000 acres. These being included, the total area which has undergone Parliamentary enclosure reaches 54 per cent. of the area of the county.

James Donaldson, the Board of Agriculture reporter, says that of the 316 parishes, 227 were enclosed by 1793, and eighty-nine were then in open field ; and that "half of the inclosed parishes may be denominated old inclosure."

Of the eighty-nine parishes, open in 1793, eighty-eight have been enclosed by Act of Parliament since ; so that there was only one parish enclosed without Parliamentary intervention from 1793 to 1903, when the last trace of the Northamptonshire common fields was swept away by the enclosure of Sutton. This fact is remarkable, it points to a wide diffusion of ownership of lands and of rights over the land ; and it should be associated with the specially strenuous resistance of Northamptonshire to enclosure in the reign of James I.

The statement that of the enclosed parishes half may be denominated old enclosure, would be more enlightening if one knew exactly what Mr. Donaldson meant by old enclosure. But we find that 113 parishes (which is as near as possible half 227) were enclosed by Acts passed in the period 1765—1792 ; if therefore by "old enclosure" he means enclosure dating back more than twenty-eight years, his statement would imply that there was no enclosure without an Act in that period. Nineteen

parishes were enclosed by Act in the five years 1760—1764, eighteen in the period 1749—1759, and four earlier. These Acts altogether account for the enclosure of 153 out of the 227 parishes, and there is evidently a strong balance of probability that the enclosure of the remaining seventy-two took place almost entirely before the middle of the eighteenth century.

LEICESTERSHIRE.

R. Monk, the reporter for Leicester, gives as an Appendix a list of the "Lordships" of that county, with the names of the Lords of the manors, or chief landowners, and the date of enclosure, when he could ascertain it. He only knew of ten open field parishes and of two half open and half enclosed; but, of these, four, Cold Overton, Cole Orton, Whitwick and Worthington, have not since been enclosed by Act of Parliament; they must therefore have been enclosed voluntarily at the end of the eighteenth or in the first half of the nineteenth century; for the tithe documents for these parishes do not indicate any surviving common field. For thirty-five of the parishes not enclosed by Act of Parliament, Monk gives no information; of the following fifteen he gives the date of enclosure:—

Parish.	Enclosed.	Parish.	Enclosed.
Shanktons	1738	Stapleford	1772
Birstall	1759	Shearsby	1773
Beeby	1761	Hathorn	1777
Thurnaston	1762	Ilston	1788
Saxelby	1765	South Kilworth ...	1789
Frisby	1769	Hose... ..	1791
Stretton Parva ...	1770	Barkston and Plunger	1791

The following fifty-five he merely describes as "enclosed":—

Allextou	Bittesby	Broughton Astley
Aston Flamville	Blackfordby	Burrow
Barwell	Brooksby	Burton-by-Prestwould

Cadeby	Hether	Stapleton
Carlton	Huncote	Stretton Magna
Coston	Ibstock	Swepton
Cotes	Isley Walton	Thorpe Arnold
Dadlington	Knossington	Thurnby
Dalby-in-the-Wolds	Lockington	Tilton-on-the-Hill
Great Dalby	Loseby	Twycross
Dishly Grange	Market Bosworth	Ullesthorpe
Eastwell	Potters Marston	Welham
Edmundthorpe	Misterton	Little Wigston
Fenny Drayton	Normanton-on-the-	Witherby
Foolesworth	Heath	Woodthorpe
Gaddesby	Odstone	Owston
Garthorpe	Rollestone	Staunton Harold
Galby	Saxby	
Goadby	Snareston	

Wanlip he describes as enclosed lately.

The following forty he describes as "old enclosure," or gives seventeenth-century dates for their enclosure—

Ashby Folville	Elmesthorpe	Ragdale
Great Ashby	Enderby	Scraptoft
Barlston	Foston	Shawell
Buckminster	Freathby	Staunton Wyville
Beaumont Leys	Glen Parva	Stoke Golding
Burbage	Kirkby Beler	Thedingworth
Burton Lazars	Lodington	Thorpe Sacheville
Braunston-by-Kirkby	Muston	Welby
Carleton Curlew	Nailston	Willoughby Waterless
Catthorp	Newton Linford	Wyfordby (or Wiverby)
Cossington	Packington	Wymondham
Cotterback	Peatling Magna	
Little Dalby	Prestwold	

Pickwell, he says, was enclosed in 1628, Shenton in 1646, and Laughton in 1665.

Here, again, in interpreting these statements, we are confronted with the difficulty of determining what antiquity is implied by the term "old enclosure," and also by the difficulty of estimating what proportion of the parishes described merely as "enclosed" belonged to any particular epoch of enclosure.

On the one hand, we note (1) that one-third of the open field parishes known to Monk were enclosed without Acts in the

following half-century, (2) that he gives the date of enclosure of fifteen other parishes for which we have no Acts, which were enclosed in the previous half-century. It would therefore appear that a very considerable amount of enclosure was going on, without Acts of Parliament, during the period in which Parliamentary enclosure was proceeding rapidly.

On the other hand, the fact that he can give seventeenth-century dates for the enclosure of three parishes suggests that probably a very large proportion of his "old enclosure parishes" and a fair proportion of his enclosed parishes were enclosed in the seventeenth century.¹

Pursuing the inquiry backwards, we find our next source of information in Celia Fiennes, a lady of Newtontony, who made a series of rides in the last few years of the seventeenth century. Newtontony is three miles east of Amesbury, amid the open chalk hills, or, as she describes it, in the midst of "a fine open champion country"; and she usually describes the aspect of the country she passes through. She travelled westwards to Land's End, eastwards to Kent, northwards to the Border, and she gives some information with regard to the state of enclosure of most of the English counties. She went through both Bedfordshire and Northamptonshire, but with regard to those two counties gives no information as to their condition of enclosure. As she is more apt to notice the presence than the absence of hedges, this, so far as it goes, confirms our conclusions with regard to Bedfordshire; and, with regard to Northamptonshire, this small piece of negative evidence tends to the conclusion that that county also was almost entirely open in the beginning of the eighteenth century.

"Leicestershire," she says, "is a very Rich Country—Red land,

¹ William Pitt, who made a second survey of the agriculture of Leicestershire for the Board, published in 1809, gives an interesting account of the enclosure of the vale of Belvoir. This, the north-eastern corner of Leicestershire, was enclosed between 1760 and 1800; and as a result a complete change in the cultivation took place; the rich land in the valleys, which had been arable common fields, was laid down in grass, and the tenants forbidden under heavy penalties to plough it; while the summits of the hills and edges of the vales, which had been sheep-runs, were converted into arable land.

good corn of all sorts and grass, *both fields and inclosures*. You see a great way upon their hills the bottoms full of Enclosures, woods, and different sorts of manureing and herbage " (p. 133).

It is evident that enclosure had considerably advanced ; but it must be noted that " fields " with Celia Fiennes means common fields. It is further to be noted that her description of the enclosures creeping up the hills implies a process of gradual enclosure. Of the neighbourhood of Bosworth (in the west of Leicestershire) she says, " this is a great flatt full of good Enclosures." The western side of Leicestershire was therefore mainly enclosed before 1700, while the north-east was all open till 1760.

But though enclosure was so far advanced in Leicestershire, " their fewell," Celia Fiennes says, " is but coudung or Coale." The use of coudung for fuel supplied to advocates of enclosure in the seventeenth and eighteenth centuries one of their chief arguments. Either the hedges of Leicestershire were not yet able to supply enough wood for fuel, or the old custom continued although it was as unnecessary as objectionable. In either case the natural inference is that much of the enclosure of Leicestershire which Celia Fiennes observed, was then recent.¹

This again is confirmed by Walter Blyth, who in the passage quoted above describes Leicestershire as entirely open, as well as Northampton, Rutland, and the south part of Warwick.

Further detailed information is given by the disputants Joseph Lee, John Moore, and the anonymous writers who joined in the controversy, who debated the ethics of enclosure in the Midlands in the years 1653—1657. John Moore, in his first pamphlet, asks, " Above one hundred touns inclosed in Leicestershire, how few amongst them all are not unpeopled and uncorned ? " Now it is probably fair to read " above

¹ Arthur Young found the practice still prevalent in Northamptonshire more than seventy years later : " they collect all the cow-dung from their fields and daub it in lumps, barns, and stables, to dry for fuel " (" Eastern Tour," Vol. I., p. 48). Edward Lawrence speaks of Yorkshire (evidently the East Riding only is meant) and Lincolnshire as the counties where the practice prevailed in 1727 (" The Duty of a Steward to his Lord," Article 3).

one hundred " as " about one hundred " or " nearly one hundred." The names of some of these are supplied by Joseph Lee in his "Vindication of Regulated Enclosure," for he gives (page 5) as examples of enclosure without depopulation the following thirteen parishes in Leicestershire: Market Bosworth, Carlton, Coten, Shenton, Cadesby (Cadeby), Bilson (Billesdon), Twicriass, Higham, Golding (Stoke Golding), Little Glen, Croft, Ashby Magna, and Stapleton, together with Stoke in Northamptonshire, Upton and Barton, which might be either in Northampton or in Warwick, and three others, Nelson, Cosford and Woscot, which I am unable to locate, except that Cosford was near Catthorp, the extreme south corner of Leicestershire; for Lee further gives a list of fifteen enclosures within three miles of Catthorp, in which Cosford and Coten are included, and also Bigging, Brownsover, Shawell, Streetfield, Over, Cottesbatch, Pultney, Sturmer, Hallfield, Sister (? Siston), Moorebarn, Cotes and Misterton (p. 8).

Of the former set of townships he says: "They have been enclosed some twenty, some thirty, some forty or fifty years." Of the latter he says: "Most of these Inclosures have been plowed within thirty years, and the rest are now about to be plowed."

It would appear, therefore, that enclosure began in Leicestershire at about the beginning of the seventeenth century, and proceeded so rapidly that nearly a hundred townships, mainly situated in the south and west of the county, were enclosed within about fifty years. Enclosure also began in Northamptonshire about the same time, but at not so great a rate. The author of "Considerations Concerning Common Fields and Enclosures," published in 1653, makes a reference to "Mr. Bentham's¹ Christian Conflict" (p. 322), which gives a list of eleven manors in Northamptonshire, enclosed and depopulated. In a later sermon, "A Scripture Word against Inclosures," 1656, John Moore says: "England (especially Leicestershire and the counties round about) stands now as

¹ This was Joseph Bentham of Kettering, who published "The Societie of the Saints," in 1638, in which he denounces enclosure with remarkable vehemence.

guilty in the sight of God of the sinnes in the text. They sold the righteous for silver and the poor for a pair of shoes, as Israel did then" (p. 1). A little later he again referred to "Enclosure in Leicestershire and Northamptonshire, and the counties adjacent." This confirms the conclusion reached from the other evidence that Leicestershire was in the centre of the seventeenth-century movement of enclosure of common fields, and that it was in Leicestershire that the movement was most effective.

RUTLAND.

Rutlandshire has had 46·5 per cent. of its area enclosed by Acts of Parliament, 47,224 acres. Of this area 14,641 acres were enclosed by Acts passed between 1756 and 1773; then for twenty years there were no Acts, the next being passed in 1793. By that and subsequent Acts 32,583 acres were enclosed.

John Crutchley, the Board of Agriculture reporter, says that two-thirds of the country was enclosed, one-third unenclosed ("Agriculture of Rutland, 1793," p. 30). As the area (32,583 acres) is just one-third of the total area of Rutlandshire (97,273 acres), Acts of Parliament entirely account for all the enclosure since 1793. Of the area enclosed before 1793 there remains about 50,000 acres, a little more than half the county, unaccounted for.

Part at least must have been enclosed before the beginning of the eighteenth century, for Celia Fiennes says: "Rutlandshire seems more woody and enclosed than some others" (p. 54). It is one of the counties described by Walter Blyth as entirely unenclosed in 1649; but, as we have seen, this description is also applied by him to Leicestershire and Northamptonshire, and as it was, especially in the case of the former county, decidedly too sweeping, we cannot infer that no enclosure took place in Rutlandshire before that date.

Leland passed through Uppingham and Stanford; he found part of the county woody, but he makes no mention of enclosure.

He also gives a very full description of the counties of Leicester

and Northamptonshire. Charnwood Forest in Leicestershire, and Rockingham Forest in Northamptonshire, were then very extensive; but all the remainder of the two counties he describes in general as "champaine," or by words which imply an unenclosed condition. The only mention of enclosure is in the case of two parks in Northamptonshire. (See Appendix C.)

WARWICK.

Warwickshire is divided by the River Avon into two parts of approximately equal area; the north-western part is a district of ancient enclosure, probably enclosed in the main direct from the forest state; the south-eastern part has a similar enclosure history to Leicester and Northampton, except that its enclosure took place generally somewhat earlier. One-quarter of the whole county has undergone Parliamentary enclosure, but the proportion so enclosed of the south-eastern part is much larger.

John Wedge, the Board of Agriculture reporter, estimates that in 1793, out of a total area of 618,000 acres, 57,000 was open field land (p. 11). To reduce 618,000 to the true area of the county (577,462 acres), one must deduct 10 per cent. A deduction of 10 per cent. leaves about 51,000 acres of common field. Enclosure Acts since account for 38,444 acres, and in parishes not enclosed by Acts the tithe documents indicate rather over 1000 acres of common field lands. There remains a little over 10,000 acres unaccounted for, which has disappeared between 1793 and the date of tithe commutation.

John Wedge appears to have attempted a list of open field parishes with their area and extent of common field and waste, but only got so far as to supply this information for five parishes (p. 54), each of which has undergone subsequent enclosure by Act of Parliament. He draws attention to the contrast between the two parts of Warwickshire: "About forty years ago the southern and eastern parts of this county consisted mostly of open fields. There are still about 50,000 acres of open field land which in a few years will probably all be enclosed. These lands, being now grazed, want much fewer

hands than they did in the former open state. Upon all inclosures of open fields the farms have generally been made much larger. For these causes the hardy yeomanry of country villages have been driven for employment into Birmingham, Coventry, and other manufacturing towns."

About 90,000 acres was enclosed by Act of Parliament in the part of Warwick described between 1743 and 1793. This, together with the 50,000 acres remaining, amounts to rather less than half the area of the division of the county under consideration. As Wedge clearly was of opinion that the greater part of S.E. Warwick was open at the date he mentions, and as there is no reason for thinking he was wrong, it is to be inferred that a considerable amount of non-Parliamentary enclosure was going on in S.E. Warwick during the second half of the eighteenth century.

The extracts above given with reference to Leicester and Northampton also prove that enclosure was going on in this part of the county during the first half of the sixteenth century, though it had so little advanced up to 1649 that Blyth speaks of this part of the county as unenclosed.

Leland gives an extremely full account of the state of enclosure of Warwickshire, which shows that as early as 1540 the north-west part of the county was "much enclosed." It was on one of his later journeys that he explored the county, entering from Oxfordshire. He found, "Banbury to Warwick, twelve miles by Champaine Groundes, fruitful of corne and grasse, and two miles by some enclosed and woody groundes" (Vol. IV., Part 2, fol. 162).

"I learned at Warwick that the most part of the shire of Warwicke, that lyeth as Avon River descendeth on the right hand or ripe of it, is in Arden (for soe is the ancient Name of that part of the shire); and the ground in Arden is much enclosed, plentifull of grasse, but not of corne. The other part of Warwickshire that lyeth on the left hand or ripe of Avon River, much to the south, is for the most part Champion, somewhat barren of wood, but plentifull of corne" (fol. 166 a).

We may add, so as to complete our review of the evidence,

that William Marshall, in his book on the "Agriculture of the Midland District of England" (1790), treats a region of which the town of Leicester was near the centre, comprising the counties of Warwick, Rutland, the north of Leicester and of Northampton, the east of Staffordshire, and the southern extremities of Derby and Nottingham, as an agricultural unit. He says: "Thirty years ago much of this district was in an open state, and some townships still remain open; there are others, however, which appear to have been long in a state of enclosure, and in which, no doubt, the present system of management originated" (p. 8). This does not add to our information about this district, but the fact that Marshall was perfectly correct in his reading of the story told by the aspect of the country is important, because for some other districts his testimony is material.

To sum up, we find that in the north-west of Warwick enclosure was general as early as 1540, while it was practically non-existent in the south-east of that county and in Leicester, Northampton and Rutland. We find that the movement towards enclosure of the "champaine" country began about the year 1600, that it proceeded steadily in spite of great popular resistance through the seventeenth century, but at a much greater rate in Leicester, and probably in S.E. Warwick, than in Northamptonshire, the rate in Rutland being probably slower than in Leicester, but certainly greater than in Northamptonshire, the course of the movement being from west to east; that about half of S.E. Warwick and of Leicester was enclosed when the movement of Parliamentary enclosure began, but less than half of Rutland, and not more than quarter (probably not more than a fifth) of Northamptonshire.

We have seen that the enclosure of Bedford was later than this, and we shall see that the same is true of Cambridgeshire and Huntingdon. In the midlands of England the course of enclosure from 1600 onwards was from west to east.

A word may be added with regard to the methods by which non-Parliamentary enclosure was effected in this district. There was great diversity in Leicestershire from village to village with

regard to the diffusion of property, as may be seen from Monk's Appendix, in which he endeavours to give the names of the principal owners in each "lordship." Some were entirely in the hands of a single individual, others had many owners, but in the great majority the land was mainly, but not entirely, owned by the lord of the manor. The description of the enclosure of S.E. Warwick supplied by John Wedge, the consolidation of farms, and the depopulation of the villages, indicates that there enclosure, whether by Act of Parliament or not, was carried through by the authority of the lord of the manor, he being the main landowner.

The method by which this would be done when an Act of Parliament was not resorted to is fully explained by Edward Lawrence ("The Duty of a Steward to his Lord, 1727"), Article XIV.

"A Steward should not forget to make the best Enquiry into the disposition of any of the Freeholders within or near any of his Lord's Manors, to sell their Lands, that he may use his best Endeavours to purchase them at as reasonable a price as may be for his Lord's Advantage and Convenience . . . especially in such Manors where improvements are to be made by inclosing Commons and Common Fields; which (as every one, who is acquainted with the late Improvements in Agriculture must know) is not a little advantageous to the Nation in general, as well as highly profitable to the Undertaker. If the Freeholders cannot *all* be perswaded to sell, yet at least an Agreement for Inclosing should be pushed forward, by the Steward, and a scheme laid, wherein it may appear that an exact and proportional share will be allotted to every proprietor; perswading them first, if possible, to sign a Form of Agreement, and then to chuse Commissioners on both sides . . . If the Steward be a Man of good sense, he will find a necessity of making use of it all, in rooting out *superstition* from amongst them, as what is so great a hindrance to all *noble* Improvements." The superstition referred to, is that enclosed land is cursed, and doomed in three generations to pass out of the hands of the descendants of the proprietor who enclosed it.

That in the early seventeenth century much of the enclosure was carried out by the power of the lord of the manor is plain from the scraps of information given by John Moore. Thus he tells us that Ashby Magna was enclosed in 1606, and that the lord gave most of his tenants leases for three lives and twenty-one years after ("Scripture Word Against Inclosures," p. 9), that being the reason why depopulation had not resulted up to 1656; that in both Misterton and Poultney no house at all was left except the minister's, so that these two manors must have been the property of absentee landlords.

But Catthorpe had no lord of the manor, it consisted of 580 acres divided among eight freeholders and five or six holders of "ancient cottages" who were also Freeholders (Joseph Lee, p. 5). The enclosure was carried out by the agreement of all the owners, except one who objected on conscientious grounds. The way in which these agreements to enclose were effected in parishes where property was divided is thus described by Moore:—"In common fields they live like loving neighbours together for the most part, till the *Spirit of Inclosure* enter into some rich Charles heart, who doe not only pry out but feign occasions to goe to law with their neighbours, and no reconcilment be made till they consent to Inclosure. So this Inclosure makes thieves, and then they cry out of thieves. Because they sold the righteous for silver, and the poor for a pair of shoes. If it had not been for two or three righteous in many Townes of these Inland Counties, what desolation had there been made ere this time?" (Scripture Word, p. 12).

CAMBRIDGE AND HUNTINGDON.

Much of these two counties anciently consisted of fen and marsh, and of the land now cultivated a great deal never passed through the common field system. But the "upland" of each county was very late in undergoing enclosure.

Vancouver, the reporter for Cambridgeshire, gives an estimate

of the areas of lands of different description, which I slightly rearrange below.

—	Unenclosed.	Enclosed.	Doubtful.
	Acres.	Acres.	Acres.
Enclosed arable	—	15,000	—
Open field arable	132,000	—	—
Improved pasture	—	52,000	—
Inferior pasture	—	—	19,800
Improved fen	—	50,000	—
Woodland	—	—	1,000
Waste and unimproved fen	150,000	—	—
Half-yearly meadow land ...	2,000	—	—
Highland common	7,500	—	—
Fen or moor common	8,000	—	—
Heath and sheepwalk	6,000	—	—
	305,500	117,000	20,800
Total area, 443,300 acres.			

The actual area of Cambridgeshire is 549,723 acres; but Vancouver was an exact and careful observer, and the proportions between the areas assigned to each description were no doubt reasonably accurate. Here we find over two-thirds of the total area unenclosed, and more than eight-ninths of the arable land. It is, of course, possible, probable even, that a larger amount than 15,000 acres of open field arable had undergone enclosure, and that the 52,000 acres of improved pasture includes a good deal of such land, laid down in grass on enclosure. But even if we included the whole, there would only be 67,000 acres of ancient common field arable which had undergone enclosure, compared with 132,000 acres still open.

Vancouver also gives detailed accounts of ninety-eight of the Cambridgeshire parishes, eighty-three of which were open, fifteen enclosed. Of those which were open in 1793, seventy-four have since been enclosed by Act of Parliament, nine have

not, viz., Babraham, Boxworth, Downham, Ely, Littleport, Lolworth, Madingley, Soham and Over.

Babraham had 1,350 acres of common field, and Vancouver says that enclosure was desired. It was completely effected before the date of tithe commutation.

Boxworth had 900 acres of common field. "The whole of this parish," says Vancouver, "lies within a ring fence and containing 2,100 acres, is the property of one gentlemen." Vancouver's acres, as we have seen, are large ones; the actual area is 2,526 acres. Enclosure was effected before the date of tithe commutation, and as might be supposed under the circumstances, without an Act.

Downham had, according to Vancouver, 680 acres of common field; the tithe map indicates 450 acres still remaining.

To Ely he assigns 2,100 acres of common field. This had all gone at the time of tithe commutation.

Of 345 acres assigned to Littleport, a remnant of forty acres survived to be recorded in the tithe map.

The common field land of Lolworth suffered no diminution; for while Vancouver gives it 650 acres, the tithe map indicates 800 acres. They were enclosed at the time of the Crimean war by common agreement of the owners, without an Act. This was the last surviving common field parish in the vicinity.

In Soham enclosure was nearly as slow. Vancouver assigns it 1,200 acres of common field; the tithe map 1,100 acres.

Madingley, Vancouver says, had 1,030 acres of common field. These were all enclosed before the date of tithe commutation.

For Over the Board of Agriculture has no tithe documents; but we may add that Horseheath had about 750 acres of common field, out of a total of 1,850 acres, according to the tithe map.

Of the fifteen parishes stated by Vancouver to have been enclosed before 1793, only two were enclosed by Act of Parliament.

The extent of the information obtained from the Acts, the tithe documents, and Vancouver's report is as follows:—

Of the 152 agricultural parishes of Cambridgeshire, we know the date of enclosure of 118, enclosed by Acts of Parliament. These are given in Appendix B.

Of thirteen, viz., Arrington, Childerley, Chippingham, Hatley St. George, Leverington, Newton in the Isle of Ely, Outwell, Tadlow, Tid St. Giles, Upwell-cum-Welney, and Wisbeach St. Mary, we know that they were enclosed without Acts before 1793. The date 1790 is given for Chippingham, and a small remnant of common field survived till 1851 in Newton.

Four parishes were enclosed, not by Acts, between 1793 and the date of tithe commutation—Babraham, Boxworth, Ely and Madingley.

Five parishes which were not entirely enclosed even at the date of tithe commutation have not been enclosed by Act since. These are Lolworth, which then had only about one-fifth of its area enclosed; Horseheath, which was about half enclosed; Soham, which had about 1,100 acres of common field and 456 acres of common, out of a total area of nearly 13,000 acres; and Downham and Littleport, which had respectively 450 and forty acres of common field remaining.

Of one parish, Over, we only know that it was open in 1793.

Of nine parishes, Borough Green, Croydon-cum-Clapton, East Hatley, Papworth St. Agnes, Long Stanton, Westley Waterless, Wisbeach St. Peter, Witcham and Witchford, we only know that they were enclosed before the date of tithe commutation.

Of two, Little Gransden and Stanground, we have no information.

I have before laid stress upon the eastward march of enclosure in the midlands during the sixteenth, seventeenth, and eighteenth centuries, which the following comparison illustrates:—

—	Parliamentary Enclosure.			
	In the 18th Century.		In the 19th Century.	
	Acts.	Acres.	Acts.	Acres.
Warwick ...	91	124,828	23	24,731
Cambridge ...	23	51,028	85	147,311

Celia Fiennes traversed the county. She describes the part from Littlebery (in Essex) to Cambridge as entirely open (p. 48), and makes no mention of enclosures in the description of the view from the "Hogmogoge Hills" (p. 49), but she speaks of "good enclosure" between Cambridge and Huntingdon.

Though Cambridgeshire was on the whole so late in undergoing enclosure, the conversion of arable into tillage had so far proceeded that about one-fifth of the county was included in the Inquisition of 1517, and it was found that in this part 1,422 acres had been enclosed and converted into parks or pasture (Leadam, "Domesday of Inclosures").

HUNTINGDON.

George Maxwell, the Board of Agriculture reporter, says that Huntingdon contains one hundred and six towns and hamlets, of which forty-one were then (1793) wholly enclosed, and of the remaining sixty-five a very considerable part was enclosed. He computes that about a half of the "high land part" of the county, which would, of course, include all old arable land, was still unenclosed ("Agriculture of Huntingdon," p. 16).

Fifty-eight parishes were enclosed by Acts subsequently to the date of his report, and one parish (Lutton) remained open to the date of tithe commutation. This leaves six out of the sixty-five open or partially enclosed parishes of his report, in which enclosure was completed by the middle of the nineteenth century without any Act.

Of the forty-one parishes wholly enclosed before 1793, twenty were enclosed by Acts of Parliament, leaving twenty-one parishes which might have been enclosed contemporaneously without Acts, or to be assigned to the time previous to the beginning of Parliamentary enclosure.

Some of this enclosure is certainly to be assigned to an early date. Celia Fiennes, as we have seen, found more enclosure as she came to Huntingdon from Cambridge. Leland also found enclosure in the smaller county.

"From Cambridge to Elteste village al by champeyne

counterey 8 miles. St. Neotes 4 miles. From St. Neotes to Stoughton Village by sum enclosid ground a 3 Miles, it is in Huntendunshir. From Stoughton to Meichdown Village a 4 Miles be much Pasture and Corne ground . . . there be goodly Gardens, Orchards, Ponds, and a Parke thereby."

THE EASTERN COUNTIES.

The story of the enclosure of Essex and Suffolk is almost completely told by the map. Each is sharply divided into a larger part very anciently enclosed, without Acts of Parliament, and a smaller part close to the boundaries of Hertford, Cambridge, and Norfolk, which was enclosed at a late date by Acts of Parliament. Essex has but one Act belonging to the eighteenth century, and that is dated as late as 1795. Suffolk has nine Acts belonging to the eighteenth, and forty-four belonging to the nineteenth century.

The additional information available only serves to bring out more clearly the very striking contrast between the regions of ancient and recent enclosure.

On the one hand we find that the Parliamentary enclosure of the extreme west and north-west portion of Essex is only part of the recent enclosure of that part.

The Enclosure Acts cover twenty-nine parishes, and an area of 22,000 acres, about 760 acres per parish. Vancouver, who reported on Essex, as well as Cambridge, tells us, "The arable land in about forty parishes lies very much in open common fields, and which in point of quantity is found to average 1,200 acres per parish."¹ He gives a list of open field parishes; Thraxted and Streethall, which have not since been enclosed by Act, are included; and each of those had some common field at the time of tithe commutation.

On the other hand, he tells us that the neighbourhood of Great Dunmow, which is quite close to the region of nineteenth century enclosure, had been enclosed from time immemorial.²

¹ "Agriculture of Essex," p. 185.

² *Ibid.*, p. 195.

The well-known passage in the "Discourse of the Commonweal," "Countries wheare most Inclosures be, are most wealthie, as essex, kent, devenshire, and such," sufficiently establishes the ancient enclosure of the greater part of Essex. And though the evidence is not very full, it is, I think, sufficient to show that the enclosure of the corresponding part of Suffolk had a similar history. Celia Fiennes says that the journey from Ipswich to Woodbridge is "7 miles mostly Lanes, Enclosed countrys"; and from Woodbridge to Saxmundham "The wayes are pretty deep, mostly Lanes, very little Commons" (p. 107).

John Norden (1602) also makes mention of Suffolk methods of hedging.

The question then arises with regard to this region of ancient enclosure in Essex and Suffolk, whether it ever passed through the typical English common field system. To this question we are able to give an unhesitating answer.

In Suffolk, far away from any other Parliamentary enclosure, in the south-east corner of the county are the parishes of Orford and Iken. The enclosure at Orford was in 1881. There were but forty-six acres to enclose, and these lay in strips alternately belonging to the lord of the manor and to the Corporation of Orford. The existence of corporate property in this small spot of land preserved it from enclosure to such a late date.

The case of Iken appears to have been somewhat similar. It was enclosed in 1804. There was only the small area of 100 acres to enclose, comprising "certain open and common fields, meadows, commonable lands, and waste grounds." The Marquis of Hertford was lord of the manor, and six individuals by name, and "divers others" are said to be the other proprietors of land. There is a special clause authorising the parish authorities, if they will, to accept rents from the Marquis of Hertford in lieu of allotments, so there must have been corporate property in the commonable lands, and this no doubt accounted for the survival of this small area of common field.

But the clearest evidence is from the town of Colchester. The borough is of great extent, and includes the four agricultural parishes of Greenstead, Bere Church, or West Donyland,

Lexden and Mile End. In these four parishes, says Vancouver, "one-third of the arable land lies in half-yearly common fields" (p. 40). The Corporation of Colchester is to this day a very large owner of arable land; how it was enclosed, and how the Corporation, as distinct from the free-men, secured the property after the passing of the Municipal Corporations Act of 1835, I do not know. The important point is conveyed in the word "half-yearly." The arable fields of Colchester were genuine common fields, subject to rights of common of pasture after harvest.

I think there can be little doubt that though much of Essex and Suffolk might have been ancient woodland, and have been enclosed directly from that condition, the primitive village community of Essex was approximately of the same type as that of central England.

NORFOLK.

Adequate material does not exist for a statistical survey of the enclosure of Norfolk, because of the disappointing habit which the promoters of Enclosure Acts for this county fell into about the year 1793,¹ and persisted in later, of not making any statement with regard to the area covered by the Act. The best statement that we can make is that 297 parishes out of 682 were enclosed by Act of Parliament.²

We have already dealt with some peculiar features of Norfolk agriculture revealed by preambles of Enclosure Acts. The chief other fact which is striking in its enclosure history is that the county is divided by the chalk ridge, which passes through the centre of the county, from north to south, and which reaches the coast at Cromer, into two parts of approximately equal area. The patches of colour which indicate enclosure by Act of Parliament are scattered indifferently over the whole map of the county; but the significance of the colour varies. East Norfolk

¹ Before 1793 thirty-one parishes were enclosed by twenty-two Acts, the area covered by nineteen of which is stated, amounting altogether to 50,187 acres. The total area so enclosed was probably not less than 54,000 acres.

² There were also eighty Enclosure Acts for the enclosure of common waste or pasture merely. In these also the area is stated for a small minority only.

has all the aspect of a country of very early enclosure. The fields are small, the hedges are big and high, like Devonshire hedges, the roads are narrow and winding. The aspect recalls Kent's previously quoted words. "There is a considerable deal of common field land in Norfolk, though a much smaller proportion than in many other counties; for notwithstanding common rights for great cattle exist in all of them, and even sheepwalk privileges in many, yet the natural industry of the people is such, that whenever a person can get 5 or 6 acres together, he plants a white-thorn edge round it, and sets an oak at every rod distance, which is consented to by a kind of general courtesy from one neighbour to another" ("Agriculture of Norfolk," 1st Edition, p. 22). The Parliamentary enclosure which took place in a parish where the neighbours had been showing this courtesy to one another consisted mainly in the extinction of common rights over enclosed land.

The making of hedges had proceeded to such an extent in East Norfolk by the end of the seventeenth century, that an anonymous author who brought out an annotated edition of Tusser's "Five hundred points of Husbandry," and "Champion and Severall," under the title "Tusser Redivivus," in the year 1710, explains the term "woodland" (a term which Tusser really used as a synonym for "several" or enclosed land) to mean East Norfolk, saying that this district was so much enclosed in small fields with fine trees in the hedges, that it was known as "the Woodlands."

At this time the western half of the county was still almost entirely open. Arthur Young wrote in 1771, "From forty to sixty years ago, all the Northern and Western and a part of the Eastern tracts of the county were sheepwalks, let so low as from 6*d.* to 1*s.* 6*d.* and 2*s.* an acre. Much of it was in this condition only thirty years ago. The great improvements have been made by reason of the following circumstances:

- (1) By enclosing without the assistance of Parliament.
- (2) By a spirited use of marle and clay.
- (3) By the introduction of an excellent course of crops.
- (4) The cultivation of hand hoed turnips.

(5) Clover and ray grass.

(6) Long leases.

(7) By the county being divided chiefly into large farms.

"Parliamentary inclosures are scarcely ever so complete and general as" (non-Parliamentary enclosure) "in Norfolk" ("Eastern Tour," Vol. II., p. 150).

William Marshall supplies a confirmatory note. "Norfolk, it is probable (speaking generally of the county), has not borne grain, in abundance, much above a century. During the passed century" (the eighteenth) "a principal part of it was *fresh land*, a newly discovered country in regard to grain crops" ("Review of the Reports to the Board of Agriculture for the Eastern Department," p. 314).

Enclosure in the western half of Norfolk and along the central chalk ridge in the eighteenth and nineteenth centuries, whether common field arable were included or not, meant the reverse of what it had meant in the first half of the sixteenth century—the conversion of land from sheeprun to arable land and to highly cultivated land. Kent, in a second edition of his report of Norfolk, published in 1796, estimated that two-thirds of the whole area of the county was then arable; and of the arable land three-quarters was enclosed, one-quarter in common field. In other words, one-half of the area of the county was enclosed arable, one-sixth common field arable. The remainder he describes as follows :

Meadows, parks, and upland pasture...	126,692	acres.
Unimproved commons	80,000	„
Marsh lands... ..	68,346	„
Warrens and sheepwalks	68,346	„

with small areas for woods, plantations, roads, lakes, rivers, and swamps. Whatever ancient common field arable had been enclosed before the beginning of the eighteenth century and converted into pasture, was apparently re-converted into arable before the end.

THE SOUTHERN MIDLANDS.

MIDDLESEX.

I have found very little information with regard to the enclosure of Middlesex beyond that obtained from the Enclosure Acts. It is remarkable that these should cover so large a part (19·7 per cent.) of the area of the county.

Of twenty-six Acts, covering 35,757 acres, twenty-three, covering 30,000 acres, belong to the period after 1793. The Board of Agriculture reporters, Thomas Baird and Peter Foot, tell us respectively (1) that there were about 50,000 acres under tillage in 1793 ("Agriculture of Middlesex," p. 7), and (2) "The Common Fields in the county of Middlesex, which are at present in a good course of husbandry, form a large proportion as to the number of acres when compared to the cultivated enclosures" (*Ibid.* p. 72).

That the common fields were "in a good course of husbandry" very probably means that the exercise of common rights had been largely restricted, and it is not improbable that while some of the ancient common fields of Middlesex became converted into small dairy farms, others became market gardens by means of a very moderate amount of interchanging of properties and holdings.

HERTFORDSHIRE.

The county of Hertford is rather remarkable for the extent of open field land (common rights have so far decayed that one can hardly call it common field) persisting to the present day. Notes have already been given on Hitchin, Bygrave, Clothall, and Wallington. There were further no less than seventeen enclosures under the Act of 1845, a number only surpassed by Oxfordshire, and in a number of other parishes small remnants of common fields are indicated by the tithe maps.

But on the whole Hertfordshire was a county of early enclosure. When the Board of Agriculture survey was made only four parishes and a part of Hitchin had undergone

Parliamentary enclosure ; but the reporter says, " There are several small common fields in this county, but these are mostly by agreement among the owners and occupiers cultivated nearly in the same way as in the enclosed state " (D. Walker, " Agriculture of Hertfordshire," p. 49).

Walter Blyth in 1649 included " Hartford " with " Essex, Kent, Surrey, Sussex," etc., as enclosed counties (" The English Improver," p. 49).

" An insurrection in hertfordshire for the comens at Northall and Cheshunt," was, according to Hales, the first beginning of the enclosure riots and rebellions in the reign of Edward VI.

It is somewhat remarkable that Hertford was in the seventeenth and eighteenth centuries so much more enclosed than the surrounding counties, than Middlesex as well as than Bedford and Cambridge, and even more enclosed than the part of Essex immediately adjoining.

Leland gives no account of the condition of the county with regard to enclosure ; but as no earlier author than Blyth speaks of Hertford as an enclosed county, I am inclined to believe that its enclosure mainly took place in the sixteenth and in the first half of the seventeenth century. It is to be noticed that Hertford was excluded from the operation of the last (39 Elizabeth, c. 2) of the Depopulation Acts, requiring that all old arable land should continue under tillage and be cultivated according to the local custom.

BUCKINGHAM.

Buckingham is, on the whole, a county of late enclosure. A large proportion (34·2 per cent.) of the area was enclosed by Acts of Parliament ; two-thirds of this enclosure belonging to the eighteenth and one-third to the nineteenth century.

The reporters to the Board of Agriculture, William James and Jacob Malcolm, supply a list of the parishes containing common fields in 1794, with an approximate statement of the area. The majority of these parishes have, of course, undergone Parliamentary enclosure since. By comparing their list with that of

the Enclosure Acts and with the summary of the tithe documents, we find that the following seventeen parishes were enclosed without Acts between 1794 and the date of tithe commutation:—

Astwood	Little Hampden	Medmenham
Buckland	Hedgerley	Great Missenden
Dinton	Horsendon	Little Missenden
Drayton Beauchamp	Great Horwood	Newton Longueville
Halton	Ickford	Quainton
Great Hampden	Marsh Gibbon	

The following five still had remains of common field at the time of tithe commutation, though the area was considerably reduced in each case:—

	Common Field Acreage.	
	In 1794.	According to Tithe Map.
	Acres.	Acres.
Burnham and Lower Boveney ...	1000	525
Chesham	300	66
Dorney	600	277
Eton	300	181
Chipping Wycombe	200	100

As so much gradual non-Parliamentary enclosure took place during the nineteenth century, it is to be supposed that the same process was also going on right through the eighteenth century.

Buckingham is traversed by the Chiltern Hills, and so is divided into two distinct regions. About half the county lies north-west of the Chilterns, on a sub-cretaceous formation, like Bedfordshire, with fertile soil, and villages thickly scattered. The remainder consists of the chalky downs and the later formations, like most of Hertfordshire and Middlesex.

The enclosure of the south-east portion was earlier than that of the north-west part. Arthur Young in 1771 was much struck

by the extent of the open fields in the latter part. The vale of Aylesbury,¹ he says, was good clay, and open field ("Eastern Tour," p. 18). From Aylesbury to Buckingham "nearly the whole country is open field, the soil among the richest I ever saw, black putrid clay" (p. 19). "As for the landlords, what in the name of wonder is the reason of their not enclosing! All this vale would make as fine meadows as any in the world" (p. 23). However, about Hockston (Hoggeston) he saw many new enclosures (p. 24). Hoggeston itself was never enclosed by Act, but several neighbouring villages had been enclosed by Acts passed previously to 1771.

Celia Fiennes passed through the same part of Buckinghamshire about eighty years before. From Stony Stratford to Great Horwood, she says, "this country is fruitfull, full of woods, Enclosures, and rich Ground. The little towns stand pretty thicke. You have many in view" (p. 97). This does not imply anything more than very partial enclosure; for Celia Fiennes, accustomed to the complete absence of hedges of her own part of Wiltshire, always notices enclosure rather than the absence of enclosure. That many little towns should be in sight of one passing through a flat country implies that it is open, except close to the villages.

Leland, in 1536, came from Bedfordshire along the boundary between Herts and Bucks and into the extreme south of Buckinghamshire, and found that enclosures had already begun. He describes the whole county in one luminous sentence, "Looke as the cuntrye of the Vale of Alesbury for the most part is clean barren of wood, and is champaine, soe is all the Chilterne well woodid and full of Enclosures" (fol. 192 a).

It seems quite clear, then, that the enclosure movement of the south-east of Berkshire was ancient; that it moved up the long slope of the Chilterns from the Thames and Middlesex, but stopped at the open chalk downs which marked the summit of the range; and that the movement which affected the enclosure of the Vale of Aylesbury and all north-western Buckinghamshire

¹ An Act for the enclosure of the common field land of Aylesbury itself was passed in the same year.

was part of the general enclosure movement of the Midlands, spreading southwards from Leicester and Northampton, as we have seen it spread eastwards.

OXFORD.

Oxfordshire may be termed a sister county to Buckinghamshire; but by far the greater part of the county lies north-west of the Chiltern Hills, which occupy the south east extremity. We find, as we should expect, that the history of the enclosure of Oxfordshire resembles that of Bedfordshire and of North-West Buckinghamshire; 45·6 per cent. of the area of Oxfordshire underwent Parliamentary enclosure compared with 46·0 per cent. of Bedfordshire and 34·2 per cent. of Bucks; in Oxford about 62 per cent. of the total Parliamentary enclosure belonged to the eighteenth century, in Bedford 54 per cent., in Buckinghamshire 66 per cent. Oxford, however, is remarkable for the extent of the enclosure (eighteen Acts enclosing 23,578 acres) under the General Enclosure Act of 1845.

Richard Davis, the Board of Agriculture reporter, while he gives a very full statement of the methods of cultivating the common fields of the county, makes no statement with regard to their extent.

As in Buckinghamshire, partial enclosure, particularly in the immediate neighbourhood of the villages, had taken place before the eighteenth century. Celia Fiennes found "Oxford Environ'd round with woods and Enclosure. vet not so neare as to annoy the town which stands pleasant and Compact," and from the Malvern Hills she says "Oxford, Gloucestershire, &c. appears in plaines, enclosures, woods and rivers and many great hills" (p. 33). By "plaines" stretches of common fields are to be understood.

Leland found no enclosure in Oxfordshire in any part he visited.

THE NORTH OF ENGLAND.

LINCOLN.

Lincoln and the East Riding of Yorkshire have a similar enclosure history. Each was largely enclosed by Acts of

Parliament; in each nearly four-fifths of the Parliamentary enclosure was effected in the eighteenth century; in each enclosure was not marked either by a general conversion of arable into pasture, as in Leicestershire, or by a general conversion of pasture into arable, as in Norfolk; in both a considerable proportion of the common-field land before enclosure was worked on the two-field system. As much as 40·1 per cent. of the East Riding of Yorkshire is covered by the Acts for enclosing common-field parishes, and 29·3 per cent. of Lincolnshire; but for the latter county there are also Acts for enclosing great extents of commonable marshes; and including these and other Acts for enclosing commons and wastes, about 35 per cent. of Lincolnshire has undergone Parliamentary enclosure.

A good deal of non-Parliamentary enclosure took place during the nineteenth century. Thomas Stone, the Board of Agriculture reporter, estimates that there were in 1793, 200,000 acres of commons, wastes, and unimbanked salt marshes, and 268,000 acres of common fields. He over-estimates the total area of the county so much, that to rectify his figures we have to deduct 10 per cent.—this leaves 421,000 acres of common fields and other commonable lands. There have been enclosed by Parliamentary action since 207,659 acres by Acts for enclosing common-field parishes, and about 74,000 acres by Acts for enclosing other commonable lands; if we suppose there are 12,000 acres of common fields and commons surviving, this accounts for 293,659 acres, and leaves about 127,000 acres unaccounted for—*i.e.*, enclosed by non-Parliamentary process during the nineteenth century.

If the same proportion between the scope of the two methods be supposed to have held good during the earlier part of the period of Parliamentary enclosure, it would follow that at the beginning of that period (1730) Lincolnshire was about half enclosed and half open.

From the references to Lincolnshire by our tourists, one would expect to find a less degree of enclosure. Arthur Young, in 1768, that is, after fifty-three Enclosure Acts for Lincolnshire had been passed, found the country from Stamford

to Grimsthorpe mostly open ("Northern Tour," p. 77), from Grimsthorpe to Colsterworth chiefly open, Colsterworth to Grantham, enclosed on the right hand, open on the left (p. 84), and from Grantham to Newark all open (p. 94). Celia Fiennes, about 1695, following the same road, found no enclosures but a "fine champion country." Leland gives the same testimony.

By comparing Celia Fiennes with Arthur Young, we have evidence of enclosure proceeding in the south-west of Lincolnshire between 1695 and 1768, which is partly, but not entirely, accounted for by Parliamentary enclosure. The three descriptions give the impression that up to the beginning of Parliamentary enclosure Lincolnshire was much less than half enclosed. It is, however, not difficult to reconcile this with the conclusion inferred from Thomas Stone's statement and the Enclosure Acts; for none of the three travellers touched more than the western part of the county. No doubt the eastern part was earlier enclosed. This is, indeed, indicated by the distribution of Parliamentary enclosure, as shown by the map.

THE EAST RIDING OF YORKSHIRE.

We have no estimate of the extent of common-field land in the East Riding from the Board of Agriculture reporter; but Arthur Young, in his "Northern Tour," describes the part between Sheffield and Goole and the East Riding as about half open and half enclosed (pp. 172—210). He further says (p. 178) that in the East Riding "Inclosures and turnpikes were carried on with great spirit during the late war" (*i.e.*, "The Seven Years' War"). Nine Acts were passed for the enclosure of eleven parishes during that war; but this can only have been a part of the spirited proceedings.

As in the case of Bedfordshire, when we allow for marshes along the Humber, and hill country on the Wolds, which never passed through the common-field system, for the indubitable non-Parliamentary enclosure proceeding side by side with Parliamentary enclosure, and particularly for the active enclosure spoken of by Arthur Young in the middle of the eighteenth

century, there remains but little enclosure of common fields to be attributed to earlier centuries. Some such enclosure must be assigned to the sixteenth century. The Commission of 1517 inquired into nearly the whole riding and found 1560 acres of arable land enclosed, 1545 acres of which were laid down to grass (W. S. Leadam, "The Domesday of Inclosure").

Leland also found some enclosure in the East Riding, which he traversed pretty completely. (*See Appendix C.*)

We have mention of a park and of enclosed land in four different places, though in each of the four only for about a mile of the route.

THE NORTH AND WEST RIDINGS.

The North and West Ridings of Yorkshire were much earlier enclosed than the East Riding. This is the natural consequence of the fact that in early times they possessed a much smaller proportion of arable land, and, as I have shown in a previous chapter, the more pasture predominates, the less the common-field arable is able to resist the tendency to enclosure. The difference between the proportions of the three ridings covered by Enclosure Acts, by which common fields were enclosed is striking: East Riding 40·1 per cent., West Riding 11·6, North Riding 6·3. But this understates the case, for I include all Acts whereby any arable common field at all is enclosed, and in the North and West Ridings many of these Acts are for the enclosure of a great stretch of moor and a mere remnant of common field, and these unduly swell the total. Examples are an Act in 1791 for the enclosure of 6000 acres of common, and 30 acres of "mesne inclosures," *i.e.*, of intermixed tilled land which is separated from the surrounding common pasture by a hedge; an Act in 1801 for the enclosure of 150 acres of common field and common meadow, and 4000 acres of common pasture at Kettlewell and Conistree; an Act in 1815 for the enclosure of a wretched remnant of nine acres of common field arable, and 6330 acres of common. The existence of such remnants of common field arable bears witness to the gradual enclosure which would have entirely extinguished them a little later, if

the opportunity of the enclosure of the commons had not been seized to bring them also within the scope of the Acts.

William Marshall's account of the enclosure of the Vale of Pickering has already been given. Arthur Young in 1768 describes the view from the road from Kirby Moorside to Cleveland as one of "extensive valleys cut into innumerable inclosures" ("Northern Tour," Vol. II., p. 93). Enclosure was the rule all the way from Driffield northwards.

Celia Fiennes kept more to the West Riding. From Darlington to Richmond, "I went through Lanes and Woods, an Enclosed country" (p. 183). Richmond to Boroughbridge was for 3 or 4 miles through narrow lanes, then for 5 or 6 through common (p. 184). From Knaresborough to Leeds "it was much in Lanes and uphill and Downhills, some little part was open common" (p. 184). From Leeds to Eland "much in enclosures" (p. 185). About Eland "all the hills full of inclosures" (*ibid.*). From Eland to Blackstone Edge, "these parts have some resemblance to Darbyshire, only here are more woody places and inclosures" (p. 186).

The earlier history of the enclosure of most of the West Riding and North Riding is summed up in the passage from Walter Blyth:—"Woodlands went before inclosure to be relieved by the Champion, and now become gallant corn countries. . . . West of Warwick, North of Worcester, Staffordshire, Shropshire, Derbyshire, Yorkshire, and all the Countries thereabouts" ("English Improver," p. 40). For while Celia Fiennes found so much enclosure, Leland found chiefly moor and forest, yet more enclosure than "Chaumpaine."

The great contrast between the description given by Celia Fiennes and that given by Leland sufficiently confirms the statement of Walter Blyth, which we may amplify as follows:—Enclosure made little progress in Yorkshire before the middle of the sixteenth century, but thenceforward it was pushed steadily on mainly by the tilling and enclosing of common wastes and pastures, and the clearing and cultivation of forests in the North and West Riding, and the common-field arable also underwent division and gradual enclosure. That the Vale

of Pickering in the North Riding and the district between Sheffield and Goole in the West Riding, being the parts where arable common fields most predominated, were the last of the cultivated districts to be enclosed; the Vale of Pickering being mainly enclosed by non-Parliamentary means in the first half of the eighteenth century; the South Yorkshire district being largely enclosed by Acts of Parliament in the second half of the eighteenth and the beginning of the nineteenth century.

Lastly attention must be drawn to the great number of Acts of Enclosure for Yorkshire enclosing common pasture or waste only.

NOTTINGHAMSHIRE.

Nottinghamshire may be said to consist of an ancient "champaign" district, which has an enclosure history exactly similar to that of the neighbouring districts of Northamptonshire and Lincolnshire, and an ancient forest district.

The county as a whole has a percentage of Parliamentary enclosure, 32·5, which must be considered high when allowance is made for the fact that so much land must have been enclosed directly from the forest state without passing through the common-field system. The two surviving examples of common-field parishes, Laxton and Eakring, have been before described; Bole also was till recently unenclosed.

The Board of Agriculture reporter, Robert Lowe, attempted to give an account of the state of enclosure of the different parishes in 1793, but evidently found it beyond his powers to make the lists at all complete. But his list of unenclosed parishes enables us to give the following nine parishes as enclosed without Parliamentary intervention since 1793:—

Askham	Saundby	South Wheatley
Kirklington	Treswell	Kneesall
Rampton	North Wheatley	Widnerpool

together with the hamlets of Ompton and Clipston.

And his list of recently-enclosed parishes enables us to give

the following nine parishes as enclosed without Parliamentary sanction shortly before 1793 :—

Bingham	Shelton	Orston
Carcolston	Cotham	Sibthorpe
Selston	Kneeton	Thoroton

together with the hamlets of Aslacton, Newton, Oldwork, and Cropwell Butler.

All these had been enclosed, he says, within the previous twenty years.

The fact that the extent of non-Parliamentary enclosure in Notts., in the period from 1773 to 1793 is just equal, according to this, to that of the non-Parliamentary enclosure after 1793, is a slight clue to the probable extent of non-Parliamentary enclosure in the eighteenth century in other counties similarly circumstanced.

We should expect, then, to find the part of the county which was anciently tilled, practically entirely open, at the beginning of the eighteenth century. This is confirmed by the evidence, so far as it goes. Celia Fiennes says: "From Nottingham Castle I saw a prospect more than 20 mile about. The land is very rich and fruitfull, so the Green meadows with the fine corn fields which seemes to bring forth in handfulls. They see most of Barley and have great encrease, there is all sorts of Graine besides, and plaines and Rivers and Great woods and Little Towns all in view " (p. 56).

Leland was similarly struck with South Nottingham. Coming south from Rotherham he found "very woody Grounde," then "hethy," then "Corny and Paster," then "Ground very frute-ful of Corne" (Vol. V., fol. 91, 92). But when he got past Nottingham the view made him burst into Latin. "After that I cam a little beyond Trent I saw all Champaine Grounde undecunque within sight, and very little wood but infinita frugum copia."

DERBY.

The enclosure history of Derbyshire closely resembles that of the West Riding of Yorkshire. A somewhat larger part

(16·5 per cent.) of it underwent enclosure by Acts for the enclosure of common-field arable in conjunction with other commonable land, and about 5 per cent. more by Acts for the enclosure of common pasture and waste. The common-field arable is frequently called "mesne inclosures" (sometimes "mesne field"), showing that the idea of a hedge was that it surrounded the corn crops to keep out beasts, not the pasture to keep them in. Celia Fiennes gives a general description of the county: "You see neither hedge nor tree but only low drye stone walls round some ground, Else its only hills and dales as thick as you Can Imagine" (p. 77). "All Darbyshire is but a world of peaked hills."

It will be remembered that it had by 1649, according to Blyth, become a gallant corn country through enclosure. Leland passed it by.

DURHAM.

The history of the enclosure of Durham is told by the Board of Agriculture reporter in a sentence: "In this county the lands, or common fields of townships, were for the most part inclosed soon after the Restoration. . . . The common fields are few in number and of small extent" (Joseph Granger, "Agriculture of Durham," p. 43).

All other evidence simply confirms this statement. The Enclosure Acts for enclosing common fields are but five in number, and the most extensive of them covers only 800 acres, of which part only is common field. (The Enclosure Acts of the other type are numerous in comparison and extensive in scope, one covering 10,000, one 20,000, one 25,000 and one 28,000 acres).

The statement, too, is confirmed by two contemporary authors, previously quoted, and by the records of Leland and Celia Fiennes. Celia Fiennes says that from Newcastle to Durham "the whole county looks like a fruitful woody place" (p. 178), and she compares it to the neighbourhood of Blackheath (p. 179), from which we must infer some open common, but all the cultivated land in a state of enclosure.

Leland traversed the whole county but found no enclosure. Nor does he describe any part of the county as "champaine" but merely as good corn, or grass, or moor, or mountain. It is, I think, safe to conclude that there were no extensive stretches of common-field arable within view; but also, one is inclined to infer that enclosure had not yet begun.

Further, there is an illuminating note from Arthur Young (1768): "Farms become large on entering Northumberland, after the small ones of Yorkshire and Durham" ("Northern Tour," Vol. III., p. 61).

It has to be borne in mind that the disorder on the Border checked the development of agriculture till the accession of James I., probably at least as far south as the North Riding of Yorkshire. With the gradual increase of population, and improvement of roads, cultivation spread over the wastes; first in Yorkshire, then in Durham, then in Northumberland. At first the agent was a peasant, carving a small farm for his own maintenance, later a landlord or farmer able to employ labourers and work a large farm.

That the enclosure of Northumberland took place later than that of Durham, and was the work of the eighteenth and nineteenth centuries, is on *a priori* grounds probable, and is further indicated by the fact that Celia Fiennes makes no mention of enclosure in her account of her ride from the Scottish border into Durham. A further reference to the enclosure of Northumberland will be made when we come to Cumberland.

THE SOUTH-EAST OF ENGLAND.

KENT.

Kent is certainly a county of very ancient enclosure. This is clearly indicated by the fact that not a single Act for the enclosure of common field has been passed by the whole county. It is also witnessed by a whole series of writers, from Boys, the Board of Agriculture reporter, who says, "There are no Common Fields in Kent,"¹ to the author of the "Discourse of

¹ "Agriculture of Kent" (1796), p. 44.

the Commonweal," "those counties which be most enclosed, as essex, kent, devenshire."

But in Kent it would appear that if some investigator as careful as Vancouver had at a somewhat earlier date reported on the agriculture of Kent, he would have found some remains of arable common fields in the far eastern corner of the county. William Lambarde, in the "Perambulation of Kent," 1570, says: "The soile is for the most part bountifull, consisting indifferently of arable, pasture, meadow and woodland. Howbeit of these wood occupieth the greatest portion even to this day except it be towards the east, which coast is more champaigne than the residue" (p. 3).

More than a hundred years later, Celia Fiennes says: "Canterbury to Dover was a good road and a sort of Champion Country" (p. 103). It was open, it was mainly arable land, but it differed in some respect from the Champain of the Midlands; and again, a hundred years later, William Marshall writes in 1798 of the Isle of Thanet: "The whole country lies open, excepting in the immediate environs of villages. . . . The present productions, if we cut off the marsh lands, may be said to be arable crops" ("Southern District," Vol. II., p. 6).

This was written, it will be noticed, just after Boys had written his statement that there were no common fields in Kent. We can reconcile the two statements if we suppose that by the disuse of rights of common, and by the consolidation of scattered properties and holdings by mutual exchanges, the characteristics of common field had been abolished, while in consequence of there never having arisen any tendency to convert the arable land into pasture, no necessity for the expensive labour of making hedges arose. But I have no evidence to show at what date the open arable land ceased to be common field.

The question arises whether the common-field system of the ordinary English type ever existed in this part of Kent; and here again there is no decisive evidence that I know of by which to answer the question. The fact that the similar question for Essex is answered in the affirmative by the Colchester common

fields perhaps counts for something; and that the Surrey common fields come at Croydon close to the county boundary, for a little more. At Eltham there is an old charity called the Fifteen Penny Lands; only a few acres remain in the form of land, the rest having been sold and the proceeds invested; but there still remains an acre described as "Land in East Field, Dockland's Shot." In 1578 a member of the Roper family, perhaps Margaret Roper, the daughter of Sir Thomas More, or her husband, bequeathed to Eltham "a parcel of ground containing by estimation four acres, in the common field, called East Field."¹ Eltham was a royal manor, hence likely to preserve old customs to a later date than other manors, and the arrangement of ancient common fields, particularly towards Eltham Common, seems clearly traceable. In Addington, an ecclesiastical manor, it seems easy to trace the signs of ancient common, commonable meadow, and common fields.

THE WEALD.

The whole of the Weald of Kent, Surrey, and Sussex appears never to have passed through the common-field system. This is indicated in the first place by the fact that there have been no Enclosure Acts for enclosing common fields. Secondly, we have what may be termed the expert evidence of William Marshall, the shrewdest of all the eighteenth-century agricultural writers, and the only one really interested in the origin and early history of the common-field system. He says of the Maidstone district, "the entire district appears to have been inclosed from the forest or pasture state. I observed not a trace of common-field lands" ("Southern District," Vol. I., p. 21). Of the Weald of Kent, "The whole is in a state of inclosure, and mostly divided by wide woodland belts, into well sized fields" (*Ibid.*, p. 345). Of the Weald of Sussex, ". . . there being, I believe, no trace at present, of common fields having ever gained an establishment" (Vol. II., p. 100). "The whole of the district (between Pulborough and Midhurst) under view

¹ Geo. Rathbone, "History of the Eltham Charities," p. 5.

Enclosed before the General Enclosure Act of 1801.

• between 1802 and 1845

• under general enclosure Act of 1845.



R. Thames

S U R R E Y

S U S S E X

Scale 1: 1,000,000 or 1 inch = 15.78 Stat. miles.

5 0 5 10 15 20

I. OF WIGHT

is in a state of Inclosure ; except a few small heathlets and commons ; and except a small remnant of common field in the Maam soil." The Maam soil, he says, is a vein of land of peculiar nature at the foot of the chalk hills, to be identified, presumably, with the Gault formation.

In 1649, seeing that a considerable amount of common field survived in the part of Surrey north of the North Downs, until the time of Parliamentary enclosure, and some in Sussex south of the South Downs, and in spite of this, Blith speaks of Surrey and Sussex as enclosed counties, enclosure must at least have predominated in the Weald.

Celia Fiennes adds a confirmation. Sussex, she says, is "much in blind, dark lanes" (p. 32). This implies narrow roads, with well-grown hedges, that is, ancient enclosure. For roads are everywhere broad in proportion as the industrial state at which enclosure takes place is advanced. Again, from Calvery to Branklye, "the way is thro' lanes, being an Enclosed Country for the most part, as is much of Sussex which joyns to Kent" (p. 112). And the view from Boxhill was that of "a fruitfull vale, full of inclosures and woods" (p. 32).

NORTH SURREY.

The part of Surrey which lies on the north slope of the North Downs, from the Kent boundary to the Bagshot sands, contained up till the time of Parliamentary enclosure a considerable proportion of common-field land, as may be seen by the appendix and the map.

James and Malcom, the reporters for Surrey, give a list of the chief common fields remaining in 1793 ("Agriculture of Surrey," p. 43), from which we find that besides Merrow, enclosed about 1870, East and West Clandon, Ashtead and Thorpe have been enclosed without Acts since. In each of these four cases enclosure took place before the date of tithe commutation.

But even this part of Surrey must be considered as on the whole an early enclosed district; as much so, in fact, as the corresponding

slope of the Chiltern Hills, and the Hertfordshire Hills on the other side of the Thames.

THE SEA COAST OF SUSSEX.

The western part of the south slope of the Sussex Downs has a few examples of common fields surviving to a late date, but they are fewer in number and smaller in area than on the north slope of the Surrey Downs. William Marshall says: "In the Isle of *Selsey* I observed some common field land; also about Chichester, in the year 1791" (Southern District, Vol. II., p. 230.) The accompanying map shows the parishes enclosed by Acts.

WESSEX.

Under the heading of Wessex I include the counties of Hampshire, Wiltshire, Berkshire and Dorset. There is a close resemblance between the enclosure history of each of these; while Gloucester is a connecting link between them and the Midland counties on the one hand, and the south-western on the other. It may be described as at present a country of very large farms, with a very large proportion of open down, the cultivated land itself remaining remarkably open, being divided in general into large rectangular fields by hedges which are frequently full of gaps. Rights of common here more than elsewhere have decayed, irrespective of actual enclosure; and using the word enclosure in its broad sense, it may be said that in Wessex the process of enclosure has least of all taken visible shape, either in the growing of hedges, or building of walls, or in the conversion of arable to pasture, or pasture to arable, or in the scattering of the habitations of the inhabitants over the whole parish; but that it has most profoundly affected the social life of the villages. The case of Grimstone, in which the nine "livings" for generations held by about a dozen different copyholders, was converted into a single farm, and by no means an exceptionally large one, is typical of the whole district. This aspect has been previously treated. What here has to be noticed is that these characteristics of Wessex enclosure make

it more difficult to trace the progress, at least so far as the higher lands are concerned. If Celia Fiennes could revisit the neighbourhood of Amesbury and Stonehenge, she would probably again describe it as "all on the downs, a fine champion country." It is fortunate that we have the accounts of two such expert observers as Thomas Davis and William Marshall. They wrote practically at the same date, Marshall apparently in 1792, Davis in 1793; but as Marshall confines himself to the actual condition, while Davis deals with the past, he must here take precedence.

"THE WESTERN CHALK HILLS.

Basingstoke to Salisbury.—The state of inclosure varies. To the eastward the country is mostly inclosed, much of it in large, square, regular inclosures. More westward, it is entirely open; as are the tops of the higher hills throughout. Extensive views, with no other break, than what is given by corn or flocks, fallows or the sheep fold.

Environs of Salisbury.—To the southward of the town there are some well-sized, square fields, with good live hedges (at least on three sides) apparently of forty or fifty years' growth; yet, extraordinary as it is, many of these fields lie open to the roads; the fences on the sides next the lanes lying in a state of neglect. And, to the north of the Avon, the country for many miles every way, lies open, unless about villages and hamlets, and along the narrow bottoms of the watered valleys. To the eastward of Salisbury an attempt has been made at inclosure; the ruins of the hedges are still evident; broken banks, with here and there a hawthorn. And similar instances are observable in other parts of the Downs.

"Are we to infer from hence, that chalk down lands are not proper to be kept in a state of inclosure? Or that where sheep are kept in flocks, and few cattle are kept, fences are not requisite? Or is the foliage of shrubs a natural and favourite food of sheep, and hence, in a country chiefly stocked with sheep, it is difficult to preserve a live hedge from destruction?"

"Ludgershall to Basingstoke.—The country is wholly inclosed: excepting a few plots to the right; mostly in large square fields, doubtless from a state of open down; the hedges in general of a Middle Age; some instances of vacant inclosure.

"With respect to the present state of appropriation of this tract of country,¹ the mere traveller is liable to be deceived. From the more public roads, the whole appears to be in a state of divided property. But on a closer examination, much of it is found to be in a state of commonage. In the immediate environs of Salisbury, there are evident remains of a common field, lying in narrow strips, intermixed, in the south of England manner; and not far from it, a common cow pasture and a common meadow. About Mere" (on the Somerset border of Wiltshire) "I observed the same appearances. In the Valley of Amesbury much of the land remains, I understand, under similar circumstances, though they do not so evidently appear in the arable lands, which by the aggregation of estates, or of farms, or by exchanges among landlords and their tenants, lie mostly in well-sized pieces. But the after-eatage,² whether of the stubbs or the meadows, is enjoyed in common. And the grass downs of the common field townships are in a state of common pasture the year round; being stinted by the arable lands" ("Southern District," p. 308, etc.).

One fact to be noticed is that Hampshire was earlier enclosed than Wiltshire; which is in accordance with what one would have expected. Enclosure spread westwards into Hampshire from Surrey and Sussex.

Davis I have previously quoted. "The greater part of this county (Wiltshire) was formerly, and at no very remote period, in the hands of great proprietors. Almost every manor had its resident lord, who held part of the lands in demesne, and granted

¹ *I.e.*, the whole of the district he calls "the Western Chalk hills."

² "After-eatage." This is Marshall's variant of "average," showing his theory of the etymology of the word, a theory which might have been suggested to him by the quaint phrase common in Enclosure Acts: "The averages whereof are eaten and enjoyed by the proprietors according to a recognised stint."

out the rest by copy or lease to under tenants, usually for three lives renewable. A state of commonage, and particularly of open common fields, was peculiarly favourable to this tenure. Inclosures naturally tend to its extinction.

“The North-West of Wiltshire being much better adapted to inclosures and to sub-division of property than the South, was inclosed first ; while the South-East or Down district, has undergone few inclosures and still fewer sub-divisions ” (“Agriculture of Wiltshire,” p. 8).

We have previously seen that Cobbett, traversing that same South-East district of Wiltshire, found in 1825 the common field or “tenantry” system completely superseded by that of great farms. Parliamentary enclosure only partly effected the change, which appears to have been so complete in the space of a single generation, 1793—1825. The violent fluctuations in the price of grain during the great war, the wholesale ruin of farmers in 1815 and 1816, the abuse of the Poor Law peculiarly rampant in Wiltshire, by which the peasants who held such little holdings as we have observed in Fordington and Stratton and Grimstone, by lease or copy, were compelled to pay in their rates the wages of the labourers employed by the great farmers who were superseding them, and the decay of home industries to which Cobbett bears witness, all these were complementary parts of the social transition, each assisting all the others, and all together converting the tiller of the soil from the peasant with a medieval status, a responsible member of a self-governing village community, into a pauperised, half-starved labourer.

Though North-West Wiltshire was enclosed earlier than the South-East, Berkshire was enclosed later than Wiltshire as a whole. This is indicated by the scope and distribution of Enclosure Acts. Parliamentary enclosure covers 26·0 per cent. of Berkshire, 24·1 per cent of Wiltshire. Of the total 120,002 acres enclosed by Act in Berkshire, 42,631 acres was enclosed in the eighteenth century ; 77,371 acres in the nineteenth. In Wiltshire the proportions are reversed ; 126,060 acres were enclosed in the eighteenth century, 86,073 acres in the nineteenth.

The non-Parliamentary enclosure in the nineteenth century was peculiarly active in Berkshire. William Pearce, the Board of Agriculture surveyor, computed that in 1794 the common fields and downs occupied 220,000 acres; forests, wastes, and commons, 40,000; and the enclosed lands, including parks and woods, only 170,000 acres ("Agriculture of Berkshire," p. 13). He further assures us that at least half of the arable land was in common fields (p. 49). As rather less than 20 per cent. of the total area of the county was enclosed by Acts at a later date, it would follow that about 80 per cent. of its area was enclosed without Acts after 1793; and from my own inquiries I can quite believe this conclusion is accurate. Enclosure under the general Acts of 1836 and 1840 may have been specially extensive in Berkshire.

Dorset underwent enclosure at an earlier period. The percentage of Parliamentary enclosure is only 8·7, which is similar to that of Hampshire, 6·0; and there is no evidence of very extensive non-Parliamentary enclosure in the nineteenth century. Stevenson in 1812 reported, "There are but few uninclosed fields remaining" ("Agriculture of Dorset," p. 194); and the earlier reporter, Claridge, in 1794, said, "Very few parishes in this county have of late years been enclosed" ("Agriculture of Dorset," p. 46). In the intervening period only fourteen Acts enclosing sixteen parishes were passed; Dorset must therefore have been mainly enclosed before the time of the American War; enclosure having no doubt spread eastwards from Devonshire, which was a very old enclosed county.

Celia Fiennes adds little to our information, except that she says the Vale of the White Horse, in Berkshire, "extends a vast way, a rich inclosed country" (p. 19), that there were "Good lands, meadows, woods and inclosures in the Isle of Purbeck, (p. 6), and that the country round "Stonidge," like that round Newton-tony, was "most champion and open, husbandry mostly corn and sheep" (p. 10). But there is a significant passage in John Norden, which shows that the characteristic Wiltshire and Dorsetshire common-field management in 1600 prevailed over all four counties. "In Dorset, Wiltshire, Hamshire, Barkeshire,

and other places champion, the farmers do much enrich their land indeed with the sheepfold " (Book V., p. 232).

Leland, however, is full of information. He came into Berkshire at Wallingford, and rode thence to Abingdon and to Oxford. The first touch of description is " About this Sinodune beginneth the fruteful Vale of White Horse—this Vale is not plentifulle of woodde " (Vol. II., fol. 14). This must be compared with Celia Fiennes' description of the same Vale, " a rich inclosed country." He next proceeded westwards along the southern side of the Thames. " From this place " (Hinxey hill, one mile from Oxford) the hilly ground was " meately woody for the space of a mile, and thens 10 miles al by Chaumpain, and sum Corne, but most pasture, to Farington." He crossed the river and entered Gloucestershire, but turning south entered Wiltshire, and found the eight miles from Cirencester to Malmesbury " about a Mile on Furse then al by Champayne Ground, fruteful of corne and Grasse, but very little wood " (fol. 26). To Chippenham " al the Ground on that side of the Ryver was Chaumpayne " (fol. 28) but towards Bradford " the countre beginneth to wax woddy " (fol. 30) ; and then he went west into Somerset, Devon and Cornwall. He came back into Dorset from Axmouth, and in the extreme western part of Dorset gives no distinct description of the state of enclosure—it is " meately good ground " or " corne, pasture and wood ; " but from Melbury to Frome was " vj miles stille by Champaine ground on an high rigge " (Vol. III., fol. 47). He came through Weymouth and Poole, and specified neither enclosure nor champain, till he reaches the north-west corner of the county ; but from Hoston to Cranbourne is " al by Champain Ground having nother Closure nor Wood," and all the way to Salisbury continues " al by Champayne " (fol. 56). Again, " all the way from Salisbury to Winchester is Champayne," but from Winchester to Southampton, while there is " mouch drye feren Ground," " the most part of the Ground betwixt is enclosid and reasonably woddyd " (fol. 74).

To Portsmouth enclosure predominated in the cultivated land. There is " much enclosid and Hethy Ground myxt with Ferne "

(fol. 79), and "the Ground within the Isle of Portsmouth is partely enclosed" (fol. 82). Turning north there was some "playn Ground" before entering Bere forest, afterwards "enclosid Ground" to Bishops Waltham, and for three miles beyond; the remaining four to Winchester being "Champain" (fol. 83).

But particularly in Dorset, instead of describing the land as enclosed, or "Champain," he frequently uses such expressions as "meately well woddid" or "good Corne and sum Grasse," which it is difficult to interpret in terms of enclosure. The choice of such expressions probably implies (1) that there is not much actual enclosure by hedges, and (2) that there are no *extensive* arable common fields. Such descriptions would suit land passing directly from the condition of forest or moor into separate cultivation, but in which the cultivated patches were not as yet enclosed with hedges; or a district in which small arable common fields were surrounded by such later extensions of cultivation. But leaving Dorset in doubt, it is clear from Leland's notes that enclosure was well begun in the south of Hampshire, while the country to the north was all open.

In the above journey Leland skirted the central chalk district; later he passed directly through it, going from Oxford through Abingdon, Lambourn, Marlborough and Devizes to Trowbridge. He passed the forests of Savernake and Blake, but all the cultivated land is described as "champayne" (Vol. VII., Part 2, fol. 63-7).

To sum up, we find that in the south of Hampshire, the cultivated land was early enclosed, and also probably in the south and west of Dorset, that enclosure gradually spread from the middle of the sixteenth century into the rest of the four counties, the movement attacking the "champain" district on three sides, on the east from Surrey, on the south from the early enclosed district between Winchester and Southampton and Portsmouth, and in the west from Devon and Somerset; the progress of enclosure appears to have been practically confined to Dorset and Hampshire in the seventeenth century; to have had the north-west of Wiltshire for its chief scene in the greater part

of the eighteenth century, and finally to have attacked south-east Wiltshire and Berkshire, the former in the first quarter, the latter throughout the first half, of the nineteenth century.

GLOUCESTER AND WORCESTER.

The whole of Gloucester, with the exception of the Forest of Dean and its neighbourhood in the west, has scattered over its parishes enclosed by Acts of Parliament; and the enclosure so effected amounted to nearly a quarter (22·5 per cent.) of the whole area of the county. The rich land in the Severn Valley was the latest enclosed district. William Marshall tells us that in 1789 "perhaps half the vale is undivided property." ("Rural Economy of Gloucestershire," Vol. I., p. 16.) As enclosure by Act of Parliament, and doubtless also without Acts, had been proceeding vigorously since 1726, it is probable that at the earlier date nearly the whole was in "a state of commonage." Of the Cotswold Hills, Marshall says: "Thirty years ago (*i.e.*, in 1759) this district lay almost entirely in an open state, namely, in arable common fields, sheep-walk, and cow-down. At present it may be said to be in a state of Inclosure, though some few townships yet remain open." (*Ibid.*, Vol. II., p. 9.)

I have already pointed out that in Gloucestershire enclosure without Acts was specially easy, in consequence of the custom of holding land. The ancient custom of "copyhold by three lives renewable" had very generally been converted into "leasehold by three lives renewable," the difference being that the lord of the manor's option of accepting a new life became real instead of nominal. It was easy for a landlord who wished to enclose to convert each such lease as it fell in to one for a short period of years; and it was in this way, Marshall says, the enclosure of the Cotswold Hills was mainly effected.

The south-west of Gloucestershire, towards Somerset, to a considerable extent shared in the early enclosure of that county; though for Somerset we have also to say that while the western half was, like Devonshire, very early enclosed, the eastern half to a certain extent shared in the comparatively late enclosure

Gloucestershire and the north-west of Wiltshire, as the map shows.

Worcester similarly shows the transition between South Warwickshire, the enclosure history of which has been dealt with, and the counties on the Welsh border. Pomeroy reported in 1794 to the Board of Agriculture: "The lands are in general inclosed; there are, however, some considerable tracts in open fields." About 45,000 acres have since been enclosed by Acts for enclosing common fields *inter alia*; which is perhaps as large an area as the phrase "considerable tracts" is intended to describe. Just one-sixth of the total area of the county is covered by the whole series of such Acts, mainly in the eastern half of the county. Leland tells us "most part of all Somersetshire is yn hegge rowys enclosid" with elms, and from his other notes we find that the north-west half of Worcestershire was enclosed by about 1540, and the southern extremity of Gloucestershire about half enclosed by that date. We further find, from evidence quoted above, that the rest of Worcestershire shared the enclosure experience of Warwick and Leicester, though probably at a somewhat earlier date, that is, undergoing enclosure mainly in the seventeenth and eighteenth centuries, though in the end the process dragged on and was only completed after the Act of 1845 was passed. We find the Cotswold Hills enclosed mainly between 1750 and 1790, the Severn Valley undergoing enclosure during this period, but only about half enclosed at the end of it, and enclosure continuing steadily to the very end of the nineteenth century, with Elmstone Hardwicke still remaining uninclosed, waiting for leases for lives to expire.

THE CELTIC FRINGE.

The part of the country which remains to be considered is that in which the problem is complicated by the question whether the primitive village community was of an English or Celtic type. The remaining counties may be grouped under the titles West Wales, Strathclyde and the Welsh border.

We have previously seen that fluidity in the tenure of the soil,

which is one characteristic of the Celtic run-rig as compared with the Anglo-Saxon common field system, favours the separation of properties and holdings at the time when co-aration ceases to be practised; and, in consequence, to early enclosure without any special efforts of the type of an Act of Parliament. But we have also seen that a prevailingly pastoral country tends to have its arable lands more easily and earlier enclosed than a prevailingly arable country. There are therefore two explanations available for the early enclosure of the whole western half of England and Wales.

First, however, the broad facts with regard to the history of enclosure must be made clear.

There are no Acts specifically for enclosing common arable fields in Wales, nor any in which the phraseology of the preamble clearly indicates the existence in Wales of land possessing all three of the essential characteristics of English common field: (1) intermixed ownership or occupation, (2) absence of adequate hedges or other obstacles to the passage of men and animals from one holding to another, (3) common rights exercisable over the tilled land.

But there were¹ in Wales open tilled fields in which properties and holdings were intermixed—that is, land possessing the first two characteristics. Several Welsh Acts for enclosing commonable waste also enclose “intermixed lands,” and one (1843, c. 14) is for the enclosure in Llandudno and three neighbouring villages, of “Divers Commons, commonable lands and waste grounds, Heaths, open and Common and other Fields and Waste lands, and other Common lands and Waste grounds, which lie intermixed in small parcels, and are inconveniently situated for the use and enjoyment of the several proprietors.”

The following are the reports on the subject by the Board of Agriculture reporters in 1793 and 1794:—

“Open or Common Fields are rarely met with in South Wales.

¹ Many townships in North Wales still contain “quilleted” areas, *i.e.*, enclosed fields containing unenclosed strips of land belonging to a different owner or owners from that of the rest of the field. Such scattered “quillets” are, as in Berkshire, frequently glebe land.

It is a mode of cultivation only practised in a few instances, where ecclesiastical and private property are blended." (John Fox, "Agriculture of Glamorgan," p. 41.)

"The only tract like a common field is an extent of very productive barley land, reaching on the coast from Aberavon to Llanrhysted. This quarter is much intermixed, and chiefly in small holdings." (Thomas Lloyd, "Agriculture of Cardigan," p. 29.)

Carmarthen. "I do not know of any considerable extent of open common field in the county." (Charles Hassell, "Agriculture of Carmarthen," p. 21.)

Pembroke. "In the neighbourhood of St. David's considerable tracts of open field lands are still remaining which is chiefly owing to the possessions of the church being intermixed with private property." (Charles Hassell, "Agriculture of Pembroke," p. 20.)

Radnor. "Here are no Common Fields." (John Clark, "Agriculture of Radnor," p. 21.)

Flint. "There are no common fields, or fields in run-rig, in this county, except between Flint and St. Asaph, and it is in intention to divide and inclose them." (George Kay, "Agriculture of Flint," p. 4.)

Cærnarvon. "Run-rig. There are no lands of this description that I could hear of, but there is a good deal of mixed property that might be exchanged." (George Kay, "Agriculture of Cærnarvon.")

There was in existence a mere remnant of open intermixed, arable land, which one reporter evidently thinks ought to be described as run-rig, and not as common field. Though in many respects agricultural methods were of the most primitive type, yet enclosure was practically complete; in two out of the four counties in which open fields are stated to be surviving, the explanation of such an exceptional circumstance is given in the intermixture of church and lay property. This well corroborates the *a priori* argument that the Celtic type of village community easily yields to enclosure; and that a predominance of pasture over arable also facilitates early enclosure of what arable there is.

Mr. A. N. Palmer shows that the varying operation of the custom of gavelkind (equal inheritance by all sons) is also closely connected with the recent phenomena of the distribution of holdings. Everywhere the land which was ancient open arable fields is now, and has been for an unknown period dating at least as far back as 1620, divided by hedges into small enclosures, as in Devonshire; but in some districts these contain, or are known to have contained in comparatively recent times, intermixed quilllets of other ownership. In these districts Mr. Palmer supposes the ancient "gafæl" or "gwely" (which may be roughly defined as a patriarchal family holding), was at the time when co-aration ceased, very much sub-divided. In other districts where the "gafæl" or "gwely" was little sub-divided, so that each occupier could support his own plough team, when co-aration ceased, holdings became entirely separated from one another. ("History of Ancient Tenures of Land in North Wales," pp. 35—37.)

We have now to fix with what accuracy we may the time of the enclosure of the western counties, and then to search for evidence in those counties of variations from the typical English village community.

DEVON, CORNWALL AND WEST SOMERSET.

These counties were very early enclosed. There is so much earlier evidence that it seems superfluous to quote Celia Fiennes, but there are some suggestive touches in her description.

"I entered into Devonshire 5 miles off from Wellington, just on a high ridge of hills which discovers a vast prospect on Each side full of Inclosures and lesser hills which is the description of most part of the West. You could see large tracts of grounds full of Enclosures, good grass and corn beset with quicksetts and hedgerows" (p. 206). In very similar words she describes the views on the roads from Exeter to Chudleigh, and from Chudleigh to Ashburton.

"Devonshire is Much like Somersetshire, fruitfull countrys for corn, graseing, much for inclosures that makes the wayes very

narrow, so as in some places a coach and waggons cannot pass. They are forced to carry their corn and carriagis on horses backes with frames of woods like pannyers on either side of the horse, so load it high and tye it with cords. This they do altogether the further westward they goe, for the wayes grow narrower and narrower up to the land's end " (p. 9). As Celia Fiennes rode into the far west of Cornwall, hers is the evidence of an eye-witness. She points to the explanation of the extreme narrowness for which Devonshire lanes are still noted—enclosure took place before the introduction of carts.

Devonshire is spoken of in the previously quoted passage in the "Discourse of the Commonweal," about 1550, as, with Essex and Kent, one of the most enclosed counties. Leland, about the year 1537 passed through North Devon into Cornwall, as far as Wadebridge and Bodmin, and back through South Devon. His statement that Somerset was much enclosed with hedgerows of elms, has already been quoted. In Devon and Cornwall he found no "champaine," but frequently "meately good corne and grasse;" on the other hand, he frequently found enclosure.

After recording his arrival at Dunster, he says: "From Combane to the Sterte most part of the Shore is Hilly Ground, and nere the Shore is no Store of wood; that that is ys al in Hegge rowes of Enclosures" (Vol. II., fol. 63). There was enclosed ground between Bideford and Torrington (fol. 68); from Torrington to Launceston was either "hilly and much enclosid," or "hilly and much morisch" (fol. 69), and also from Launceston to Boscastle (fol. 72).

Entering South Devon, he remarks simply on the fertility of the soil, but remarks: "The hole Ground bytwixt Torrebay and Exmouth booth sumwhat to the shore and especially inward is wel inclosed" (Vol. III., fol. 31).

In the year of Leland's visit, probably either 1537 or 1538, the cultivated lands of Devon and Cornwall and Somerset were largely, but not entirely, enclosed. In East Somerset alone did Leland find any land which he could describe as "champaine"; we may infer therefore that though no doubt there was a good

deal of open field arable, probably still cultivated by co-aration, it existed in the form of comparatively small areas round villages and hamlets; nowhere, in Leland's route, extending over a considerable tract of country.

Carew, in his book on Cornwall, dated 1600, gives an account of the enclosure of that county. Of the manorial tenants, he says: "They fal everywhere from Commons to Inclosure and partake not of some Eastern Tenants envious dispositions, who will sooner prejudice their owne present thrift, by continuing this *mingle mangle*, than advance the Lordes expectant benefit, after their terme expired" (p. 30).

This pregnant passage tells us—

(1) That the Enclosure of tilled land in Cornwall had been proceeding rapidly up to 1600 and was then nearly complete;

(2) That previous to enclosure the system of cultivation, whether it most resembled the English common field system or Scotch run-rig, had for one of its features the intermixture of holdings; and for another some elements of collective ownership or management entitling it to the name "Commons";

(3) That Carew's conception of a manorial tenant is not that of a freeholder, nor of a copyholder, but that of a leaseholder, whose term expires, the lord of the manor reaping the fruit, on the expiration of the lease, of any improvements the tenant may have made. He further on explains that the system of leases for three lives was practically universal in Cornwall, not in the modern form in which any three lives may be named in the lease, but depending for its continuance on the lives of the lessee, his widow and his son. It is obvious that this condition of land tenure would be more favourable to early enclosure than copyhold.

Another passage in Carew bears witness to the practical completion of enclosure. Writing of the legal conditions under which the miners pursued their enterprise, he says: "Their workes, both streame and Load, lie either in severall or in waistrell," that is, either in enclosed land under separate exclusive ownership and occupation, or in waste. One cannot draw the inference that there was absolutely no open field land;

but merely that its extent was in comparison so small as to appear negligible in this connection to Carew.

Though it is not improbable that the enclosure of Cornwall took place at an earlier stage of agricultural evolution than that of Devonshire, it is somewhat improbable that it took place at an earlier date. It is a reasonable inference from the evidence that by the end of the sixteenth century the enclosure of Devon and Cornwall was practically complete. When it began is a different question.

The charter of John by which all Devonshire except Dartmoor and Exmoor was deforested, expressly forbids the making of hedges on those two forests. This is itself some evidence that enclosure of some sort, probably enclosure of waste, for the purpose of cultivation, was going on actively in the beginning of the thirteenth century.

Attention must here be drawn to an ancient custom in Devon and Cornwall surviving to the end of the eighteenth century. William Marshall gives an account of it, and shows its probable importance in determining the character of enclosure and of all the attendant circumstances in Devon and Cornwall.

“*West Devonshire.* This district has no traces of common fields. The cultivated lands are all enclosed, mostly in well sized enclosures; generally large in proportion to the sizes of farms. They have every appearance of having been formed from a state of common pasture; in which state, some considerable part of the District still remains; and what is observable, the better parts of these open commons have evidently been heretofore in a state of aration; lying in obvious ridges and furrows; with generally the remains of hedgebanks, corresponding with the ridges, and with faint traces of buildings.

“From these circumstances it is understood by some men of observation, that these lands have formerly been in a state of permanent inclosure, and have been thrown up again, to a state of commonage, through a decrease in the population of the country.

“But from observations made in different parts of Devonshire, these appearances, which are common, perhaps, to every part

of the county, would rather seem to have arisen out of a custom, peculiar perhaps to this part of the island, and which still remains in use, of lords of manors having the privileges of letting portions of the common lands, lying within their respective precincts, to tenants, for the purpose of taking one or more crops of corn, and then suffering the land to revert to a state of grass and commonage.

“In the infancy of society, and while the country remained in the forest state, this was a most rational and eligible way of proceeding. The rough sides of the dells and dingles with which it abounds were most fit for the production of wood; the flatter, better parts of the surface of the country were required for corn and pasturage; and how could a more ready way of procuring both have been fallen upon than that of giving due portions of it to the industrious part of the inhabitants, to clear away the wood and adjust the surface, and after having reaped a few crops of corn to pay the expense of cultivation, to throw it up to grass, before it had become too much exhausted to prevent its becoming, in a few years, profitable sward? In this manner the county would be supplied progressively as population increased, with corn and pasturage, and the forests be converted, by degrees, into common pasture.

“The wild or unreclaimed lands being at length gone over in this way, some other source of arable crops would be requisite. Indeed, before this could take place, the pasture grounds would be disproportionate to the corn lands; and out of these circumstances, it is highly probable, arose the present Inclosures.” (“Rural Economy of the West of England,” 1795, p. 31.)

The same custom was observed in Cornwall by G. B. Morgan, the Board of Agriculture Reporter. (“Agriculture of Cornwall,” p. 46.)

I believe this custom is the explanation of the huge size of the hedges which is frequently observable in Devonshire. A mound about eight feet high, and six or seven feet through, surmounted by a quickset hedge, is not uncommon. When a plot of land which had once been enclosed from the waste for

cultivation, and then thrown into common pasture, with its hedges cast down, had recovered its fertility, it would naturally again be selected for enclosure and cultivation; the cast down rough stone wall, now overgrown with vegetation, would be made the foundation for a new hedge; and the same process might be repeated several times before final enclosure.

BRAUNTON GREAT FIELD.

I have said above that it is reasonable to infer from the evidence that enclosure was practically complete in Devon and Cornwall by the end of the sixteenth century. It is not, however, absolutely complete to the present day; for Braunton Great Field remains uninclosed. Braunton is a little town of about two thousand inhabitants, situated between Ilfracombe and Barnstaple, near the sea coast. Braunton Field is said to have "as many acres as there are days in the year," each nominal acre being a strip of land of about an acre in area. Properties and holdings are very much intermixed, many of the holdings are very small and cultivated by their owners. Each "acre" is separated from the rest on each side by a balk of untilled land, growing grass, yarrow, hawkweed, etc., just a foot wide. They are locally known as "launchers," which one associates with the Dorset name "lawns" for the strips of ploughed land, and the name "landshare," in the Stratton Court rolls for the unploughed balks.

There is also always a path, or a broader balk, called an "edge," separating the different sets of acres, which elsewhere would be called "Shots" or "Furlongs," from one another.

No common rights exist at present, or have existed in living memory over either the unploughed balks, or the tillage lands themselves. But old villagers remember that long ago one half of the field was kept for wheat, and the other half for potatoes, clover, etc., in other words, that there use to be a common rule for the cultivation of the field and this common rule was similar to that prevailing in the Gloucestershire every year lands. At



Part of Branton Great Field.

Scale 3000

50 0 50 100 Yards.

The dotted lines represent bulks separating adjacent strips in the open field; the continuous lines represent hedges. It is easy to see how the enclosures on the edge of the field were made out of two or three strips thrown together.

present each occupant cultivates his strips just as he pleases. It is of course possible that this obsolete common rule is itself a survival from an older one, and that originally this field was cultivated on the two-field system so prevalent in Lincolnshire; half under wheat, half fallow, the fallow being commonable all the year, and the wheat after harvest. But on the other hand, the custom of getting a crop every year may have been the original one, and Branton Great Field may be ancient "Every Year land" or "Infield."

Branton Field is noteworthy in that it shows that however the primitive village community of West Wales may have differed from that of Wessex, it must have had certain characteristics in common with it, by which open arable fields of intermixed occupation were created in the neighbourhood of villages. Branton cannot have been from the beginning an isolated example. The process of enclosure by the method Marshall describes went on around and outside these ancient tilled open fields.

Another interesting fact is revealed by the study of the twenty-five inch Ordnance map for Branton. Branton Field has been much reduced in area; one can easily see that the adjoining lands were once part of the open field, for the hedges in the lands are so placed as to form a continuation of the spider-web lines of the "launchers" within the field. The average size of the enclosed fields outside the Great Field is indeed a little greater than of the separate lands within it, but there is an imperceptible gradation, beginning with the smallest "lands" in the Great Field which are nearest the village, on through those more remote, the nearer enclosed fields, and then the more remote of them. Enclosure has been effected by simply enclosing the strips of arable land in the open field as they are. The fact that no common rights existed over the Field, supposing this always to have been the case, would have made such enclosure almost a matter of indifference to the other occupiers; and the motive, no doubt, would be the desire to lay the strip down in pasture. The whole field is known to the villagers as "the tillage land."

THE WELSH BORDER.

The enclosure history of the counties along the Welsh border is somewhat similar to that of Devonshire. It took place early, partly in consequence of the predominance of pasture over arable, and partly under the influence of a custom of temporarily enclosing the waste and common pasture, similar to that in Devon and Cornwall.

The percentages of area of these counties enclosed by Acts for enclosure of common field arable are respectively :

					Per cent.
Cheshire	...	...	...	...	0·5
Hereford	...	...	...	...	3·6
Monmouth	...	...	...	...	0·4
Shropshire	...	...	...	...	0·8
Staffordshire	...	...	...	...	2·8

The Board of Agriculture reporter's statements on the common fields surviving in 1793 are that in Cheshire there was not so much as 1,000 acres (Wedge, "Agriculture of Cheshire," p. 9); in Staffordshire little more than 1,000 acres (Pitt, "Agriculture of Staffordshire," p. 85); that Shropshire "does not contain much common field land" (J. Bishton, "Agriculture of Shropshire," p. 8); but that in Hereford some of the best lands of the county are common fields (Clark, "Agriculture of Hereford," p. 69). Of Hereford, William Marshall gives a fuller account. "Herefordshire is an inclosed county. Some few remnants of common fields are seen in what is called the upper part of the county; but in general it appears to have been inclosed from the forest state; crooked fences and winding narrow lanes" (p. 224).

Celia Fiennes found from Nantwich to Chester "much Enclosures" (p. 147), but from Salford to Northwich, "I went a very pleasant roade, much in the downs, mostly campion ground, some few Enclosures"; Herefordshire, "a country of Gardens and Orchards, with apple and pear trees thick in the hedge-rows" (p. 33); Staffordshire, "well wooded and full of Enclosures,

Good Rich Ground, extremely differing from Derbyshire" (p. 89). This was her first impression, confirmed later. "Harteshill is so high that from the top of it you see near 20 miles round, and shows all the county which in this part of Staffordshire is full of woods and inclosures and good lands, except the Knackwood" (p. 137). From "Nedwoodforest" . . . "you have a fine prospect of the country, enclosed good lands" (p. 139). Also beyond Stafford towards Cheshire was mostly enclosures (p. 144), and from Stafford to Wolverhampton the journey was through lanes (p. 194).

Walter Blyth includes Staffordshire and Shropshire as part of "the Woodlands, who before Enclosure, were wont to be relieved by the Fieldon, with corn of all sorts. And now grown as gallant Corne countries as be in England" ("The English Improver," 1649, p. 40).

Evidence of early enclosure is supplied by Leland. About White Castle, which I take to be Bishop's Castle, in south-west Shropshire, "the Countrys is Champion" (Vol. IV. fol. 176 b), but from Hereford to Leominster was enclosed ground (176 b and 177 a), thence towards Ludlow "by goodly corne Ground, part by enclosed" (178 b), Bridgenorth to Kidderminster "most by enclosed Ground" (182 b), to Bewdly was by "a fayre downe," but all the way thence to Milton (4 miles), Hertlebury (2 miles), Salopbrook (5 miles), Worcester (3 miles), Wick (6 miles) and Bromsgrove (4 miles), each stage is said to be by enclosed ground (fols. 183 b—186 a).

As for Monmouthshire, "The soyle of al Venteland" (Gwent, the country between the Wye and Usk) "is of dark reddish Yerth ful of slaty stones, and other greater of the same colour. The country is also sumwhat mountaynous and well replenished with Woodes, also fertile of Corne; but men there study more to Pastures, the which be wel inclosed" (Vol. V., fol. 5), and "Erchenfeld is full of Enclosures very (fruteful) of Corne and Wood" (fol. 9). Round Shrewsbury there is "ground plentiful of Corne, wood and pasture" (Vol. V., fol. 80), at Whitechurch "meately fruteful sandy ground" (fol. 81), and sandy ground on to Northwich (*ibid.*).

Nowhere else in these counties is either "enclosure" or "champaine" specified.

The evidence as to the existence of a custom of temporary enclosure of the waste, is supplied by Robert Plot's book on "Staffordshire," published in 1686: "For the heathy land of this County, it is seldom enclosed; but when they intend it for tillage, which is never for above five years neither, and then it is throwne open to the Commons again" (p. 343). "Their gouty, moorisch, peaty, cold black land, they husbände also much after the same manner as they doe the heathy lands in the Moore Lands" (p. 345).

Another passage brings into juxtaposition the more recent enclosures from forest or moor for the sake of tillage, and the ancient arable common fields. "Others again have placed the origin of mildewing in making small inclosures, corn not being so lyable to this evil in the common open fields" (p. 351).

It is reasonable to suppose that the custom found in Staffordshire and in Devon and Cornwall also prevailed in other counties, particularly in those along the Welsh border. It is some confirmation that Eden about a hundred years later found a similar custom still surviving in Sutton Coldfield, in Warwickshire, but near the Staffordshire boundary.

"The poor here, besides the right of commonage, have this peculiar privilege, that every house-keeper may take in one acre of common, and plough it four years: and the fifth year he must sow it with clover and lay it to the common again; after which he may take another acre, and work it in the like manner. By this method, about 400 acres of common are kept constantly in tillage" ("State of the Poor," Vol. III., p. 749, written probably in 1795).

The enclosure history of these five counties may be summed up in the statement that it probably proceeded very similarly to enclosure in Devonshire, but at a somewhat later date; and that enclosure was later towards the north. Monmouth, we see, was "full of enclosures" before 1540; Shropshire "partly enclosed" with some "champion"; but though Leland passed through Cheshire, he does not mention enclosures, and Celia

Fiennes found the North of Cheshire mostly open as late as about 1697. In Hereford and Staffordshire there was a large proportion of ancient arable land, and complete enclosure was consequently longer delayed, leaving an appreciable area to be enclosed by Acts of Parliament.

STRATHCLYDE.

Lancashire had no common field enclosed by Act of Parliament. It is possible that its partial autonomy as a Palatine County may account for this; but it must be noticed that the Acts of enclosure for Lancashire for enclosing commonable waste, are numerous right through the period of Enclosure Acts. Nor, though Lancashire was an early enclosed county, can we explain the absence of Enclosure Acts by the assumption that the enclosure of tilled land was completed by the beginning of the eighteenth century, for some common field persisted to the end of that century.

John Holt, the Board of Agriculture reporter, tells us: "There are but few open, or common fields, at this time remaining; the inconvenience attending which, while they were in that state, have caused great exertions to accomplish a division, in order that every individual might cultivate his own lands, according to his own method; and that the lots of a few acres, in many places divided into small portions, and again separated at different distances, might be brought together into one point" ("Agriculture of Lancashire," p. 49). It would appear from this that the open fields of Lancashire, like Braunton Great Field, though unenclosed, and intermixed, and subject to some common rule for cultivation, were not subject to common rights. Any owner, therefore, who by exchanges or by buying and selling, could get his lands together in a convenient plot, might enclose without trespassing on his neighbours' rights.

From Holt's statement we find that enclosure was nearly, but not quite, complete by 1793. It was certainly far advanced a hundred years earlier. Celia Fiennes rode from Prescott to Wigan, "seven long miles mostly through lanes" (p. 153);

from Gascoyne to Lancaster, "mostly all along lanes being an enclosed country" (p. 157). From Blackstone Edge the view was of "a fruitfull valley full of inclosures" (p. 186). From Rochdale to Manchester, "the grounds were all enclosed with quicksetts" (p. 187).

Similarly Leland: "Manchester to Morle I passid by enclosid Grounde partely pasturable, partely fruteful of corn" (Vol. V., fol. 83). "The Ground bytwixt Morle and Preston enclosid for Pasture and Cornes. . . . Likewyse is the soile bytwixt Preston and Garstan; but alway the moste parte of Enclosures be for Pasturages" (fol. 84).

Cumberland and Westmoreland were later enclosed than Lancashire; and some few remnants of open arable field were dealt with by Acts. At Bolton, in Westmoreland, "certain open or common fields called Broad Ing Bartle and Star Ing" of 22 acres, at Soulby 90 acres of open field, and at Barton 180 acres, were enclosed by Acts mainly passed for the sake of enclosing waste; and at Kirkby, in Kendal, "a common open field" of 108 acres was enclosed. There were five Acts in Cumberland enclosing open fields; but only two say precisely how much. At Torpenton, 20 acres of field and 700 acres of waste was enclosed; at Greystoke, 240 acres of field and 3260 acres of waste.

But the enclosure of open-field arable was proceeding very steadily through the eighteenth century; and a clear account of the process is furnished us by two keen observers.

Eden gives an account of the condition of the arable land in seven Cumberland parishes, written either in December, 1794, or January, 1795.

"*Gilcrux*. About 400 acres of common field have been enclosed within the last fifty years" ("State of the Poor," Vol. II., p. 76).

"*Hesket*. No more than 200 acres have been enclosed within the last fifty years. A large part appears to have had its hedges planted a little before that period" (*Ibid.*, p. 81).

"*Ainstable*. Area 5,120 acres of which 3,480 are common.¹

¹ *I.e.*, common pasture or waste.

About 400 acres have been enclosed in the common fields within the last fifty years. . . . The average rent of land is about 18s. per acre ; but it is observable that here and in most parts of Cumberland, an extensive common right¹ is attached to most arable land " (p. 46).

" *Croglin*. The average rent of open fields is 9s. 6d. the acre, of inclosures, 15s. or 16s. About 100 acres of common-field land have been enclosed within the last fifty years ; but a great part of the arable land still remains in narrow, crooked *dales*, or *ranes*, as they are called " (p. 67).

" *Castle Carrock*. The greatest part of this parish remains in *dales*, or *doles* as they are called ; which are strips of cultivated land belonging to different proprietors, separated from each other by ridges of grass land ; about 100 acres may have been enclosed in the last fifty years " (p. 65).

" *Cumrew*. The land is cultivated in the old Cumberland manner ; the grass ridges in the fields are from twenty to thirty feet wide ; and some of them are 1000 feet in length. Grazing cattle often injure the crops " (p. 68).

" *Warwick*. Almost the whole of the cultivated land (1126 acres) has been enclosed within the last fifty years. It formerly, although divided, lay in long strips, or narrow *dales*, separated from each other by *ranes*, or narrow ridges of land, which are left unploughed. In this manner a great deal, and perhaps the whole, of the cultivated lands in Cumberland, was anciently disposed " (p. 92).

The other observer is the poet Wordsworth. In his book on the scenery of the lake district, he quotes from West's "Antiquities of Furness" to show that in the troubled times between the union of the Crowns of England and Scotland, holdings were let to groups of four tenants, each group dividing its tenement into four equal parts. "These divisions were not properly distinguished ; the land remained mixed ; each tenant had a share through all the arable and meadow land, and common of pasture over all the wastes. . . . The land being

¹ *I.e.*, over the neighbouring common pasture.

mixed and the several tenants united in equipping the plough, the absence of the fourth man" (who was called out for military service) "was no prejudice to the cultivation of his land, which was committed to the care of three." In High Furness, "The Abbots of Furness enfranchised these pastoral vassals, and permitted them to enclose quilllets to their houses, for which they paid encroachment rent."

Wordsworth then proceeds with the tale of enclosure: "The enclosures, formed by the tenantry, are for a long time confined to the homesteads, and the arable and meadow land of the fields is possessed in common fields; the several portions being marked out by stones, bushes, or trees; while portions, where the custom has survived, to this day are called *dales*, from the word *deylen*, to distribute; but while the valley was thus lying open, enclosures seem to have taken place upon the sides of the mountains; because the land there was not intermixed, and was of little comparative value; and therefore small opposition would be made to its being appropriated by those to whose habitations it was contiguous. Hence the singular appearance which the sides of many of these mountains exhibit, intersected, as they are, almost to the summit with stone walls. . . . There" (in the meadows and lower grounds), "where the increasing value of land, and the inconvenience suffered from intermixed plots of ground in common field, had induced each inhabitant to enclose his own, they were compelled to make fences of alders, willows, and other trees . . . but these last partitions do not seem to have been general till long past the pacification of the Borders, by the union of the two crowns" (Fourth Edition, p. 23).

The date of the enclosure of the intermixed arable and meadow land is thus fixed within certain broad limits. It did not begin till "long past the pacification of the Borders, by the union of the two crowns." It took some time to effect the pacification of the Borders, even after the accession of James I. made it possible; "long past" that event is a vague date, but may very well bring us at least as late as the date when the enclosure of the common fields of Durham is supposed to have begun, "soon after the Restoration." It is certain, further,

from Eden's information, that enclosure was going on steadily right through the second half of the eighteenth century, but by no means complete in 1795. The high prices of the war period would have greatly stimulated the movement, for it is obvious that if rents were thereby doubled both for open and enclosed land, the gross profit of enclosing would also be doubled; the net gain probably more than doubled. When Wordsworth wrote, the open fields were apparently still fairly numerous, but they had become a mere survival.

The date of the enclosure of this district is, however, the least interesting of the inferences to be drawn.

We find that up to the union of the Crowns, cultivation was carried on by a system very closely resembling the "run-rig" of the Hebrides. Groups of four tenants combined together, and yoked their horses to a common plough, and equally divided the holding between them, each tenant having his equal share in all parts of the holding. We next find that on the decay of this co-aration, for a long period, varying in duration in different parishes, holdings remained intermixed, but it seems clear that as in the one surviving Devonshire open field, and probably as in Lancashire, common rights were not exercised over the arable fields; though it might happen that besides the "ranes," the grassy balks between the strips of arable land, there might be considerable stretches of grass amidst the arable field which was used for a common pasture. Lastly, we find that open, intermixed arable land and meadows, having this history, passes into a state of enclosure where increase of population, agricultural progress, and the increasing value of land make enclosure sufficiently profitable, by a gradual, piecemeal process, without the need for Act of Parliament, or reference to a Commission, or any combined resolution on the part of the lord and tenants of a manor.

It is because the process was late in Cumberland and Westmoreland and because it happened to interest three authors, West, Wordsworth, and Eden, who were not agriculturists, that the record of it for these two counties is available. All the indications suggest that Northumberland and Durham underwent

a similar evolution ; and all the preceding information with regard to the enclosure of Wales and much of the land immediately on the Welsh border, and of West Somerset, Devon and Cornwall, harmonises with the hypothesis that in those districts also the process was fundamentally the same, though with local differences, due to a very much earlier pacification.

CHAPTER XVIII.

THE RESULTS OF ENCLOSURE.

THE scenery of England and Wales has been transformed by the enclosure of its lands, but the extent and results of the transformation vary. Here you have the landscape cut into little fields with great hedges, looking from an elevated point of view like a patchwork quilt; there the skimpy quickest hedges only slightly emphasise the natural sweeping lines of the hills: here you have narrow winding lanes; there broad, straight roads with margins of grass on either side: here you have compact villages in which almost all the habitations in the parish are clustered together; there farmhouses and cottages so scattered that were it not for the church, which seems to attract to its neighbourhood the inn and the smithy, there would be no recognisable village at all.

This diversity in the effect of enclosure on the face of the country is a symbol of the diversity of its effect upon the material, social, and moral conditions of the local peasantry, who, like the land itself, may be said to have undergone Enclosure.

Where, as in Devon and Cornwall, in Cumberland and Westmoreland, the division of intermixed arable and meadow land took place early and gradually, and in subordination to the reclamation of waste, that reclamation itself being carried on steadily and gradually, the result was the creation of numberless small holdings and properties. A career was offered to the enterprising and laborious, and enterprise and industry grew accordingly,—“Devonshire myghty and Strong,” says Leland; and the great part taken by Devonshire in the national struggles in the reign of Elizabeth must be partly attributed to the reaction upon the character of the people of the conquest over the difficulties of bringing the rocky soil, woodland or moor, into

cultivation: a conquest which made Devonshire husbandry famous for two generations, and "Devonshiring" a well-known term for a particular method of preparing waste land for cultivation.

Perhaps the greatest evil of Acts for the enclosure of waste in the past, was that they prevented such gradual reclamation and enclosure by peasant cultivators. At the present day the vital objection applies to enclosure of waste by any method that the area of such free open spaces is already sufficiently curtailed, that every remaining acre is becoming continually more precious, so that while public-spirited people fight for their preservation in remote places, in the neighbourhood of towns, citizens tax themselves to add to their area.

The enclosure of arable common fields, and of all the commonable lands of whole parishes within what I have called the Parliamentary Enclosure Belt, is of immeasurably greater historical importance. The ethics of such enclosure has been the subject of fierce debate for centuries; now the process is practically complete, and it is possible to appraise its results.

We have observed that with regard to the immediate results, capable of being contemporaneously verified, there is no real controversy between the disputants; it is on the inferences to be drawn as to the more ultimate results on the nation as a whole, and in the judgment pronounced upon the desirability of such results, that the dispute turned. The more candid disputants on either side admit the vital points in their opponents' case: thus, for example, no opponent of enclosure denies that it tended to raise rents; and, on the other hand, it was the greatest advocate of enclosure who declared that "By nineteen out of twenty Enclosure Acts the poor are injured."

The increase of rent was, of course, the motive of enclosure; and though there were exceptional cases in which the results were very disappointing to the promoters, as a rule the increase of rent was very great. Arthur Young gives the full financial details of twenty-three Acts for the enclosure of open field parishes in Lincolnshire.¹ The total rents before enclosure amounted to

¹ "Agriculture of Lincoln," p. 83.

£15,504; on an average they were nearly doubled, the increase of rent obtained being £14,256, and the expenditure necessary to obtain this result was £48,217. Assuming that the money was borrowed at 6 per cent., there remained to the landowners a net profit of £11,363. These results were no doubt something above the average, but they were not exceptional. In Long Sutton the rent was raised from an average of 5s. per acre to between 30s. and 50s. per acre.¹

The increase of rent was not a concern purely of the land-owning class. As the advocates of enclosure continually pointed out, the rent was a pretty accurate test of the net produce of the agriculture of the parish; it was roughly proportional to the amount of food grown but not consumed on the spot, and sent away to markets to feed urban consumers at a distance. It was upon this net produce, they pointed out, that the taxable resources of the country depended. It was argued that an addition to the population of the country which was all engaged in gaining its own subsistence from the soil, added neither to the number of soldiers who could be enlisted for war without paralysing industry, nor to the power of the State to equip and support an army. On the other hand, a change by which a whole village of peasants who consumed nearly all the food they produced, was swept away and replaced by one or two highly rented farms, producing a less quantity of food, but sending much more to market, did supply the State with additional resources for the maintenance of its forces.

Private interests stimulated the appreciation of these public advantages. Money had to be borrowed to meet the heavy initial expenses of enclosure, and the banking system grew with the enclosure movement of the eighteenth century. And hence a secondary gain to the State. Increased opportunities for the remunerative investment of capital increased the supply of loanable capital, and made possible the enormous State loans by which the Napoleonic war was carried on. Lawyers, land surveyors, Parliamentary agents and others,

¹ "Agriculture of Lincoln," p. 77.

reaped a copious harvest; and further, London in particular, and other towns in varying measure, grew in wealth by ministering to the increased "effective demands" of the enriched aristocracy. }

But the opponents of enclosure were concerned with the gross rather than the net produce of land, and, as we have seen, it can be proved from the testimony of the advocates of enclosure and of impartial witnesses, that over a great part of the Midlands enclosure meant the conversion of arable to pasture, and local depopulation. The Board of Agriculture gives what may be considered an official estimate of the diminution of gross produce which would follow. An acre of common field arable might be expected to produce 2010 lbs. of bread in a three years course (that is, 670 lbs. of bread per annum), and 30 lbs. of meat per annum. The same area enclosed and converted to pasture would produce 176 lbs. of mutton, or 120 lbs. of beef. If we split the difference between the production of beef and mutton, we have on the average 148 lbs. of meat produced. There is on enclosure a gain of 113 lbs. of meat against a loss of 570 lbs. of bread; supposing the food values of equal quantities of bread and meat to be equal, there is a loss of 557 lbs. out of a total produce of 705 lbs.

And yet, through a chain of causation which can now be clearly perceived, but which at the time was not evident, though locally there might be a loss of gross produce, there was a gain throughout the kingdom. The key to the position was the operation of the Poor Laws.

Enclosure of arable fields and open field parishes in the Parliamentary Enclosure Belt in many ways greatly affected the operation of the Poor Laws.

By increasing rents it made a given poor-rate yield more. Further, the increase of rent reconciled the enclosing landowners to an increase in the poor-rate; more especially when it fell, not on them, but on their neighbours. For, as we have seen, the effect of enclosure in some parishes in a given neighbourhood was often to drive the poor into the parishes which remained unenclosed; these bore the burden, while the others reaped the profits.

As we have seen, enclosure, even when arable was not converted to pasturage, tended to ruin small owners and to eliminate small farmers, so that these had to join the ranks of agricultural labourers. The number of potential paupers was thus increased.

Destitution and recklessness among the labouring classes also increased. The common rights and small holdings of a few acres in the common fields were, at best, as we have seen, exchanged for a sum of money for which no investment offered itself, which therefore soon disappeared. With these small holdings disappeared also the hope of gradually taking more and more additional strips of land in the fields and the fear of losing the little already gained.

Early marriage was particularly encouraged by the change from the open field condition to enclosure. Before enclosure, the conditions of labour made the common field farmers who employed labourers, desire young unmarried men and women who would live in the farmhouse; such farm servants postponed marriage till they had accumulated some savings and could begin their married life with some resources—a cow, for example—over and above their labour. After enclosure, the enriched farming class preferred to pay board wages, and the young labourer with nothing to gain by waiting, with the assurance of Poor Law assistance if needed, naturally preferred to marry early.

Lastly, the disappearance of the yeoman class and of the connecting links between the largest farmers and the day labourers naturally tended to make the careful local administration of the Poor Law more difficult; it even to a great extent destroyed the motive for economical administration. The open field parish retained some of the social vitality of a self-governing community; men who had to concert together for the regulation of the fields, for the purchase of a parish bull, were more likely than the farmers of an enclosed parish to settle in concert questions of Poor Law relief in accordance with the interest of the parish as a whole.

This last point of connection between the enclosure and the Poor Law history of the country during the eighteenth century and

the first part of the nineteenth is, however, interesting in itself, apart from the present argument. The point here laid stress upon is that whatever hardships for labourers and others resulted from the enclosure of arable fields, they did not starve, they did not eat less bread; they might be rendered miserable, but they married earlier and reared large families, somewhere or other. Poor Law relief ensured their offering an "effective demand" for bread. This effective demand compelled the increase of arable cultivation somewhere within the country; for foreign supplies were practically unavailable. The enclosure of waste for tillage and the enclosure of arable for pasture were economically inter-dependent.

The gross agricultural produce of the country as a whole was therefore increased by common field enclosure.

The effect upon urban industries was also great. The greater the local depopulation in rural districts produced by enclosure, the greater the supply of needy labourers of industrious habits and robust physique drafted to the growing industrial towns. Local depopulation was the usual result of Enclosure, as we have seen, in the Midlands and in Wiltshire, and parts of neighbouring counties. Where, as in Norfolk and parts of Lincoln and Yorkshire, local depopulation did not ensue, there was a vast increase in the agricultural produce sent to market, and in consequence, in the manufactured commodities demanded. Enclosure tended to assist urban industry therefore by an increased labour supply, an increased market, and perhaps also, an increased supply of capital.

Summing up, therefore, the economic results of the whole mass of little village revolutions under examination, we find increased population, increased production of all sorts of commodities, increased national resources for purposes of taxation and foreign war. The moral effects we find to have been increased misery and recklessness, showing itself in increased pauperism and drunkenness. An increase of the quantity of human life is attained at the expense of a degradation in its quality.

APPENDIX A.

STATISTICAL SUMMARY OF ACTS OF ENCLOSURE ENCLOSING COMMON PASTURE AND WASTE ONLY.

	Acts specifying Acreage Enclosed.		Acts not speci- fying Acreage Enclosed.		Total.		Acres Enclosed per annum.
	Acts.	Acreage as stated.	Acts.	Acreage estimated.	Acts.	Acres.	
1727—1760	49	65,203	7	9,315	56	74,518	2,192
1761—1792	292	411,952	47	66,307	339	478,259	14,946
1793—1801	153	230,249	29	43,642	182	273,891	30,432
1802—1815	469	615,970	95	123,773	564	739,743	52,839
1816—1845	202	164,994	42	34,306	244	199,300	6,643
Totals. .	1,165	1,488,368	220	277,343	1,385	1,765,711	

From 1727 to 1760 the number of Acts of this class passed per annum was steadily increasing, the Seven Years' War (1756-1763) apparently acting as a stimulus. During this period the average acreage enclosed per Act was 1330·7 acres. The increase in the number of Acts continued up till 1792, and again at a greatly enhanced rate after the beginning of the great French war. From 1761-1792 the average acreage enclosed per Act was 1410·8 acres; from 1792-1801, 1504·9 acres. In 1801 a Clauses Act, termed "A General Enclosure Act" was passed to facilitate Parliamentary proceedings. This had the double effect of increasing the average number of Acts passed per annum from 20 to 43, but of reducing the average acreage per Act to 1313·4 acres. From 1816-1845 the average acreage per Act was 816·8 acres.

APPENDIX B.

PRIVATE ACTS ENCLOSING COMMON FIELDS.

<i>Abbreviations</i>	A. F. Acres of common field arable.	P. Parish.
	A. P. Acres of common pasture.	M.I. Mesne inclosures.
	A. M. Acres of common meadow.	yl. Yardlands.
	F.'s. Common fields.	

* Indicates that the area enclosed is not stated in acres in the Act, but in yardlands, oxgangs, or other such units, or otherwise has been estimated from data supplied by the Act.

NOTE.—The spelling adopted is that used in the Act. In many cases it varies from that now in use.

BEDFORD.

Date.	Enclosure.	Area enclosed.	Date.	Enclosure.	Area enclosed.
1742	Sutton ...	2,200		Brought forward ...	33,048
1760	Apsley Guise ...		1796	Marston Moretaine ...	
1765	Felmersham ...			Pertenhall ...	850
	" Podington ...	2,400		Ridgmont ...	950
1768	Tilsworth ...		1797	Bedford ...	400
1769	Pavenham ...			Campton with Shefford	
	" Sundon ...			Chalgrove ...	1,780
1770	Souldrop, 350 A. F., 150			Dunton ...	2,200
	A. P. ...	500		Elstow ...	1,060
1774	Potton ...			Harrold ...	3,300
1775	Lidlington ...			Southill ...	2,600
1776	Odell ...			Toddington and Carlton	2,800
1777	Tempsford ...	2,000	1798	Sandy ...	
1778	Little Berkford ...	1,500	1800	Over and Nether Dean...	1,570
	" Bolnhurst ...	953		Farndish ...	672
1780	Northill and Sandy			Tilbrooke ...	1,380
1783	Turvey ...			Little Staughton ...	1,000
1793	Milton Bryant ...	1,400	1801	Wrestlingworth ...	1,860
	" Riseley ...	2,000			
1794	Shelton ...	1,000			55,470
1795	Bedford ...	1,450			
	" Crawley ...	1,400	1802	Cardington ...	3,000
	" Eaton Socon ...	4,650		Everton cum Tetworth	420
	" Henlow ...	2,000		Kempston ...	2,600
	" Milbrooke ...	900		Shillington and Holwell	
1796	Blunham... ..	2,695	1803	Keysoe ...	1,700
	" Houghton Regis...	4,000		Milton Ernest ...	1,350
	" Maulden ...	2,000		Oakley ...	1,450
Carried forward ...		33,048	Carried forward ...		10,520

BEDFORD—continued.

Date.	Enclosure.	Area enclosed.
	Brought forward ...	10,520
1804	Arlsey	
"	Astwick	600
1805	Thurleigh	1,460
"	Carlton, Chillington and Steventon	
1806	Haughton Conquest ...	1,500
"	Eversholt	130
"	Flitwick	1,000
1807	Salford	500
1808	Clophill	
"	Harlington	700
1809	Flitton cum Silsoe and Pulloxhill	
"	Ravensden	1,000
"	Barton in the Clay ...	
"	Sharnbrook	
"	Wilshamstead	
1810	Roxton	3,000
1811	Wymington	700
"	Wilden	1,600
1812	Biddenham	
"	Stagsden	
1814	Potton	
1820	Great Barford	
"	Greenhurst, Upper and Lower, and Upper Stondon	
	Carried forward ...	22,710

Date.	Enclosure.	Area enclosed.
	Brought forward ...	22,710
1827	Langford	1,700
1832	Clifton	1,400
1834	Colmworth	1,600
1836	Wootton	
"	Stepingley, 300 A. F. ...	400
1837	Cranfield	
		27,810

Enclosed under the General Enclosure Act, 1845.

Date of Act.	Date of Award.	Parish.	Area.
*	1851	Stotfold	2,030
1847	1852	Goldington	1,040
1855	1858	Streatley and Sharpenhoe	1,662
	1860	Eton Bray	1,860
	1891	Totternhoe	1,717
			8,309

	Acres.
Before 1802 ...	55,470
1802-1845 ...	27,810
After 1845 ...	8,309

BERKSHIRE.

Date.	Enclosure.	Area enclosed.
1724	Sunninghill, c. Bayworth, liberty of Sonning, 5 F.'s, 3 Commons ...	*1,190
1743	Aston Tirrold, 12 F.'s ...	
"	Early, F. only	423
1746	Inkpen	
1758	Upton, 57 yl.	1,800
1761	Hinton, 60 yl. F. and 620 A. P.	*2,420
1764	Haversham	844
1770	Ashbury	
1771	East Garston	
"	Hampstead Norreys, 750 A. F., 700 A. P. ...	1,450
1772	Great Faringdon, 52 yl. F., 100 A. M....	1,660
"	Upper Letcombe and Childrey	
1776	Eastbury and Blagrove	
	Carried forward ...	9,787

Date.	Enclosure.	Area enclosed.
	Brought forward ...	9,787
1776	Ferry Hinksey	
1777	Farnborough	
"	Uffington, Balking, Wool- ston, Kingston, Lisle, Fawler	
1778	Bockhampton	
1779	Elcot	338
"	Speen	
1783	Stanford, 80 yl....	2,000
1785	Bray	320
1788	Little Faringdon (part of Langford)	
1793	Aston Upthorpe... ..	
1794	Compton Beauchamp ...	
"	Shilton	
1795	Walton and Boreshill ...	
1796	Longcott... ..	
1799	Remenham	
	Carried forward ...	12,445

BERKSHIRE—continued.

Date.	Enclosure.	Area enclosed.	Date.	Enclosure.	Area enclosed.
	Brought forward ...	12,445		Brought forward ...	18,092
1800	Sparsholt and Westcote		1811	Drayton ...	
1801	Little Coxwell ...		1812	West Compton ...	2,000
"	Denchworth ...	700	"	Ashall ...	1,500
"	Lyford ...	506	"	Great Shefford and West	
"	Letcomb Regis and		"	Shefford ...	520
"	Bassett ...		1814	Chieveley ...	400
"	Sutton Courtney and		"	Wytham ...	620
"	Sutton Wick ...		"	Bray ...	
"	East Hendred ...		"	Cumner and South Hinck-	
		13,651	"	sey ...	3,000
1802	Buckland ...	2,074	"	Streatley ...	
"	West Challow ...	403	"	Welford ...	1,400
"	Harwell ...		"	Wargrave and Wearfield	2,000
"	Kennington ...		"	Boxford ...	1,500
"	Up Lamborne ...		"	Marcham ...	
1803	Chipping Lamborne and		"	Sandhurst ...	3,400
"	Blagrave ...		1816	Sonning ...	2,500
"	East Hanney ...		1818	South Moreton ...	
"	Waltham St. Lawrence	700	1821	Easthamstead ...	2,250
"	Wantage and Grove ...	2,400	1825	West Ilsley ...	1,270
1804	Charney ...	950	"	Marcham ...	700
"	Ufton ...		1827	Ruscombe ...	
1806	Kingston Bagpuize ...	655	1828	Appleton ...	1,500
1807	Shottesbrook and White				42,652
"	Waltham ...				
"	Hurst, 700 A. F., 600 A. P.	1,300			
1808	Aston Upthorpe and				
"	Aston Tirrold ...				
"	Ardington ...				
"	Langford ...				
1809	Basildon ...	110			
"	Englefield, 327 A. F., 36				
"	A. P. ...	363			
"	Milton ...	663			
"	Long Wittenham ...				
1810	Chieveley ...	600			
"	Enborne, Hamstead				
"	Marshall, Inkpen and				
"	Kintbury ...	1,400			
1811	Chaddleworth ...				
"	Hungerford ...	780			
"	Thatcham Borough, Hen-				
"	wick and Greenham ...	825			
"	Brightwell ...				
"	Beenham and Padworth	574			
"	Fyfield ...	1,100			
"	Sulhamstead and Meales				
"	Tilehurst, 600 A. F., 600				
"	A. P. ...	1,200			
"	Woohampton ...	1,995			
	Carried forward ...	18,092			

Enclosed under the General Enclosure Act, 1845.

Date of Act.	Date of Award.	Parish.	Area.
*	1849	Newbury (E. & W. Fields) ...	212
*	"	North Moreton ...	1,025
*	1851	Cholsey ...	2,190
*	1853	East Lockinge ...	970
1851	1856	Shinfield ...	312
1851	1858	St. Giles, Reading	242
1860	1868	Charlton in Wantage	1,280
1880	1883	Steventon ...	1,373
			7,604

BERKSHIRE AND OXFORD.

1852	1855	Bampton and Shilton	2,730
*	1856	Purley, Sulham and Whitchurch ...	300

Half Area, assigned to Berks. 1,515

	Acres.
Before 1802 ...	13,651
1802-1845 ...	42,652
After 1845 ...	9,119

BUCKINGHAMSHIRE.

Date.	Enclosure.	Area enclosed.	Date.	Enclosure.	Area enclosed.
1738	Ashenden, 900 A. F. ...	*1,300		Brought forward ...	40,207
1742	Wotton Underwood, 1,168 A. F., 500 A. P. ...	1,668	1794	Akeley cum Stockholt, 13 yl. ...	*455
1744	Shipton (Winslow cum Shipton P.), F. only...	640	"	Newport Pagnell ...	900
1762	Swanburne, 77 yl. ...	*2,695	"	Wendover ...	2,009
"	Shenley Brookend ...	960	1795	Aston Abbotts ...	650
1764	Westbury ...	3,000	"	Padbury, 69 yl. ...	*2,415
1765	Westcote... ..	1,300	"	Steeple Claydon, 80½ yl. ...	*2,817
1766	Little Horwood... ..	960	1796	Little Brickhill ...	600
"	Winslow (Winslow cum Shipton P.) ...	1,400	"	Grandborough ...	1,100
1767	Olney	1,600	"	Sherington ...	1,600
"	Shalstone, 28 yl. F., 530 A. P. ...	1,370	"	Great Woolstone ...	300
1768	Loughton		1797	Adstock, 47 yl. ...	*1,645
"	Woughton-on-the-Green ...		"	Drayton Parslow ...	
1769	Cublington, 25 yl. ...	875	"	Thornborough, 62 yl. ...	*2,170
"	Grendon Underwood, 37 yl. ...	*1,295	"	Wing	3,402
1770	Simpson		"	Wingrave with Rowsham ...	2,400
"	Stoke Goldington	1,000	"	Stoke Mandeville ...	1,000
1771	Aylesbury, all F. ...		1798	Emberton	1,300
"	Great Brickhill... ..	1,260	"	Weston Turville, 1,000 A. F. and M. ...	1,000
"	Whitchurch		1799	Horton	
1772	North Crawley		"	Singleborough	
"	Soulbury and Hollington ...		"	Walton	1,200
1773	Tingewick and Radcliffe cum Chackmore ...		"	Wraisbury	
1774	Dunton	629	1800	Iver, 817 A. F., 473 A. M., 1,172 A. P. ...	2,462
"	Stoke Hammond		1801	Lavendon and Brayfield ...	
"	Twyford and Charndon ...	1,900	"	Weedon	1,700
"	Waddesdon, 49 yl. ...	*1,715	"	Maidsmorton and Buckingham	
1776	Hartwell and Stone, all F. ...	1,740			<u>71,323</u>
1777	Ludgershall, 1 F., 53 yl. ...	1,800	1802	Donnington	900
"	Wendover		"	Moulsoe	1,600
1778	Hardwicke	1,200	"	Woburn	800
"	Hitcham... ..		1803	Great Kimble, Little Kimble and Ellesborough ...	2,500
"	Hanslop	1,900	1805	Chearsley	917
"	North Marston	2,000	1806	Saunderton	1,200
1779	Bierton and Hallcot ...		1807	Newport Pagnell ...	900
"	Taplow		1808	Upton cum Chalvey ...	752
1781	Preston Bisset	1,000	1809	Langley Marish... ..	
1782	Calverton, and west side of Stony Stratford ...		"	Bledlow	4,000
1788	Bradwell... ..	1,000	"	Marsworth	1,200
"	Wavendon	2,000	1810	Datchett... ..	
1789	Bourton and Watchfield ...		"	Stoke Pogis	
1790	Bowbrickhill and Fenny Stratford	2,000	"	Bletchley	2,200
1791	Little Woolston... ..		"	Newnton Blossomville... ..	
1793	Castlethorpe				
Carried forward ...		40,207	Carried forward ...		16,769

BUCKINGHAMSHIRE—continued.

Date.	Enclosure.	Area enclosed.	Enclosed under the General Enclosure Act, 1845.			
	Brought forward	... 16,769				
1810	Slapton and Horton	...	Date of Act.	Date of Award.	Parish.	Area.
1811	Stewkley...	... 3,000				
1813	Turweston	...	1850	1855	Penn	... 1,078
1814	Aston Clinton	... 2,200	"	"	Hitchendon or	488
"	Mursley	...			Hughendon	... 608
1815	Amersham	... 890	1852	"	Great Marlow	... 1,140
1820	Little Marlow	... 450	1853	1856	Pitstone	... 1,350
"	Princes Risborough	... 2,900	"	1857	Cheddington and	2,350
1821	Farnham Royal...	...			Ivinghoe	...
"	Ivinghoe	...	1856	1865	Edlesborough	...
1822	Clifton Reynes	... 450				7,014
"	Towersey	... 986				
1824	Long Crendon	... 2,500				
1830	Haddenham	... 2,945				
"	Monks Risborough	...				
		<u>33,090</u>				
					Before 1802	... 71,323
					1802-1845	... 33,090
					After 1845	... 7,014

CAMBRIDGE.

Date.	Enclosure.	Area enclosed.	Date.	Enclosure.	Area enclosed.
1770	Abington Pigotts	... 1,000	1802	St. Giles, Cambridge	... 1,200
1775	Knapwell	... 1,100	"	Graveley	... 1,500
1777	Weston Colville...	... 1,970	"	Horningsea (with old enclosures)	... 1,450
1796	Barrington	... 2,500	"	Sawston	... 1,040
1797	Great Wilbraham (with old enclosures)	... *2,300	1803	Fen Ditton	... 1,400
"	Little Wilbraham	... 1,600	1804	Manea in Ely	... 900
1798	Harston, Hauxton, Little Shefford and Newton	...	1805	Snalewell	...
"	Longstow (with old enclosures)	... 1,400	"	Swaffham Prior...	...
"	Swaffham Bulbeck (with old enclosures)	... 4,000	1806	Dullingham	...
1799	Carlton cum Willingham (with old enclosures)	1,500	"	Fulbourn	...
"	Grantchester and Coton	...	"	Cherry Hinton	...
"	Pampisford	... 2,000	"	Kirtling and Ashley cum Silverley	... 3,000
1800	Connington	... 1,500	1807	Barnwell...	...
"	Elsworth	... 3,900	"	Landbeach	...
"	Guilden Morden	... 2,500	"	Steeple Morden	...
"	Milton	... 1,550	1808	Girton	...
1801	Great Abingdon...	... 1,560	"	Harlton	... 1,100
"	Little Abingdon	... 1,350	1809	Bourn	...
"	Balsham	... 4,000	"	Chatteris...	...
"	Bassingbourne	... 3,500	"	Dry Drayton	...
"	Bottisham	... 4,000	"	Fordham...	...
"	Histon and Impington...	...	"	West Wratting	...
"	Trumpington	... 2,000	"	Whittlesford	... 2,000
		<u>45,230</u>	1810	Hastingfield	...
			"	Ickleton	...
			"	Kinston	...
					Carried forward ... 13,590

CAMBRIDGE—continued.

Date.	Enclosure.	Area enclosed	Date.	Enclosure.	Area enclosed.
	Brought forward	... 13,590		Brought forward	... 30,674
1810	Teversham ...	...	1839	Melbourn ...	...
1811	Brinkley ...	...	"	Barton ...	...
"	Croxton ...	... 1,200	"	Comberton ...	...
"	Great and Little Eversdon ...	...	"	Rampton (with old enclosures) ...	... 1,100
"	Lanstanton All Saints ...	...	1840	Whittlesea ...	...
"	Shepreth ...	... 1,000	"	Thriflow ...	...
1812	Stapleford ...	... 1,400	"	Wicken ...	...
"	Toft ...	...	1841	Cheveley ...	...
"	West Whickham ...	...	"	Gamlingay ...	...
1813	Great Cransden ...	...	1842	Coltenham ...	...
"	Langstanton St. Michael	...	1843	Haddenham ...	...
"	Meldreth, Melbourn and Whaddon ...	...	1845	Foulmire ...	... 2,111
"	Little Shelford ...	... 1,200			33,885
"	Wood Ditton ...	...			
"	Waterbeach ...	...			
"	Kennet ...	...			
1814	Burwill ...	...	<i>Enclosed under the General Enclosure Act, 1845.</i>		
"	Stretchworth ...	...	Date of Act.	Date of Award.	Parish. Area.
1815	Papworth Everard ...	...	"	1854	Isleham ... 1,370
1819	Hinxton ...	...	1848	"	Caldecot ... 747
1822	Duxford ...	... 2,500	1850	"	Mepal ... 442
1825	Doddington and Coveney	... 290	1851	"	Newton ... 1,041
1826	Foxton ...	... 1,586	1847	1855	Wilburton ... 780
1828	Litlington ...	... 1,686	1855	1857	Westwick in Oakington ... 217
1829	Wentworth ...	... 990	1858	1863	Shudy Camps, Castle Camps and Bartlow ... 1,037
1830	Caxton ...	... 1,500	1864	1868	Ellisley ... 1,490
1833	Oakington ...	...	1883	1889	Hildersham ... 1,174
1834	Great Shelford ...	...			
1835	Stretcham ...	...			
1836	Hardwick ...	...			
"	Orwell ...	...			
1838	Sutton ...	...			
"	Swavesey ...	...			
"	Linton ...	... 3,732			
"	Witcham ...	...			
"	Chesterton ...	...			
"	Fen Drayton ...	...			
1839	Stow cum Quay ...	...			
	Carried forward	... 30,674			

CHESHIRE.

Date.	Enclosure.	Area enclosed.	Date.	Enclosure.	Area enclosed.
1805	St. Mary on the Hill (certain quilllets of intermixed lands) ...	... 126		Brought forward	... 126
	Carried forward	... 126	1814	Wendon and Arksden ...	... 3,200
					3,326

CUMBERLAND.

Date.	Enclosure.	Area enclosed.	Date.	Enclosure.	Area enclosed.
1772	Great and Little Stanton, Newbiggin and Great Blencow ...	...	1813	Greystoke, 240 A. F. ...	3,500
1779	Irthington, 3,600 A. waste and divers open fields ...	4,000	1814	Torpentrow, 20 A. F., 700 A. waste ...	720
		4,000	1825	Dearham... ..	480
					<u>4,700</u>
				Before 1802 ...	Acres. 4,000
				1802-1845 ...	4,700

DERBYSHIRE.

Date.	Enclosure.	Area enclosed.	Date.	Enclosure.	Area enclosed.
1727	Scarcliffe and Palterton, 500 A. F., 420 A. P. ...	970	1783	Brought forward ...	15,118
1756	Weston cum Membris and Sawley ...	...	1785	Boilstone... ..	500
1760	Mackworth ...	...	1785	Holbrooke ...	500
1762	Aston-upon-Trent ...	1,500	1786	Weston upon Trent ...	1,500
"	Elvaston and Thulston ...	...	1787	Barrow upon Trent ...	1,000
1763	Draycott ...	...	"	Little Eaton ...	900
"	Scropton... ..	...	"	Melbourne and King's Norton ...	2,500
"	Tideswell ...	1,000	"	Sawley ...	750
1764	Ashford and Sheldon (Bakewell P.) ...	...	1786	Parwick ...	1,000
1765	Long Eaton, 131 oxgangs ...	1,600	"	Spondon ...	1,000
"	Hartshorn ...	...	1789	Marston upon Dove, Hatton, Horn and Hornhay ...	830
1766	Repton ...	...	"	Osmaston next Derby, 270 F. ...	*500
"	Willington ...	1,300	1790	Mickleover ...	800
1768	Littleover ...	1,200	1793	Taddington and Priest-cliff ...	1,600
"	Normanton next Derby ...	700	1794	Ilkeston ...	760
1771	Fairfield, 860 A. P. ...	*1,000	1795	Barlborough, 250 A. F., 650 A. P. ...	900
"	Stapenhill and Wins-hill, 400 A. F., 160 A. P. ...	560	"	Eckington, 200 A. F. and M. I. 1,070 A. P. ...	1,270
"	Stretton, Hordington, Bondend and Braunston, 600 A. F., 610 A. P. ...	1,210	1797	Etwall ...	1,600
1772	Ockbrock ...	700	1798	Hartington ...	12,000
1773	Church Broughton, 160 A. F., 100 A. P. ...	360			<u>45,028</u>
1777	Killamarsh, 60 A. F., 350 A. P. ...	410	1802	Alvaston and Boulton ...	1,200
"	Tibshelf, 42 A. F., 404 A. P. ...	446	"	Chellaston ...	700
1778	Bolsover and Clown ...	...	1803	Brassington and Brad-bourne... ..	4,000
1780	Findern ...	500	"	Great Hacklow, mesne fields ...	400
"	Hilton, 400 A. F., 600 A. P. ...	1,000	1804	Little Hacklow, 400 A. P. and mesne fields ...	600
1782	Sandicare ...	662			<u>6,900</u>
	Carried forward ...	15,118		Carried forward ...	6,900

DERBYSHIRE—*continued.*

Date.	Enclosure.	Area enclosed.	Date.	Enclosure.	Area enclosed.
	Brought forward ...	6,900		Brought forward ...	37,811
1805	Chelmorton and Flag	1,300	1814	Brampton, M. I.	3,000
1806	Bakewell and Over Had-		1815	Youlgreave, mesne or	
	den ...	2,800		intermixt lands ...	1,160
"	Hope, Bradwell and		1816	Homesfield ...	3,000
	Thornhill ...	1,400	1817	Hollington ...	280
1807	Wheston and Tideswell,		1818	Norbury, 100 A. P.	200
	M. I. ...	4,000	1820	Smisby ...	550
1808	Hathersage ...	10,000	1821	Whittington ...	284
1809	Dronfield, M. I.	5,000	1824	Snelston ...	160
"	Elton and Winster ...	500	1834	Kirk Langley, 110 A. F.,	
1810	Great and Little Lang-			120 A. P. ...	230
	stone and Wardlow,				
	M. I. ...	1,500			<u>46,675</u>
1811	Beeley ...	2,000			
1813	Whitwell ...	950			
1814	Breadsall ...	1,461			
	Carried forward ...	37,811			

	Acres.
Before 1802 ...	45,028
1802-1845 ...	46,675

DORSET.

Date.	Enclosure.	Area enclosed.	Date.	Enclosure.	Area enclosed.
	Brought forward ...			Brought forward ...	1,525
1733	Buckland Newton, 800		1805	Broadmaine ...	990
	A. F., 800 A. P.	1,600	1806	Hampreston ...	
1736	West Stafford c. Froome		1807	Corfe Mullen, 200 A. F.,	
	Bellet ...	600		&c., 1,500 A. Heath ...	1,700
1761	Langton Herring ...		"	Cattistock ...	1,200
1762	Portesham ...	1,200	1808	Winterborne Waste ...	777
1768	Winfrith Newburgh ...	2,254	1809	Abbotsbury ...	1,500
1779	West Knighton ...	1,000	"	Compton Vallance ...	
1785	Wimborne Minster ...	3,000	"	Gillingham and Mot-	
1789	Podington ...			combe ...	500
1794	Tolpuddle ...		"	West Melbury ...	
"	Preston and South		"	Pimperne ...	
	Poyntz ...		1809	Plush ...	359
1796	Hanley ...		"	Great Washbourne ...	
1797	Hintel Murtel and Gus-		1810	Litton Cheney ...	780
	suage All Saints ...		"	Walditch, 187 A. F., 9	
"	Wyke Regis ...			A. P. ...	196
1798	Bradford Peverell ...		1811	Shapwick ...	1,160
1799	Charlton Marshall ...	2,200	1812	Gussage St. Michael ...	1,100
1800	Winterborne Strickland	1,050	1814	Tarrant Keinston, all F.	169
1801	Turnwood ...	800	1815	Dawlish ...	400
			1818	Loders ...	450
			1819	Brodd Sydling and Up	
				Sydling ...	
1803	Chickerill ...		1820	Chilfrome ...	900
"	Spetisbury ...	1,000	1824	Bincombe ...	1,300
1804	Beaminster, 290 A. F.,		"	Tarrant Hinton ...	2,000
	235 A. P. ...	525			
	Carried forward ...	1,525		Carried forward ...	17,006

DORSET—continued.

Date.	Enclosure.	Area enclosed.	Date of Act.	Date of Award.	Parish.	Area.
	Brought forward	... 17,006				
1830	Charminster ...	700			Brought forward	... 704
1831	Maiden Newton ...	800	*	1854	Askerswell	... 635
"	Piddle Hinton ...	1,600	1855	1857	West Lulworth	... 634
1834	Upway ...	320	1857	1860	Ashmore	... 635
1836	Godmanstone ...		1861	1863	Winterborne	
					Steepleton	... 558
			1866	1868	Warmwell	... 620
		<u>20,426</u>				

Enclosed under the General Enclosure Act, 1845.

Date of Act.	Date of Award.	Parish.	Area.
1851	1853	Compton Abbas	... 704
		Carried forward	... 704

	Acres.
Before 1802	... 13,704
1802-1845	... 20,426
After 1845	... 3,786

DURHAM.

Date.	Enclosure.	Area enclosed.	Date.	Enclosure.	Area enclosed.
1761	Norham, In fields, 437		1814	Gateshead	... 200
	A., moor 1,500 A.	... 1,937			
1769	Wolsingham	... 200			
1782	Bolam	... 800			
1783	Barnard Castle	... 800			
1794	Crawcrook	... 700			
		<u>4,437</u>			

	Acres.
Before 1802	... 4,437
1802-1845	... 200

ESSEX.

Date.	Enclosure.	Area enclosed.	<i>Enclosed under the General Enclosure Act, 1845.</i>			
Date.	Date of Act.	Date of Award.	Parish.	Area.		
1795	Great Parndon, 227 A. F.,					
	124 A. P.	... 351				
1801	Great Chesterford	... 1,200	1846	1850	Walthamstow	... 198
"	Little Chesterford	... 600	*	1851	Henham	... 630
"	Hadstock	... 1,400	1847	"	Netteswell	... 204
"	Littlebury	... 3,000	*	"	Langley	... 360
		<u>6,551</u>	*	1853	Haverhill	... 298
			*	"	Wicken Bonhunt	... 292
1807	Chrishall	... 1,500	1855	1860	Roydon	... 285
1811	Great and Little Chishill	2,500	1856	1861	Newport	... 815
1812	Saffron Walden	...	1859	"	Clavering	... 750
1814	Heydon	...	1866	1869	Widdington	... 820
1820	Farnham	... 240				
1824	Wendon Tofts and Elmdon	... 1,950				
1838	Berden, Manewden, Stansted Mountfichet	...				
		<u>6,190</u>				

	Acres
Before 1802	... 6,551
1802-1845	... 6,190
After 1845	... 4,652

GLOUCESTER.

Date.	Enclosure.	Area enclosed.	Date.	Enclosure.	Area enclosed.
1726	Little Rissington ...			Brought forward ...	53,706
1727	Cherrington, 3 F.'s, 1,800		1777	Shirburne and Windrush	
	A.	2,200	1778	Chapel Honeyburn, 32 yl.	*1,120
1729	Wick Risington, 58 yl...	*2,000		" Frampton and Hayley...	1,500
1731	Prestbury			" Leckhampton and Chel-	
	Upper and Lower Slaugh-			tenham	
	ter, 87 yl.	*2,845		" Naunton, 53 yl.	*1,855
1739	Shipton, Moyle and Dovel,			" Siddington St. Peter and	
	all F.	800		St. Mary	534
1744	Westonbirt, 2 F.'s	350	1779	Abington	1,000
1753	Eastlechmartin, 53½ yl...	*1,863		" Buckland	2,000
	Quennington	3,000		" Clifford Chambers	400
1755	Hawling	881		" Mayseyhampton	1,600
1759	Little Barrington, 42 yl.		1780	Salperton	1,354
	F., 600 A. P.	*1,860		" Shennington, 1,500 A. F.	*1,800
	" Preston upon Stower, 25½		1782	Eastrington	2,500
	yl.	*900		" Winstow (Winstone)	770
1761	Snowshil, 500 A. F., 18		1786	Oddington	1,000
	A. M., 1,100 A. P.	1,618	1789	Lower Swell	
1763	Childswickham, 83 yl...	*2,905	1792	Broadwell	
1765	Donnington (Stow on			" Rodmorton and Coates...	
	the Wold P.)			" Shipton, Whittington and	
1766	Haselton	858		Dowdeswell	
	" Hatherop, 966 A. F., 150			" Turkdean	
	A. P.	1,116	1793	Aldsworth	
	" Mangersbury			" Marsmore	1,800
1767	Bibury, 3,000 A. F., 300		1794	Little Compton	
	A. P.	3,300		" Corse	
	" Willersey, 36 yl.	*1,260		" Elmore Brockworth and	
1769	Ampney Holyrood and			North Cerney... ..	
	Ashbrook	2,080		" Longborough	1,453
	" Bledington, 52 yl.	*1,820		" Old Sodbury and Little	
	" Coln St. Aldwin's, 1,950			Sodbury	800
	A. F., 100 A. P.	2,050	1795	Cold Aston	1,600
1770	Notgrove	1,200		" Hasfield	
1771	Aston Subedge, 31 yl. F.,			" Trinley	
	150 A. P.	*1,235	1796	Awre	
	" Preston and Stratton ...	2,000		" Barnwood, Matson,	
1772	Eastleach Tourville, 1,574			Wotton	
	A. F., 877 A. P.	2,451	1797	Ashelworth	
	" Kemerton, 36 yl.	*1,260		" Coln St. Dennis... ..	
	" Quinton, 39½ yl.	*1,372		" Horton	611
1773	Bourton on the Water ...		1798	Guiting Power	
	" Beckford... ..	2,500	1799	Berrington, Broad Camp-	
	" Longmarston, 43 yl. ...	1,505		den and Westington...	
1774	Oxenton	1,000		" Kempford and Dryfield	
	Staunton... ..	700	1800	Welford	
1775	Addlestrop	926		" Arlington	
	" Claydon, all F.	1,081	1801	Cheltenham	
	" Todenham, 32 yl. F. ...	*960		" Down Ampney, Lutton,	
1776	Dorsington, 40 yl.	900		Eisey	1,242
1777	Condicote, 26 yl.	*910		" Slimbridge, Cam and	
	" Duntisborne Abbots ...			Coaley... ..	
Carried forward ...		53,706			
					<u>78,645</u>

GLOUCESTER (*continued*).

Date.	Enclosure.	Area enclosed.	Date.	Enclosure.	Area enclosed.
1802	Churcham ...	...		Brought forward ...	16,580
1803	Chedworth and Compton		1830	Cheltenham ...	430
	Abdale... ..	6,200	"	Stanley St. Leonards and	
"	Staverton with Bodding-			Eastington ...	170
	ton	...	1832	Thornbury ...	514
"	Beverstone ...	2,200	1833	Elkstone ...	280
1804	Sutton ...	1,120	1834	Duntsbourne Rouse ...	496
"	Temple Guiting... ..	...	1838	Quedgley ...	90
"	Broyden ...	...	"	Wickwar, Cromhall and	
1805	Tredington ...	...		Tortworth 90 A. F.,	
1806	Gotherington ...	...		600 A. P. ...	690
"	Norton ...	...	1839	Fretherne and Saul 380	
1807	Downhatherley ...	...		A. F., 106 A. M. & P.	486
"	Pannington ...	...	"	Berkeley ...	700
"	Stanley Pontlarge ...	...	1841	Olveston ...	180
"	Alderton... ..	...			
1808	South Cerney ...	...			20,616
"	Deerhurst and Lye ...	...			
"	Tewkesbury ...	...			
1809	Alvington ...	...			
"	Stanway ...	...			
1811	Fiddington ...	...			
1812	Aston upon Carrant and				
	Pamington Home-				
	downs	...			
"	Greet and Sudely (in				
	Winchcomb parish)... ..	...			
"	Haresfield ...	...			
"	Longney ...	...			
"	Pebworth (with old				
	enclosures)	2,000			
"	Wormington ...	...			
1813	Ebrington and Hitcoat...	...			
"	Frampton upon Severn				
	and Slimbridge ...	...			
"	Great Rissington ...	1,600			
"	Withington ...	...			
1814	Hempstead, Barnwood				
	and Upton St. Law-				
	rence	*200			
"	Sevenhampton ...	...			
"	Winchcomb ...	...			
1815	Miserden... ..	...			
1818	Hawkesbury ...	...			
"	Morton Vallance and				
	Standish	...			
1819	Bitton 70 A. F., 190 A. P.	260			
1821	Bourton on the Hill				
	and Moreton in the				
	Marsh	3,000			
1829	Didmarton and Oldbury				
	on the Hill	...			
	Carried forward ...	16,580			

Enclosed under the General Enclosure Act, 1845.

Date of Act.	Date of Award.	Parish.	Area.
*	1851	Tibberton ...	222
*	1852	Westbury on	
		Severn ...	855
1851	1853	Marshfield ...	290
1850	1854	Weston Subedge ...	879
1855	1862	Dymock ...	208
1864	1867	Sandhurst, Norton	
		and Wotton ...	506
1865	1869	Stinchcombe ...	205
1866	1871	Minsterworth ...	400
"	1876	Coaley ...	154
"	"	Cam ...	166
1895	1899	Upton St. Leonards	534
			4,419

	Acres.
Before 1802 ...	78,645
1802-1845 ...	20,616
After 1845 ...	4,419

HAMPSHIRE.

Date.	Enclosure.	Area enclosed.	Date.	Enclosure.	Area enclosed.
1740	Andover	...	1802	West Aston and Middle-	...
1741	Chawton, 7 F.'s and	...	ton	750	
	the Common	...	1803	Kilmiston	...
1743	Dunmer, 1260 A. F., 500	...	1804	Romsey Extra	...
	A. P.	1,760	1805	New Alresford, 326 A. F.,	...
1749	East Woodhay and Hol-	...	84 A. P.	410	
	lington, 1,000 A. F., 300	...	1806	Monxton... ..	600
	A. P.	1,300	1807	Ringwood	...
1757	Barton Stacey, 1807	...	1808	Porchester	1,050
	A. F., 678 A. P. ...	2,507	1810	Eling and Fawley ...	...
"	Earlstone	488	1812	Charlton, Catherington,	...
1759	Bishop's Waltham ...	205		Clanfield, Blendworth	...
1760	Folkesworth	510		and Idsworth	2,500
"	Fletton	...	"	Ovington	...
1774	Abbott's Ann	1,259	"	Wimmering, Widley	...
1778	Gratley	...		Cosham, and Hilsea	800
1780	Leckford Abbots ...	...	"	Weyhill and Appleshaw	680
1781	Highclere (or Burgh-	...	1813	Ecchinswell	500
	clere)	...	1817	Harbridge	...
1783	Kingsomborn	1,890	"	Portsea	170
"	Andevor	...	1820	Preston Candover and	...
1785	Upper Clatford ...	...		Nutley	1,800
1786	Basingstoke	...	1822	Ellingham and Ilsley ...	...
"	Upper Wallop, Hars-	...	1825	Christchurch and Milton	...
	bourne Pryors and	...	1827	Tangley, 286 A. F., 10	...
	Tufton	...		A. P.	296
1788	Headbourn Worthy ...	1,400	1829	Sherborne St. John ...	1,000
1789	Broughton	2,700	1842	Kingsclere	2,300
"	Odiham, Northwarn-	...			
	borough, Hillside, Rye	...			
	and Stapely	...			
1790	Dibden	...			
1792	Monk Sherburne ...	700			
"	Shipton	...			
1794	Crawley and Bishop's	...			
	Sutton... ..	...			
"	Houghton	...			
"	Quarley... ..	...			
"	Upton Gray	...			
1796	Basing and Mappleder-	...			
	well	...			
"	Mitchelmarsh, Braish-	...			
	field and Awbridge...	...			
"	Nether Wallop	...			
1797	Whitchurch	...			
1798	Welstead and Bent-	...			
	worth	400			
"	Rockbourne and Wich-	...			
	bury	...			
1799	Easton	...			

15,459

Enclosed under the General Enclosure Act, 1845.

Date of Act.	Date of Award.	Parish.	Area.
*	1852	Chale	126
1849	1857	Binsted	990
1856	1859	Niton (Isle of Wight)	449
1861	1866	(Easton common fields) Freshwater	37
			1,512
			Acres.
	Before 1802 ...		15,459
	1802-1845 ...		12,856
	After 1845 ...		1,512

HEREFORD.

Date.	Enclosure.	Area enclosed.	Date.	Enclosure.	Area enclosed.
1772	Wigmore, 600 A. F., 80 A. P. ...	680	1811	Brought forward ...	2,900
1795	Marle Wolton and Kingston ...	1,000	1811	Eardisland ...	270
1796	Tarrington ...	450	1813	Clehonger ...	
1799	Yarkhill, Weston Begard, Dormington w. Bartestree, Stoke Edith with Westhide ...	1,380		Much Cowarn ...	
	Leintwardine and Burington ...			Stretton, Grandsome and Bishops Frome ...	
1801	Frome, Much Cowarne and Evisbeach, 250 A. F., 160 A. M. ...	410		Eastnor, 180 A. P. ...	*220
				Ledbury, 50 A. F., 90 A. P. ...	140
			1814	Norton Canon ...	
				Aymestrey and Kingsland ...	340
				Puttenham ...	
		<u>3,920</u>			<u>3,870</u>

1802	Bodenham ...	2,000
1807	Byford ...	
	Marden, Sutton and Withington ...	
1809	Bredwardine and Dorston ...	
	Bishopston and Mancell Lacy ...	
	Mordiford ...	
	Shobden, Aynestry and Lingen ...	900
1810	Steepleton ...	
	Wigmore ...	
1811	Allesmore ...	
	Carried forward ...	<u>2,900</u>

Enclosed under the General Enclosure Act, 1845.

Date of Act.	Date of Award.	Parish.	Area.
*	1854	Bosbury ...	105
*	1856	Ullingswick ...	260
1858	1862	(Lyde Fields) Pipe and Lyde ...	13
			<u>378</u>
		Before 1802 ...	Acres.
		1802-1845 ...	3,920
		After 1845 ...	378

HERTFORD.

Date.	Enclosure.	Area enclosed.	Date.	Enclosure.	Area enclosed.
1766	Hexton, 1,527 A. F. ...	*2,000		Brought forward ...	12,624
	Walsworth (Hitchin par.) ...	1,000	1799	St. John and All Saints, Hertford ...	
1768	Lilley and Offley ...		1801	Aldenham ...	500
1776	Ickleford ...			Barkaway and Reed ...	7,000
1795	Kelshall (with old enclosures) ...	2,233		Hertingfordbury ...	400
1796	Norton ...	1,850			<u>20,524</u>
1797	King's Walden ...	500			
	Tring ...		1802	Hinxworth ...	1,264
	Weston ...	1,100	1806	Cottered ...	
1798	Kensworth ...	1,200	1807	Offley ...	
1799	Cheshunt, 1,555 A. F., 1186 A. P. ...	2,741	1809	Barley ...	1,700
	Carried forward ...	<u>12,624</u>		Carried forward ...	<u>2,964</u>

HERTFORD—*continued.*

Date.	Enclosure.	Area enclosed.	Date of Act.	Date of Award.	Parish.	Area.
	Brought forward ...	2,964			Brought forward ...	3,161
1810	Codicote, Welwyn and Knebworth ...		1852	1855	Watford Field ...	70
1811	Pirton ...		*	"	Hoddesden ...	860
"	Wymondby and Ippolitts ...		*	1856	Widford ...	320
1812	Braughing ...	1,300	1853	1858	Wormley ...	232
1813	Westmill... ..	400	1858	"	Aston, Bennington, and Little Munden ...	1,280
1814	Great Hormead ...	900	"	1859	Little Hadham ...	214
1820	Bishop's Stortford ...	300	1857	1863	Ashwell ...	2,474
1826	Anstey ...	1,200	"	1864	Little Hormead and Layston... ..	450
1830	Standon ...	1,400	1862	1867	Datchworth and Knebworth ...	161
		<u>8,464</u>	1866	1869	Throcking... ..	108
<i>Enclosed under the General Enclosure Act, 1845.</i>						
Date of Act.	Date of Award.	Parish.	Area.			
*	1850	Walkern ...	540			
*	1852	Bengeo, Sacombe and Stapleford... ..	410			
*	1853	Great and Little Munden ...	860			
*	"	Buckland ...	795			
*	1854	Stevenage ...	556			
	Carried forward ...	3,161				
					Acres.	
					Before 1802 ...	20,524
					1802-1845 ...	8,464
					After 1845 ...	10,775

HUNTINGDON.

Date.	Enclosure.	Area enclosed.	Date.	Enclosure.	Area enclosed.
1727	Overton Longville and Botolph's Bridge ...			Brought forward ...	21,875
1766	Laighton Bromeswold ...	1,515	1795	Great Catworth...	2,000
1767	Yaxley ...		"	Wornditch ...	700
1769	Stoneley ...	1,000	"	Warboys...	4,300
1770	St. Noets ...	300	1796	Woodhurst, Somersham, and Pidley with Fen-ton, 2,625 A. P. ...	*3,000
1771	Hartford...	1,400	1797	Diddington ...	1,100
1772	Brampton ...	2,500	"	Eynesbury ...	2,000
"	King's Ripton ...	1,100	"	Southoe ...	1,100
"	Wolley ...	1,000	1799	Molesworth ...	1,000
1773	Houghton cum Witton...	2,500	1800	Bythorn ...	1,200
"	Little Stukely ...		"	Holywell and Needingworth ...	3,000
1774	Ellington ...	1,500	"	Offord Cluny ...	1,100
"	Easton ..		1801	Covington ...	850
"	Graffham ...		"	Hemingford Grey and Abbots ...	3,000
1775	Spaldwick with Upthorpe		"	Old Hurst ...	1,000
1779	Elton ...	3,000	"	St. Ives ...	1,400
1780	Barham ...	800	"	Stanground and Farcet...	1,522
"	Little Catworth...				
1786	Ravely ...	2,000			
1794	Broughton ...	1,600			
"	Winwick...	1,660			
	Carried forward ...	21,875			50,147

HUNTINGDON—continued.

Date.	Enclosure.	Area enclosed.	Date.	Enclosure.	Area enclosed.
1802	Denton	1,000		Brought forward ...	30,735
"	Fenstanton	2,200	1813	Stukely	2,000
1803	Godmanchester ...	4,600	1819	Yelling, whole year lands	1,800
1804	Brington (with old en-		1830	Wistow	1,300
	losures)	1,250	1836	Abbotsley	
1804	Saltree	2,700	1843	Great Gransden... ..	3,000
"	Great Staughton ...	900	1844	Bury	299
1805	Cherry Orton, Waterville		"	Ramsey	230
	and Alwalton... ..				
"	Stilton	1,200			39,364
1806	Offord Darcy	1,000			
1807	Stibbington cum Wan-		<i>Enclosed under the General Enclosure</i>		
	desford and Sibson ...	565	<i>Act, 1845.</i>		
"	Great Staughton and		Date	Date	
	Graffham	2,000	of	of	Parish.
1808	Swineshead	900	Act.	Award.	Area.
"	Waresley and Gamlingay		"	1852	Keystone
	(with old enclosures)	2,000		1853	Upwood and Ram-
1809	Glatton with Holme ...	1,300		sey	1,600
"	Woodstone	500	1864	1869	Great Gidding ...
1811	Great Paxton and Tose-				1,735
	land	2,100			
1812	Little Paxton	720			3,855
"	Upton	900			
1813	Bluntisham w. Earith				
	and Colne	3,000			Acres.
"	Buckdon	1,900		Before 1802 ...	50,147
				1802-1845 ...	39,364
				After 1845 ...	3,855
	Carried forward ...	30,735			

LEICESTER.

Date.	Enclosure.	Area enclosed.	Date.	Enclosure.	Area enclosed.
1730	Horninghole	916		Brought forward ...	15,506
1734	Little and Great Cley-		1759	Sibley	2,200
	brooke	430	1760	Barrow upon Soar ...	2,250
1744	Langton		"	Frisby upon the Wreak.,	1,500
1749	Norton juxta Twicross...	1,744	"	Hoby	1,000
1752	Narborow, 30 yl. ...	*1,050	"	Hinckly	2,000
1755	Knighton, 48 yl. ...	*1,680	"	Melton Mowbray ...	2,000
1757	Wimeswould	*1,440	"	Somerby	1,400
1758	Great Glen, 32½yl. ...	1,000	"	Seagrave	
1759	Breedon	1,336	1761	Ashfordby	1,800
"	Belgrave, 34 yl....	1,000	"	Ansty	1,100
"	Desford and Peckleton...	1,010	"	Abkettleby	900
"	Evington and Stough-		"	Rearsby	1,600
	ton	1,000	1762	Belgrave and Barkby ...	1,600
"	Hoton	1,100	"	Hungerton	900
"	Loughborough, 6 F.'s and		"	Quorndon	1,020
	P.		1764	Billesden	2,500
"	Oadby, 71 yl.	1,800	"	Nether Broughton ...	900
	Carried forward ...	15,506		Carried forward ...	40,176

LEICESTER—continued.

Date.	Enclosure.	Area enclosed.
	Brought forward ...	40,176
1764	Husband's Bosworth,	
	96 yl. ...	4,000
"	St. Margaret's, Leicester,	
	34 yl. ...	*1,190
"	Sharnford, 48½ yl. ...	1,400
"	Stoney Stanton, 46½ yl. ...	1,400
"	Wartnaby ...	700
"	Whetston, 49½ yl. ...	*1,733
"	Great Wigstone... ..	
1765	Burton Overy ...	1,600
"	Grimston ...	1,000
"	Houghton-on-the-Hill ...	1,800
"	North Kilworth, 80 yl... ..	1,800
"	Scaford ...	2,000
1766	Braunston ...	1,500
"	Blaby, 38½ yl. ...	1,200
"	Croxton ...	2,100
"	Countesthorpe, 38 yl. ...	1,400
"	Lubenham, 31 yl. ...	960
"	Ratcliffe Culey ...	560
"	Waltham in the Wolds... ..	2,000
1767	Aileston ...	1,200
"	Cosby, 52½ yl. ...	*1,837
1768	Ashby de la Zouch ...	1,040
"	Little Sheepey, 24 yl. ...	500
1769	Eaton, 97½ yl. ...	1,800
"	Fleckney, 47½ yl. ...	*1,654
"	Markfield ...	380
"	Shackston, 28 yl. ...	*980
"	Thurlstone, 23½ yl. ...	750
1770	Bottesford, Eastthorpe	
	and Normanton, 203½	
	oxgangs ...	4,300
"	Foxton ...	1,500
"	Halloughton ...	3,000
"	Norton, 25 yl. ...	665
"	Ratby, all F. ...	850
"	Ravenstone ...	250
"	Saddington ...	1,500
1771	Appleby ...	1,000
"	Kirkby Mallory... ..	780
"	Keyham (Rothley P.) ...	900
"	Kilby and Newton Har-	
	court, 78 yl. ...	2,000
"	Sproxtton, 49 yl. ...	2,000
"	Saltby, 54 yl. ...	2,400
1772	Gumley ...	1,145
"	Skeffington ...	1,200
"	Stapleford ...	390
1773	Knaptoft, 48 yl... ..	1,050
1774	Hucklescote and Don-	
	nington on the Heath	500
	Carried forward ...	104,190

Date.	Enclosure.	Area enclosed.
	Brought forward ..	104,190
1774	Ratcliffe upon Wreak,	
	26 yl. ...	800
1776	Bruntingthorpe, 44 yl... ..	1,200
"	Great Bowden, 88 yl. ...	2,600
1777	Gilmorton, 44½ yl. ...	2,200
"	Shepshead ...	2,000
"	Syston and Barkly ...	1,600
"	Wykeham and Candwell,	
	26½ yl. ...	750
1778	Earl Shilton ...	1,500
"	Kimcoate and Knaptoft,	
	84 yl. ...	2,600
"	Sapcote ...	1,300
"	Long Whatton ...	800
"	Castle Donington, 1400	
	A. F., 290 A. M., 610	
	A. P. ...	2,300
"	Kegworth ...	2,000
1779	Barkby ...	1,800
"	Croft ...	850
"	Claxton or Long Claw-	
	son, 169 oxgangs ...	*3,380
"	Knight Thorpe ...	450
"	Leire, 31½ yl. ...	370
"	Stanton under Barden... ..	600
"	Kibworth and Smeeton	
	Westerby, 148 yl. ...	3,900
1780	Stonesby ...	1,100
"	Swinford... ..	1,400
1781	Cropton... ..	360
"	Mountsorrell, 300 A.F....	*450
"	Rothley ...	1,200
1782	Orton on the Hill ...	1,000
1783	Tugby ...	1,150
1785	Osgathorpe ...	200
1786	Bitteswell ...	1,600
1788	Humberstone ...	1,400
"	Mousley ...	1,100
1789	Grooby ...	500
"	Hemmington ...	1,000
"	Harston ...	*800
"	Thrussington, 47 yl. ...	*1,645
1790	Harby ...	
"	Lutterworth, 69 yl. ...	1,400
1791	East and West Langton,	
	&c., 152 yl. ...	*5,320
1792	Redmile ...	
"	Strathern ...	
"	Walton in the Wolds,	
	52½ yl... ..	1,500
1793	Queneborough ...	2,200
"	Slawston... ..	1,400
	Carried forward ...	163,915

LINCOLN—continued.

Date.	Enclosure.	Area enclosed.	Date.	Enclosure.	Area enclosed.
	Brought forward ...	60,102		Brought forward ..	147,482
1766	Keddington ...	400	1773	Helpringham ...	3,000
"	Kettlethorp ...	645	"	Halham and Roughton	2,000
"	Scothorne and Sudbrooke	2,800	"	Horsington ...	1,500
1767	East Barkwith ...	1,200	"	East Keal ...	900
"	Donnington ...	3,100	"	Toynton All Saints and	
"	Newton ...	1,000	"	St. Peter ...	1,000
"	Scamblesby ...	2,100	"	Thorpe on the Hill ...	1,700
"	Wootton ...	3,000	"	Whitton ...	1,200
1768	Billingborough and Bir-		"	West Willoughby, 34 ox-	
"	thorpe ...	2,700	"	gangs and large com-	
"	Morton ...	4,400	"	mon ...	*1,000
"	Threckingham ...	500	1774	Ibstock ...	1,200
"	Toynton Supra ...	1,100	"	Ludborough ...	
"	Willoughton ...	2,600	"	Owmy ...	1,600
1769	Atterby, Smitherby and		"	Potterhamworth ...	3,000
"	Waddingham ...	3,000	"	Spridlington ...	2,400
"	Barnolby le Beck ...	1,200	"	Timberland ...	2,500
"	Beckenham and Sutton		"	Wilsford ...	2,400
"	Claypole ...		"	West Keal ...	1,000
"	North Hickham ...		"	Wroot ...	700
"	Ingham ...	2,000	1775	Fulletby ...	2,000
"	Sudbrooke (Ancaster P.)	1,200	"	Quadring, 70 A. F., &c.,	
"	South Willingham ...	1,800	"	2,400 A. fen ...	2,470
"	Waltham ...	2,250	1776	Asterby and Goulesby ...	2,600
1770	Benniworth ...	2,292	"	Gunby and North	
"	Great Carlton ...	2,000	"	Witham ...	1,650
"	Matton ...	1,180	"	North and South Killing-	
"	Navenby ...	2,800	"	holme ...	5,000
"	Scawby ...	2,500	"	Nocton ...	4,500
"	Waddington, 195 ox-		"	Raithby, nr. Spilsby ...	600
"	gangs ...	3,500	"	Upton, 1430 A. F., 1150	
"	Winterton, 2,000 A. F.,		"	A. P. ...	2,580
"	360 A. M., 1,000 A. P.	3,360	"	Welby, 970 A. F. ...	*1,200
"	Westborough cum Dod-		"	Nettleham ...	3,000
"	dington ...		1777	Brampton ...	1,060
"	Welton (near Louth) ...		"	Candlesby ...	900
1771	West Ashby ...	3,000	"	Hatherne ...	1,300
"	Boothby Graffoe ...	1,600	"	Kirlington ...	1,800
"	Bishop Norton ...	1,700	"	Leadenham ...	3,000
"	South Reston ...	500	"	Metheringham ...	5,000
1772	Hammeringham ...	1,000	"	South Winstead ...	1,700
"	West Halton ...		"	South Sturton ...	1,500
"	Moorby and Wilksby ...	1,000	"	Surfleet, 1,240 A. fen.,	
"	Great Paunton ...	*3,000	"	300 A. F., &c. ...	1,540
"	Middle Raisin ...	4,000	1778	Hackthorne ...	2,660
"	Stainby ...	1,380	"	Ruskington ...	3,000
"	Low Toynton ...	373	"	Thimbleby ...	1,200
"	Welton ...	3,000	1779	Amcotts ...	1,300
1773	Brinkhill ...	600	"	Brattleby ...	1,050
"	Goxhill ...	7,000	"	Huttoft, 1,200 A. F., 670	
"	Hemingby ...	2,600	"	A. P. ...	1,870
"	Hackonby ...	2,000	"	Market Raisin ...	725
Carried forward ...		147,482	Carried forward ...		229,787

LINCOLN—*continued.*

Date.	Enclosure.	Area enclosed.	Date.	Enclosure.	Area enclosed.
	Brought forward ..	229,787		Brought forward ..	317,224
1779	Willingham	1,500	1797	Barrow	4,700
1780	Ligburn	1,213	"	Blankney and Scopwick	3,850
1785	Donnington upon Baine	1,600	"	Greatford	850
1786	Canwick	2,240	"	Swayfield and Corby ...	
1787	Dorrington	1,800	1798	Messingham and East	
1788	Swaby and Belleau ...	1,500	"	Butterwick	5,000
"	North and South Rauceby	5,450	"	Mavis Enderby	800
1789	Denton	2,650	1800	Barholm	930
"	Normanby next Spittal	1,700	"	Braceborough	1,110
1791	Nettleton	3,600	"	Wrawly cum Brigg ...	2,450
"	Ludford	2,400	1801	Belchford	2,300
1792	Hemswell	2,220	"	Little Bytham and	
"	Tealby	2,600	"	Ormby	1,500
"	Uffington	2,600	"	West Deeping and Tal-	
"	Wood Enderby	600	"	lington	2,000
"	Welton in the Marsh ...		"	South Ferriby	1,500
1793	Allington	900	"	East Halton	2,500
"	Barton upon Humber ...	5,770	"	Langtoft and Baston ...	2,100
"	Covenham	1,600	"	Sotby	1,000
"	Dunston	1,220	"	Scremby	550
"	Greetham	1,000	"	Ashby	1,830
"	Kirton in Lindsey ...	4,600	"	Louth	1,854
1794	Althorpe... ..	380			
"	Long Bennington and				354,048
"	Foston	3,860			
"	Bottisford and Yadle-		1802	Kelby, Aiseby and Oseby	2,500
"	thorpe	1,750	"	Thurly, 1,100 A. F.,	
"	Faldingworth	2,400	"	1,100 A. fen	2,200
"	South Kelsey	3,200	"	Coningsby	1,750
"	Martin	550	"	Saxelby	1,200
"	Skillington	1,950	1803	Burton and West Halton	1,400
"	New Sleaford and Hold-		"	Boultham	636
"	ingham	2,000	"	Kirkby cum Osgodby ...	1,350
"	South Witham	1,646	"	Rippingale and Kirkby	
1795	Grantham	1,688	"	Underwood, 2,150	
"	Hagworthingham ...	800	"	A. F., 2,032 A. fen ...	4,182
"	Londonthorpe	680	"	West Rasen	1,240
"	Osmournby, Newton and		"	Salesby with Thores-	
"	Scott Willoughby ...	1,600	"	thorpe... ..	680
"	Owmby	580	"	Castle Bytham	2,500
"	Ropsley and Little		"	Horncastle	1,000
"	Hamby	4,000	"	Lincoln	1,500
"	Scartho	1,200	"	Stowe, Sturton and	
"	Swarby	1,000	"	Bransly	2,000
1796	Caistor	390	1804	Carlby and Aunby ...	*1,220
"	Hibaldstowe	3,800	"	Great and Little Gonerby	
"	Luddington and Gar-		"	and Manthorpe	4,000
"	thorpe	1,200	"	Hogsthorpe and Mumby	
"	Scredington	2,800	"	cum Chapel	2,590
"	North and South Stoke	1,200	"	Skellingthorpe	2,000
"	Tattershall, Thorpe and		1805	Anderby	730
"	Kirkby super Bane ...				
	Carried forward ..	317,224		Carried forward ...	35,978

LINCOLN—continued.

Date.	Enclosure.	Area enclosed.
	Brought forward ...	35,978
1805	Colsterworth ...	3,500
"	Mareham on the Hill ...	656
"	Mauten ...	
"	Swallow ...	2,550
1806	Easton ...	1,000
"	East Kirkby ...	375
"	Market Deeping and Deeping St. James ...	2,000
1807	Crosby ...	
"	Ashby de la Laund ...	1,500
"	Waith ...	
"	Yarburgh ...	900
1808	Scotter ...	4,500
1809	Croxton ...	1,300
"	Friskeneay ...	
1810	Boston (with old enclosures) ...	1,338
"	Fishtoft, 2,795 A. F., and old enclosure, 95 A. P. ...	2,890
"	Sibsey ...	
"	Withcall ...	2,700
"	Leverton, 410 A. F. and M., 135 A. P. ...	545
"	Leake ...	
1811	Ashby juxta Partney ...	500
"	Cabourne ...	2,700
"	Little Ponton (with old enclosures) ...	1,980
"	Thrusthorpe and Hannah cum Hagnaby ...	540
1813	Crowle ...	
"	Haburgh ...	2,500
"	North Kelsey ...	3,000
"	Witham on the Hill ...	2,400
1814	Thorseway ...	2,600
1815	Benington ...	
	Carried forward ...	77,952

Date.	Enclosure.	Area enclosed.
	Brought forward	... 77,952
1815	Grasby	500
"	Manby	500
1817	Fulstrow... ..	1,900
1818	Skirbeck	...
"	Welsthorpe	800
"	Ulceby with Fothering- ton	1,026
1819	Alvingham	1,300
"	Cumberworth	580
"	Firsby	...
1824	Ulceby	3,500
1825	Appleby	950
1826	Farlesthorne	390
1827	Great Grimsby	1,000
1842	Clee	...
		90,398

*Enclosed under the General Inclosure
Act, 1845.*

Date of Act.	Date of Award.	Parish.	Area.
1855	1858	North Cotes ...	520

LINCOLN AND RUTLAND.

1871	1875	Stamford and Tin-	
		well, total area	
		1,621 A., in Lin-	
		coln	811
			1,331

	Acres.
Before 1802 ...	354,048
1802-1845 ...	90,398
After 1845 ...	1,331

MIDDLESEX.

Date.	Enclosure.	Area enclosed.
1774	Laleham ...	...
1780	Ickenham ...	...
1789	Stanwell ...	3,000
1795	Hillingdon and Cowley, 3 F's. ...	...
1799	Teddington ...	883
1800	Edmonton ...	1,231
	Carried forward ...	5,114

Date.	Enclosure.	Area enclosed.
	Brought forward ...	5,114
1800	Hanworth, Feltham and Sunbury, 1,500 A. F., 1,700 A. P.	3,200
1801	Enfield	3,540
		11,854

MIDDLESEX—*continued.*

Date.	Enclosure.	Area enclosed.
1803	Harrow	...
1804	Ruislip	...
1805	Harmendsworth ...	1,100
1809	Echelford or Ashford ...	1,200
"	Hayes	2,000
1811	Hampton	...
1812	Hillingdon	1,400
1813	Greenford	640
"	Hanwell	350
"	Great Stanmore, all F.	216
"	East Bedfont	1,100
"	Isleworth, Heston and Twickenham ...	2,470
1815	Willesden	560
1818	Cranford	395
Carried forward		11,431

Date.	Enclosure.	Area enclosed.
	Brought forward ...	11,431
1819	Harlington	820
1824	West Drayton	...
1825	Northolt	...
		12,251

Enclosed under the General Enclosure Act, 1845.

Date of Act.	Date of Award.	Parish.	Area.
1848	1851	Littleton	625
			Acres.
Before 1802 ...			11,854
1802-1845 ...			12,251
After 1845 ...			625

MONMOUTH.

Date.	Enclosure.	Area enclosed.
1776	Ifton	780

Enclosed under the General Enclosure Act, 1845.

Date of Act.	Date of Award.	Parish.	Area.
1852	1854	Undy	128
"	"	Caldicot	243
Carried forward		...	471

Date of Act.	Date of Award.	Parish.	Area.
		Brought forward ...	471
1858	1859	Magor	142
			513

			Acres.
Before 1802 ...			780
After 1845 ...			513
			1,293

NORFOLK.

Date.	Enclosure.	Area enclosed.
1755	Brancaster	2,350
"	Swanton, Morley and Worthing ...	1,400
1760	Litcham	600
1762	Snettisham (half inclosures) ...	5,000
1766	Carlton Forehoe and Kimberley ...	...
1767	Sherborn	1,600
1769	Hilborowe, 2,600 In-fields and Outfields ...	3,020
1772	Fineham... ..	2,450
"	Roudham	...
Carried forward		16,420

Date.	Enclosure.	Area enclosed.
	Brought forward ...	16,420
1774	Beetley, Great Bittering and Grassenhall ...	1,130
"	Barton Bendish ...	4,370
"	Tottingham, 1,710 A. F., 1,300 A. P. ...	3,010
"	Weeting	4,450
1777	Little Cressingham, 300 A. F., 467 A. P. ...	767
"	Carlton Rode	3,000
1779	Dersingham	2,000
"	Grimston	4,000
1780	Foulden	3,000

Carried forward ... 42,147

NORFOLK—continued.

Date.	Enclosure.	Area enclosed.	Date.	Enclosure.	Area enclosed.
	Brought forward ...	42,147		Brought forward ...	70,504
1780	Heatcham ...	4,000	1801	Mattishall ...	1,100
"	Salthouse and Kelling ...	1,490	"	Thorpe Abbots... ..	
"	Tottenham and West Briggs... ..	1,400	"	Walton and Carbrooke... ..	
1781	Great Ringstead ...	3,000	"	Burgh and Billockby ...	
1785	Ashill, 900 A. F., 1,000 A. P.	1,900	"	Downham Market, Wimbocbam and Bexwell... ..	
1786	Tichwell ...		"	Hickling ...	
1793	Marham ...	3,700	"	Potter Higham ...	300
"	Stiffkey and Morston ...		"	South Walsham... ..	
1794	Little Dunham, 1,300 A. F., 400 A. P. ...	1,700			<u>71,904</u>
"	Shouldham and Garboise Thorpe	5,570			
"	Thornham ...		1802	Ellingham, Broome, Kirby Cane and Geldestone	
1795	Bintry and Twyford ...		"	Filby ...	
"	Great Hockham ...		"	Gooderstone ...	3,000
"	East Lexham and Great Dunham		"	East Tuddenham ...	
"	Sedgeford ...		"	Catfield and Sutton ...	
1796	Northwold ...		"	Runham ...	
"	Reymerstone, Letton, Cranworth and South Barrow		1803	Aslacton ...	
"	Sherington ...		"	Whitwell and Hackford ...	225
1797	Acle ...		1804	Brigham ...	
"	Saham Toney ...		"	Crimplesham ...	2,000
1798	Hethersett ...		"	Sporle and Palgrave ...	
1799	North Ellingham ...		"	Thetford... ..	
"	Hovingham and Marsham, 297 A. F., 1,400 A. P.	1,697	"	Waborne... ..	
"	Keninghall ...		1805	Brunstead ...	
"	Ransworth ...		"	Briningham, Stody and Brinton	
"	Shropham ...		"	Great and Little Framsham and North Pickenham... ..	4,000
"	Upton and Fishley ...		"	West Newton ...	
1800	Cawston ...		"	Palling ...	
"	Forsford, Horsham and Newton St. Faith's ...		"	Scoulton... ..	
"	Ovington ...		"	Winterton, East and West Somerton ...	
"	Ludham ...		"	Methwold ...	7,375
1801	Alburgh and Wortwell... ..		1806	Hackford ...	850
"	Blofield and Hemblington		"	Weasenham and Wellingham	
"	Boughton ...		"	Griston ...	
"	Great and Little Cressingham		"	Moundford ...	1,000
"	East Harling ...		"	Little Snoring ...	
"	Happisburgh and Lessingham		"	Sparham and Billingford Wymondham	
"	Holme Hale and West Bradenham	3,900	"	Wormegay ...	
			1807	Stalham ...	
			"	Martham ...	
	Carried forward ...	70,504		Carried forward ...	18,450

NORFOLK—*continued.*

Date.	Enclosure.	Area enclosed.	Date.	Enclosure.	Area enclosed.
	Brought forward ...	18,450		Brought forward ...	19,950
1807	Repps with Bastwick and Eccles near the Sea ...		1811	Scarning, Hoe, Worthing and Dillington ...	
"	Holt and Letheringsett Pentney ...		1812	Earsham, Ditchingham and Edenham ...	
1808	Cley next the Sea ...		"	Honingham ...	160
"	Claxton and Rockland... Fulmodeston, Stibbard and Ryburgh... ..		"	Witton Bacton, Edington and Paston ...	
"	Neatishead ...		"	Attleburgh ...	
"	Twetshall ...		"	Congham c. Brandon Parva or Little Brand	
"	North Walsham and Felmingham ...		"	Caston ...	
"	Bawdswell and Ling ...		"	Deopham ...	
"	Bodham ...		"	Hempstead ...	
"	Gaywood and Mintlyn... Wicklewood ...	1,500	"	Horsey ...	
"	Walsingham and Houghton next Walsingham		"	Rockland ...	
1809	Barton Turf ...		"	Mysingset Stanfield and Horningtoft ...	
"	Bunwell ...		"	Barford ...	
"	North Creake ...		1813	Croxton ...	
"	Fornett ...		"	Morley ...	
"	Sherringham ...		"	Seething, Kirkstead, Mundham and Sisland ...	
"	Strumpshaw and Surlingham ...		"	Tasburgh ...	
"	Swanton, Abbot, Lamas and Buxton ...		"	Wrampingham... ..	
"	Thurlton, Haddiscoe and Thorpenext Haddiscoe		"	Woodton... ..	90
1810	Gayton ...		"	Feltwell ...	
"	Hemsby ...		"	Geist ...	
"	Hardley and Langley ...		"	Hardingham ...	
"	Thuxton ...		"	Rollesby ...	
"	Great Plumstead and Postwick ...		"	Stow Bedon ...	
"	Thorne ...		1814	Suldey ...	200
"	Yaxham, Westfield, Whinbergh and Garvestone ...		"	Skeyton, Burgh next Aylesham and Tottington ...	
1811	Bathley ...		"	Wendling ...	
"	Drayton, Banburgh and Hellesden ...		"	East Bradenham ...	
"	Gressenthall and Great Bittering ...		"	Foxley ...	
"	Mattishall Bergh ...		"	Hockwold cum Wilton...	
"	Great Snoring ...		"	Middleton ...	
"	Welborne ...		1815	Hindringham ...	
"	Barnham Broome and Bickerstone ...		"	Langham ...	
"	Fundenhall and Ashwelthorpe... ..		"	Necton ...	
			"	South Runcton and Holme... ..	
			"	Smallburgh ...	
			"	Stoke, Wretton, Wereham and Winnold ...	
			"	Thompson ...	
			1816	Larling ...	
			1817	Hempnall ...	
			1818	Great Melton ...	
	Carried forward ...	19,950		Carried forward ...	20,400

NORFOLK—continued.

Date.	Enclosure.	Area enclosed.
	Brought forward ...	20,400
1818	East Rudham, West Rainton and Helhoughton ...	
1820	Blo' Norton ...	
"	Blakeney, Wiverton and Glandford ...	
"	Holme next the Sea ...	
"	Tibenham and Moulton ...	
1821	Little Barningham and Calthorpe ...	*60
1825	Hockering and Morton Weston ...	400
1827	Thursford and Kettlestone ...	
1828	Belaugh, Scottow, Little Hautbois and Hoveton St. Peter ...	
1829	North Elmham... ..	
"	Gunthorpe ...	90
"	Sculthorpe ...	
1836	West Runeton ...	
1837	Ashby and Hellington...	
1839	West Beckham and Alby Garboldisham, 226 A. F., 10 A. M., 680 A. P. ...	916
1840	Freethorpe, Limpenhoe and Reedham ...	100
	Carried forward ...	21,966

Date.	Enclosure.	Area enclosed.
	Brought forward	21,966
1841	Bodingham	...
"	Elsing	...
1842	Ormesby and Scratby	...
		21,966

Enclosed under the General Enclosure Act, 1845.

Date of Act.	Date of Award.	Parish.	Area.
* 1851	1851	Feltwell	860
1849	1852	Brandiston, Haver- land and Swan- nington... ..	490
* 1854	1854	Heacham	213
1857	1860	Cossey	810
1859	1863	Docking	4,640
1863	1869	Swaffham... ..	5,160
			12,173

	Acres.
Before 1802 ...	71,904
1802-1845 ...	21,966
After 1845 ...	12,173

NORTHAMPTON.

Date.	Enclosure.	Area enclosed.
1727	Grafton, 4 common fields 272 A., 1 common ...	318
1733	Chipping Warden, 63½ yl.	1,964
1743	Great Brixton ...	4,000
1745	Faxton, 23½ yl. ...	1,170
1749	Wakerley and Wittering	
1750	Nether Hoyford, Stow with Nine Churches and Bingbrooke, 39 yl. F. ...	*1,365
1751	Farthingstone, 47½ yl. ...	*1,662
1752	Drayton, 42½ yl. ...	*1,487
1753	Hinton, 30 yl. ...	*1,050
1754	Welton, 72 yl. ...	*2,520
1755	Norton by Daventry, 25½ yl. ...	*901
1756	Boughton and Pitford, 85½ yl. ...	*2,993
	Carried forward ...	19,430

Date.	Enclosure.	Area enclosed.
	Brought forward ...	19,430
1758	Upper and Lower Bod- dington ...	3,000
"	Helmdon, 70 yl....	1,550
"	Woodford, 30½ yl.	*1,067
1759	Ecton, 103 yl. ...	*3,605
"	Slapton, 38 yl. ...	*1,330
1760	Blakesley, 64 yl.	2,000
"	West Farndon, 20 yl. ...	*700
"	Marston St. Lawrence, 48 yl. ...	*1,680
"	Sulgrave, 71 yl....	*2,485
1761	Eydon, 28 yl. ...	*980
"	Morton Pinkney, 42 yl. F., 1,200 A. P. ...	*2,460
"	Wappenham, 52 yl.	*1,820
1762	Towcester Wood, Bur- cott and Caldecott ...	2,000
	Carried forward ...	44,107

NORTHAMPTON—continued.

Date.	Enclosure.	Area enclosed.	Date.	Enclosure.	Area enclosed.
	Brought forward	44,107		Brought forward	112,028
1763	Woodford	2,000	1774	Duddington	800
1764	Everdon, 43½ yl.	1,930	"	Harringtonworth	1,600
"	Guilsborough, Coton and Nortoft 20½ yl.	1,337	"	Hellidon	1,500
"	West Hadden, 48 yl.	*1,680	"	Hollowell	425
"	Ledgers Ashby, 32½ yl.	*1,146	"	Staverton	2,400
"	Newnham, 48½ yl.	1,580	"	Warmington	3,000
"	Warksworth, 55½ yl.	1,700	1775	Braunston	2,300
1765	Long Buckby	3,800	"	Cranford, 22½ yl.	*787
"	Denford	1,450	"	Pottersbury and Cosgrave	
"	Hardingstone and Cotton, 79½ yl.	*2,783	"	Scaidwell	1,000
"	Spratton	2,200	1776	Clipston and Newbold, 84 yl.	2,900
"	Syresham, 61 yl.	*2,135	"	Crick	3,000
"	Twywell	1,000	"	Dustin	1,500
"	Wellingborough, 80 yl. F.	4,000	"	Desborough	1,890
1766	Great Doddington, 56 yl.	*1,960	"	Walgrave	1,850
"	Hinton in the Hedges, all F.	1,330	"	Weedon Beck	1,700
"	Harleston, 28½ yl.	*1,000	"	Yelvertoft	2,000
"	Kingsthorp	1,743	"	Yardley Hastings	1,630
"	Thenford or Fenford, 33 yl.	750	1777	Grafton Underwood	1,229
1767	Arthingworth	1,400	"	Holcot	1,300
"	Cosgrave, 1700 A. F., 130 A. P.	1,830	"	Killesby, 36½ yl.	2,200
"	Old or Would, 49 yl.	2,000	"	Mears Ashby	1,400
"	Great Oxendon	1,300	"	Thorpe Malsor	600
1769	Knuston		"	Tansor	1,300
"	Middleton Cheney, upper and lower, 41 yl.	*1,435	"	Welford	1,800
1770	Denton	700	"	Whitton, Norton and Brockhall	1,060
1771	Earl's Barton	2,400	"	Nassington, Yarwell, Apethorpe and Woodnewton	3,800
"	Lowick	1,150	1778	Bulwick	1,400
"	Pattishall, Eastcote, Astcote and Darlescote	2,500	"	Titchmarsh	3,000
"	Slipton	560	"	Great Billing, 48½ yl.	*1,697
"	Weedon or Weston, 58½ yl. F., 1600 A. P.	*3,647	"	Braybrooke	1,500
"	Watford and Murcott	1,250	"	Barby	2,200
1772	Astrop, 77 yl.	*2,695	"	Byfield and Westrup	2,500
"	Aldwinckle	2,000	"	Floore	1,800
"	Charlton, 59 yl.	1,000	"	Harpole	1,800
"	Denshager	900	"	Isham	1,400
"	Moulton	2,600	"	Maidford, 28 yl.	700
"	Thorpe Achurch	1,500	"	Northampton Fields	840
1773	East Hadden	1,530	"	Rushden	3,500
"	Irchester, Wellingborough and Great Doddington		"	Wooton, 50 yl.	1,800
			1779	Bugbrooke	1,500
			"	Badby	1,500
			"	Little Bowden, 51 yl.	1,350
			"	Evenly	1,200
			"	Kislingbury, 80½ yl.	1,708
			"	Milton, Malsor and Collingtree, 70½ yl.	2,000
			"	Woodend	600
	Carried forward	112,028		Carried forward	190,994

NORTHAMPTON—continued.

Date.	Enclosure.	Area enclosed.	Date.	Enclosure.	Area enclosed.
	Brought forward	.. 190,994		Brought forward	... 17,847
1780	Brixworth, 102½ yl. ...	2,700	1805	Thingden or Finedon ...	3,000
"	East Farndon, 45 yl. ...	1,400	1806	Ashley ...	1,200
"	Tiffield ...	1,100	1807	Oundle and Ashton ...	2,600
"	Grendon ...	1,600	"	Croughton, 54 yl. ...	*1,890
"	Thrapstone ...	1,060	"	Warkton, Little Oakley and Luddingham ...	2,418
1781	Little Harrowden, 48½ yl. ...	1,500	"	Weekly and Geddington	2,160
1782	Great and Little Crexton, 28½ yl. ...	1,200	1808	Blisworth ...	1,500
"	Piddington and Hackleton ...	1,500	"	Irthlingborough ...	3,500
1786	Broughton ...	...	"	Orlbury ...	1,300
1788	Wollaston, 89 yl. ...	2,760	1809	Longthorpe (with old enclosures) ...	1,240
1790	Polebrooke ...	1,400	"	Rothersthorpe ...	1,200
1792	Aynho, 45 yl. ...	*1,575	"	King's Cliffe ...	1,100
"	Great and Little Weldon	2,400	"	Maxey with Deepingate, Northborough, Glington w. Peakirk Elton and Kelpstone ...	...
1793	Orston and Thorston ...	2,200	1811	St. John Peterborough...	...
"	Wadenhoe ...	675	1812	Cold Higham w. Grims-cote and Potcote ...	1,150
1794	Lampert and Hanging Houghton ...	539	"	Rothwell (with old enclosures) ...	3,200
1795	St. Martin Stamford Baron... ..	600	1813	Calterstock cum Glapthorn ...	1,500
"	Ravensthorpe ...	1,400	"	Marston Trussell (with old enclosures) ...	1,200
1796	Ufford with Ashton and Bainton ...	2,700	1814	Quinton ...	504
"	Whitfield ...	...	1815	Cottingham cum Middleton ...	1,750
1797	Raunds ...	4,700	1817	Easton on the Hill ...	3,000
"	Whittlebury ...	670	1819	Aldrington ...	680
1798	Bozeat ...	2,268	"	Paulerspury with Heath-encote ...	2,500
"	Wilbarston, 60 yl. ...	1,200	1820	Eye ...	800
1799	Queen's Norton and Duncott ...	1,400	"	Naseby ...	*2,000
"	Grasthorpe ...	350	1823	Abthorpe ...	280
1800	Barnack with Pilsgate... ..	2,500	1827	Little Houghton, Brafield in the Green and Cocknoe ...	2,500
"	Islip ...	1,300	1829	Brackley... ..	1,318
"	Newton Bromshold ...	820	"	Corby ...	1,035
1801	Chelston cum Caldecott	1,700	1830	Little Addington ...	1,160
"	Wilby, 29 yl. ...	1,000	1834	Stanwick ...	1,275
		<u>237,211</u>	1838	Higham Ferrers... ..	...
			1839	Ringstead ...	...
1802	Daventry ...	1,600	1840	Stoke Bruern and Shut-lehanger ...	...
"	Hargrave ...	1,350	1841	Barnack w. Pilsgate and Southorpe ...	...
"	Hannington ...	800	"	Collyweston ...	...
"	Weston by Welland and Sutton Bassett, 70 yl. ...	*2,450			
1803	Great Addington ...	1,100			
"	Braddon ...	700			
"	Burton Latimer... ..	3,000			
"	Werrington and Walton	2,450			
1804	Kettering ...	2,300			
"	King's Sutton ...	1,200			
1805	Cranford St. John ...	897			
					<u>66,807</u>
	Carried forward	... 17,847			

NORTHAMPTON—*continued.*

<i>Enclosed under the General Enclosure Act, 1845.</i>				Date of Act.	Date of Award.	Parish.	Area.
Date of Act.	Date of Award.	Parish.	Area.	1901	—	Brought forward ...	4,254
						Sutton ...	450
1864	1867	Lutton ...	754				<u>4,704</u>
1895	1898	Castor and Ailes- worth ...	3,500			Acres. Before 1802 ...	237,211
						1802-1845 ...	66,807
		Carried forward ...	4,254			After 1845 ...	4,704

NORTHUMBERLAND.

Date.	Enclosure.	Area enclosed.	Date.	Enclosure.	Area enclosed.
1740	Gunnerton, Ingrounds			Brought forward ...	3,040
	1,300 A., Out 1,000 A.	2,300	1809	Simonburn, 300 A. F.,	
1757	West Matfen, 1,250 A. F.,			5,000 A. P. ...	5,300
	50 A. P. ...	1,300	1812	Ovingham ...	2,951
1776	Corbridge ...	5,300	1844	Haltwhistle Common,	
1784	Elrington ...	757		1,360 A., also certain	
		<u>9,657</u>		lands called Rig or	
				Dale lands ...	1,400
					<u>12,691</u>
1804	Simonburn, 40 A.F. and			Acres. Before 1802 ...	9,657
	M., 3,000 A. P. ...	3,040		1802-1845 ...	12,691
	Carried forward ...	3,040			

NOTTINGHAM.

Date.	Enclosure.	Area enclosed.	Date.	Enclosure.	Area enclosed.
1759	Barton and Clifton ...	1,500		Brought forward ...	24,402
"	Everton, 1,300 A. P. ...	*2,000	1768	Epperstone ...	1,000
"	Staunton... ..		"	Rempstone (Rampton)...	1,230
1760	Costock or Cortlingstoke	710	1769	Blidworth, 200 A. F.,	
"	Broughton Sulney ...	2,000		3,300 A. P. ...	3,500
"	Coddington ...	1,780	"	Hucknal Torkard ...	1,200
"	Clifton ...		1770	Mattersey ...	2,300
"	Hawksworth ...		"	Normanton upon Soar ...	1,100
"	Hayton ...	1,260	1771	North Muskham Holme	
"	Nusson, 900 A. F., 860			and Bathley ...	3,000
	A. M., 2,000 A. P. ...	3,760	"	Misterton ...	500
1765	Carlton upon Trent ...		"	Stapleford and Brancote	1,100
"	Lowdham ...	2,500	1772	Laneham... ..	
"	Wilford ...	1,100	1773	Cromwell ...	
1766	Balderton ...		1774	Finningley ...	7,000
1767	Carlton in Lindrick ...	2,492	"	West Redford ...	900
"	Farndon ...		"	Sutton St. Ann's, 50½ yl.	1,200
"	Lenton and Radford ..	1,000	1775	Flintham ...	
"	Ruddington ...	2,700	"	Hickling, 2,100 A. F.,	
1768	Burton Joyce and Bul- coate ...	1,600		800 A. P. ...	2,900
			"	Normanton and Southwell	
	Carried forward ...	24,402		Carried forward ...	51,332

NOTTINGHAM—*continued.*

Date.	Enclosure.	Area enclosed.	Date.	Enclosure.	Area enclosed.
	Brought forward	51,332		Brought forward	110,220
1775	Scrooby ...	1,350	1800	Normanton upon Trent	750
"	Sutton cum Lound ...	4,000	"	Ordsall, 200 A. F., 210	
1776	Beckingham ...	2,000	"	A. M. & P. ...	410
"	Clareborough and Wel-		"	Wysall ...	1,100
"	ham ...	1,180	"	Newark upon Trent ...	400
"	Sutton Bonnington, 32½ yl.	800			
"	Screveton, one F. ...	350			112,880
1777	Bleasby ...		1802	Blyth and Harworth ...	
"	Farnsfield ...		"	Cropwell... ..	1,500
"	Halam and Edingley ...		"	Runskill and Scrooby ...	1,300
"	Winthorpe ...	5,000	"	Walkeringham ...	
1778	Kersall ...	800	1803	Dunham and Ragnal, 900	
1779	Calverton ...		"	A. F., 200 A. M., 330 A. P.	1,430
1780	Scarrington and Oslacton		"	Sutton upon Trent ...	1,800
1787	Cropwell Butler and		"	Tollerton... ..	440
"	Cropwell Bishop ...		1804	Alverton ...	400
"	Ratcliffe upon Trent ...	1,500	"	Gotham ...	1,800
"	Trowell, 72 oxgangs, 680		1805	Plumtree ...	1,770
"	A. F., 252 A. P. ...	1,012	1806	Beeston ...	840
1789	Arnould ...	2,500	1807	Barnby ...	
"	Whatton ...	1,700	"	Elton ...	900
1790	North Collingham, 740		1808	Gamston ...	520
"	A. F., 674 A. M., 160		"	West Markham ...	
"	A. P. ...	1,574	"	Strelley and Bilborough	400
"	Cotgrave ...	2,365	1809	Eaton ...	796
"	Clayworth ...	2,000	1810	East Markham ...	
1792	Basford, 160 A. F. and M.,		1814	Headon cum Upton ...	
"	1,200 A. P. ...	1,360	1818	Warsop, 344 A. F., 1,400	
"	Lambley, 60 A. F., 600		"	A. P., M. I. ...	*1,800
"	A. P. ...	660	1819	East Drayton ...	700
"	Syerston ...	500	1821	Nolesby, Kirton and	
"	Gedling, Stoke, Bardolph		"	Egmonton ...	
"	and Carlton ...	*4,300	1822	Sturton and Little-	
1793	Granby and Sutton ...		"	borough, 455 A. P. ...	*900
"	Willoughby on the		1826	Norwell, M. I. ...	1,300
"	Wolds ...	1,700			
1795	Caunton ...	823			18,596
"	North Leverton and				
"	Habblesthorpe ...	1,400			
"	South Leverton ...	1,600			
"	East Stoke and Elston...	2,500			
"	Upton ...	1,384			
"	Woodborough ...	1,000			
1796	Gateford and Shireoaks				
"	Gringley on the Hill ...	3,000			
"	Snenton (? Shelton) ...	800			
"	Weston ...	1,230			
1797	Bunny ...	1,000			
1798	Keyworth ...	1,500			
"	Great Leke ...	3,000			
1799	Harworth ...	1,300			
"	Tuxford ...	1,700			
	Carried forward	110,220			

Enclosed under the General Enclosure Act, 1845.

Date of Act.	Date of Award.	Parish.	Area.
*	1851	Girton (South Searle P.)	584
1849	1852	Oxton ...	1,140
1849	1854	Mansfield Woodhouse ...	1,545
			3,269
			Acres.
	Before 1802	...	112,880
	1802-1845	...	18,596
	After 1845	...	3,269

OXFORD.

Date.	Enclosure.	Area enclosed.	Date.	Enclosure.	Area enclosed.
1730	Mixbury	2,400		Brought forward ...	68,542
1757	Burchester	1,200	1777	Great and Little Bourton, one F.	1,500
"	Piddington, 22 yl. F., 400 A. P.	*1,060	"	Stanton St. John, 50 yl.	*1,750
1758	Northleigh, 52 yl. F., 600 P.	*2,160	1779	Bucknell... ..	800
1759	Neithrop and Wickham, 60½ yl.... ..	*2,109	"	Dean	
1761	Ferrington, 32½ yl. ...	980	"	Idbury	1,072
"	Wardington, Williams- cott and Coton, 108 yl.	3,000	1780	Stratton Audley and Caversfield, 37½ yl. ...	2,200
1763	Merton, F. only... ..	740	1783	Hanwell	*2,000
1765	Horley and Horton, 104 yl.	2,000	1787	Coggs	
"	Somerton, 48½ yl. ...	1,800	"	Goring	
"	Shutford... ..	900	"	Sarsden, Churchill, Lyne- ham, Merriscourt and Finescourt	4,140
1766	Adderbury, 156½ yl. ...	*5,477	1788	Little Faringdon	
"	Bladon, 16 yl.	*560	1789	Sibford Ferris, 41 yl. ...	950
"	Steeple Aston, 41 yl. ...	1,435	1791	Oddington	
"	Great Tew, 79 yl.	*2,765	1792	South Leigh	
1767	Chesterton, 62 yl.	*2,170	1793	Little Barford	
"	Kencott, 731 A. F., 232 A. P.	963	"	Burchester King's End Dunstew... ..	1,200
"	Sandford, 63½ yl.	*2,227	"	Milcomb, 1 F., 56½ yl. ...	1,695
1768	Shipton upon Charwell	1,100	"	Stoke Lyne and Fewcott Little Tew, all F., 40½ yl.	*1,215
1769	Chipping Norton and Salford, 185½ yl.	*6,572	1794	Burford	
"	Wootton, 40 yl.	*1,400	"	Southnewington	
1770	Balckbourton, 41½ yl. ...	*1,452	1795	Westcot Barton and Middle Barton, 84 yl. ...	*2,940
"	Westwell, 39 yl. F., 400 A. P.	1,300	"	Wigginton, 37½ yl.	*1,312
1771	Swalcliffe	1,000	1796	Alvescott... ..	
1772	Epwell, 27 yl.	1,400	"	Hampton Poyle... ..	
"	Handborough, 51 yl. ...	*1,785	1797	Mollington, 40½ yl. ...	1,150
"	Heath, 39½ yl.	800	1798	Kelmscott	
1773	Burford	800	1799	Bloxham... ..	
"	Hook Norton and South- top, 112½ yl.	5,000	"	Cassington and Worton Ensham	1,000
"	Broad Sibford or South Gower and Burdrup... ..	2,000	"	Wendlebury	1,160
"	Stanton Harcourt		"	Whitchurch	
1774	Copredy	1,550	1801	Drayton... ..	270
1775	Burcott (Dorchester P.)... 32½ yl.... ..	*1,137	"	Lower Heyford and Cal- cot	1,700
"	Broadwell and Filkins ...		"	Headington	
"	Brize Norton		"	Stonesfield	
"	Great Rolewright, 70 yl. ...	*2,450			
"	Upper and Lower Tad- marten, 81 yl. (one field)	2,000			
1776	Alkeston, 1 F., 38 yl. ...	1,000	1802	Baldwin Brightwell	977
"	Blackthorn, 39½ yl. ...	1,850	"	Swerford... ..	1,200
			"	Spelsbury	
	Carried forward ...	68,542		Carried forward ...	2,177

OXFORD—continued.

			Enclosed under the General Enclosure Act, 1845.			
Date.	Enclosure.	Area enclosed.	Date of Act.	Date of Award.	Parish.	Area.
	Brought forward	2,177				
1803	Broughton	600				
"	Wroxton and Balscot		1846	1849	Milton (Shipton under Wychwood P.)	1,960
1804	Islip					
"	Shuttington	660				
1805	Shirburn, 920 A. F., 261 A. P.	1,181	*	1849	Fencot and Murcot (Charlton upon Otmoor P.)	1,005
1807	Fritwell	1,900				
"	Deddington and Great Barford		1849	1852	Pyrton	640
1808	Watlington		1850	1852	Shipton under Wychwood	1,710
1809	Wheatley, 60 A. P.	*100	1848	1853	Warborough	1,520
1810	Launton		1849	1853	Standlake, Bright-hampton and Hardwicke	2,860
"	Culham	1,160				
"	Kidlington		1849	1853	Cowley	1,000
"	Lewknow and Portcomb		1850	1853	Southstoke cum Woodcote	1,765
"	Newington	636	1848	1854	Chinnor	1,000
1811	East and West Chadlington and Chilson	3,800	"	"	Cottisford and Hethe	1,210
"	Garsington		1854	1856	South Weston	470
"	Kirtlington		*	1858	Charlton Field (Charlton upon Otmoor)	595
1812	Bampton...		1855	1858	Horsepath...	900
1813	Swinbrooke	800	1859	1861	Drayton	900
1814	Ambrosden		"	"	Dorchester	1,000
1817	Fulbrook...	1,500	"	1862	Ramsden	488
"	Iffley	800	1852	1863	Bensington, Berwick Salome, and part of Ewelme	2,450
1818	Noke		1860	1864	Cheekendon	590
1820	Great Haseley	500				
1821	Taynton	1,800				
"	Witney	500				
1823	Thame and Sydenham...					
1827	Beckley					
1829	St. Giles, Oxford					
1831	Woolvercot	550				
1832	Aston Rowant					
"	Caversham	600				
1836	Baldon (Marsh and Toot)					
1838	Curbridge	1,500				
1840	Great Milton	1,300				
1841	Upper Heyford					
1842	Britwell					
1843	Grafton					
"	Chalgrove					
		22,064				
BERKSHIRE AND OXFORD.						
See above. 2 Acts, for Oxford						
			1515 A.			1,515
						23,578
						Acres.
Before 1802						96,596
1802-1845						22,064
After 1845						23,578

BERKSHIRE AND OXFORD.

See above. 2 Acts, for Oxford			
1515 A.	...	...	1,515
			23,578
			Acres.
Before 1802	...	96,596	
1802-1845	...	22,064	
After 1845	...	23,578	

RUTLAND.

Date.	Enclosure.	Area enclosed.	Date.	Enclosure.	Area enclosed.
1756	Egletton or Edgeton, F...	844		Brought forward ...	3,057
"	Tinwell ...	1,013	1759	Thistleton ...	1,380
1758	Edith Weston, 32 yl. ...	1,200	1762	Whissondine ...	
Carried forward ...		3,057	Carried forward ...		4,437

SOMERSET—continued.

Date.	Enclosure.	Area enclosed.	Date.	Enclosure.	Area enclosed.
	Brought forward ...	6,690		Brought forward ...	4,678
1797	Higham and Huish Episcopi, 1,000 A. F., 840		1811	Cheddar, Priddy and Rodney Stoke ...	1,100
	A. P. ...	1,840	1812	Charlton Horethorne ...	313
"	Huish Episcopi, 1,100		"	Milborne Port ...	800
	A. F., 220 A. P. ...	1,320	1813	Long Ashton, 690 A. P. ...	*1,000
"	Moorlinch, 430 A. F.,		"	Uphill, 40 A. F., 340	
	175 A. P. ...	605	"	A. P. ...	380
"	Othery, 550 A. F., 600 A. P.	1,150	"	Wraxall, Nailsea and Burton, 1,617 A. P. ...	*2,000
"	Somerton and Compton Dundon ...		1814	Berkeley and Standwick ...	300
1798	Chilton ...	620	"	Moorlinch ...	350
"	Catcott, 350 A. F., 550		"	Portishead ...	
	A. P. ...	900	1818	Martock ...	278
"	Caddington ...	2,000	1819	Martock in Muchelney, 596 A. F., 426 A. M., 2 A. P. ...	1,024
"	Middlezoy ...	1,100	1826	Chilthorne Domer, 50 A. F., 130 A. P. ...	200
1800	Huntspill, Cannington, Stockland Bristol and Stogursey ...		"	West Lyndford ...	400
		16,225	1830	Kingsbury Episcopi, 300 A. F., 400 A. P. ...	700
1802	Pitney, 600 A. F., 300		"	Weston Zoyland and Middlezoy, all F. ...	500
	A. P. ...	900	1836	South Petherton, all F. ...	600
1803	North Perrott ...	220	1837	Clapton ...	
"	Lilstock ...	210			14,623
1804	Kings ...	260			
"	Keinton Mandefield ...				
"	Alford ...	250			
1806	Martock ...	1,025			
1809	Congresbury, Week St. Laurence and Puxton ...	820			
"	Long Sutton ...				
1810	Weston super Mare ...	993			
	Carried forward ...	4,678			

STAFFORD.

Date.	Enclosure.	Area enclosed.	Date.	Enclosure.	Area enclosed.
	Brought forward ...			Brought forward ...	9,947
1765	Elford ...	1,500	1800	Stafford ...	470
1770	Comberford and Wigginton ...	3,000	"	Castlechurch ...	120
1773	Whitgreave ...	1,087	1801	West Bromwich... ..	387
1783	Allstonefield, 160 A. F., 300 A. P. ...	460			10,924
1792	Great and Little Saredon and Great Wyrley ...				
1794	Abbotts Bromley, 100 A. F., 900 A. P. ...	1,000	1806	Knightley, Mill Meece, Standon ...	400
1798	Stone, all F. ...	400	1807	Basford ...	359
1799	Pattingham and Patshall ...	2,500	1808	Checkley... ..	500
	Carried forward ...	9,947		Carried forward ...	1,259

301

*Enclosed under the General Enclosure
Act, 1845.*

SURREY.

*Enclosed under the General Enclosure
Act, 1845.*

SUSSEX.

Date.	Enclosure.	Area enclosed.	Date.	Enclosure.	Area enclosed
1799	Houghton and South Stoke, 900 A. P.	... *1,400	1804	Brought forward	... 1,397
			1804	Tottington, all F.	... 163
			1805	Broadwater	... 779
1803	Lancing	... 730	1809	Angmering	... 234
"	Rustington, all F.	... 360	"	Chidham...	
1804	Goring	... 307	"	Warningcamp	
	Carried forward	... 1,397		Carried forward	... 2,573

SUSSEX—continued.

Date.	Enclosure.	Area enclosed.	
	Brought forward ...	2,573	
1810	Amberley ...	2,000	<i>Enclosed under the General Enclosure Act, 1845.</i>
"	Tellescomb, 454 A. F., 236 A. P. ...	690	
1812	Poling, all F. ...	170	
"	West Thorney ...	960	
1813	Eartham ...	1,500	
"	Warminghurst, Ashington, and Chalkton ...		
1818	Westbourne ...	800	
1819	Chidham, Westbourne, and Warblington ...	320	
"	Selsey, 535 A. F., 134 A. P. ...	689	
1821	Bosham and Funtington, 300 A. F., 530 A. P. ...	830	
"	Tangmere ...	200	
1826	Felpham ...	400	
1830	Kingston near Lewes and Ilford ...	2,405	
1841	Bury ...		
		<u>13,537</u>	

Date of Act.	Date of Award.	Parish.	Area.
*	1849	Oving ...	178
1868	1871	Hunston ...	78
			<u>248</u>
			Acres.
	Before 1802	...	1,400
	1802-1845	...	13,537
	After 1845	...	248

WARWICK.

Date.	Enclosure.	Area enclosed.	Date.	Enclosure.	Area enclosed.
	Brought forward ...	25,715			
1726	Bobenhull ...	1,000	1757	Priors Hardwick, 22 yl.	*770
1730	Lillington ...		"	Prior's Marston, 72 yl...	3,800
"	Welsbourne Hastings ...		"	Wolfamecoat, 44 yl.	1,800
1731	Bishop's Tachbroke ...	688	1758	Geydon, 42 yl. ...	*1,470
"	Nuneaton and Attleborough, 76 yl. ...	*2,670	"	Wilcote, 4 F.'s...	
1732	Little Kinneton, 46½ yl.	*1617	1759	Honington, 39 yl.	*1,365
1733	Barston ...	400	"	Willoughby, 36 yl.	1,500
"	Westbourne Hastings and Newbold Pacy, 40 yl. ...	1,400	1760	Barford, 49½ yl...	*1,733
1739	Pailton, all F. ...	900	"	Southam, 50 yl...	2,200
1740	Stichall ...	600	1761	Exhall, 11 yl.	*365
1741	Brinklow ...	1,700	"	Pailton, 28½ yl. ...	*1,008
1742	Aston Cantlow, 116½ yl.	4,067	"	Ryton ...	
1744	Wolfamecoat ...	1,690	1762	Princethorpe, 14½ yl. F.	1,000
1753	Kilmorton, 16½ yl.	*569	1764	Atherstone, 24 yl.	650
1755	Churchover, 32 yl. ...	*1,120	"	Chilvers Coton ...	1,100
"	Great Harborow, 27 yl.	*945	1765	Bourton, 20 yl. ...	1,300
"	Kenilworth ...	1,100	"	Granburrow, 24½ yl.	*997
1756	Clifton upon Dunsmore, 20 yl. ...	*700	"	Snitterfield, 17½ yl.	*621
"	Radway, 36½ yl...	*1,277	1766	Bidford, 23½ yl...	*822
"	Sow ...	1,400	"	Haselor, 43 yl. ...	1,400
1757	Loxley, 18½ yl. ...	*647	"	Ruyton (Bulkington P.), 10 yl. ...	700
"	Morton Morrell, 35 yl...	*1,225	1767	Cubbington, 31 yl.	*1,085
			"	Wixford and Exhall, 69 yl. ...	*2,415
	Carried forward ...	25,715		Carried forward ...	53,816

APPENDIX B.

303

WARWICK—continued.

Date.	Enclosure.	Area enclosed.	Date.	Enclosure.	Area enclosed.
	Brought forward	53,816		Brought forward	106,208
1768	Lemington Priors	990	1795	Upper Easington and Fullready, 72 yl.	2,520
1769	Wiley, 13 yl.	455	"	Newton Regis and Clifton Campsville	600
"	Bedworth, 16½ yl.	500	"	Ratley	900
1770	Aulcester, 185 A. F., 450 A. P.	635	1796	Tysoe, 131 yl.	3,000
"	Bulkington	1,600	1797	Oxhill, 42 yl.	1,470
1771	Alveston, 56½ yl.	2,091	1799	Sherborne	1050
"	Butlers Marston, 32½ yl.	1,137	1801	Aston, 171 A. F. & M., 1,000 A. P.	1,171
"	Knightcot and Northend, 32½ yl.	1,147			<u>116,919</u>
"	Monk's Kirby, 18½ yl.	647	1802	Birbury and Marton	1,750
"	Polesworth, 24 yl.	840	"	Saltley and Washwood	300
"	Stretton on the Foss, 45 yl. F., 200 A. P.	1,550	"	Whatcote	
1772	Little Kington, Combrooke and Brookhampton, 19½ yl.	682	1803	Kinwarton	420
"	St. Nicholas	1,650	1805	Cherrington	
"	Shilton, 15½ yl.	547	"	Milverton	
1773	Rugby, 42 yl.	1,500	"	Whichford, Ascott and Sowerton	2,600
1774	Foleshill		"	Hampton in Arden	600
"	Halford, 34 yl.	1,190	1806	Polesworth and Grendon	450
"	Stratford upon Avon, 50 yl.	1,600	1807	Norton Lindsey	600
1775	Long Itchington and Bascote, 87 yl.	2,000	1811	Long Compton	2,300
"	Lea Marston and Dunton	770	1812	Grafton	
"	Wootton Wawen	1,900	1813	Solihull and Hampton in Arden	
1776	Barton and Martleeve, 30 yl.	1,050	1817	Leek, Wootton	1,000
"	Warmington, one F., 46 yl.	1,200	"	Stuiley	
1777	Weston under Wetheley		1818	Brickenhill, Little Packington and Diddington	
1778	Fenny Compton	2,200	1824	Sutton Coldfield	
"	Napton upon the Hill, 96 yl.	3,000	1825	Nether Whitacre	400
"	Shuckburgh Fields, 26 yl.	880	1826	Wolverton	470
1779	Aven Dassett	1,200	1831	Claverdon	60
"	Brinton and Drayton, 59 yl.	1,700			<u>10,950</u>
"	Colleshill, 900 A. F., 1,000 A. P.	1,900	<i>Enclosed under the General Enclosure Act, 1845.</i>		
"	Harbury, 120 yl.	3,600	Date of Act.	Date of Award.	Parish.
1781	Ilmington, 52 yl.	1,820	1847	1851	Whitnash
1783	Burton Hastings	600	1856	1860	Coventry
1784	Lower Brailes, 3,000 A. F., etc.	3,500	1867	1870	Crimscott and Whimpstone (Whitchurch P.)
1785	Meriden, 103 A. F., 286 A. P.	389			1,170
1786	Shottery, 38½ yl.	1,600			<u>3,235</u>
1791	Stockton	1,320			
1793	Shottiswell, 51 yl.	1,200			
1794	Lower Pillarton, 57½ yl.	1,802			
	Carried forward	106,208			

		Acres.
Before 1802	...	116,919
1802-1845	...	10,950
After 1845	...	3,235

WESTMORELAND.

Date.	Enclosure.	Area enclosed.	Date.	Enclosure.	Area enclosed.
1808	Bolton (certain open or common fields called Broad Ing Bartle and Star Ings, 22 A., waste 540 A.) ...	562	1811	Brought forward ...	1,952
1810	Soulby, 90 A. F., 1,300 A. P. ...	1,390	1819	Kirkby in Kendal, a common open field ...	105
				Barton, 130 A. F., 1,050 A. P. ...	1,180
	Carried forward ...	1,952			3,237

WILTSHIRE.

Date.	Enclosure.	Area enclosed.	Date.	Enclosure.	Area enclosed.
1726	Compton Bassett, 1 F. ...			Brought forward ...	17,936
1732	Staunton ...	800	1782	Stanton St. Quintin ...	
1741	Sherston Magna, all F. ...	1,000	1783	Heytesbury ...	5,700
1748	Badbury, 2 F.'s ...		"	Netherampton, Odstock, etc. ...	
1749	Broad Blumsden ...	*700	1785	Colerne Down, 1,305 A. F., 238 P. ...	1,543
1766	Heddington ...		"	Foffint, Swallow Clift, Ebesborne Wake, Broadchalk, Bowerchalk, Alvedeston, Bishopston and Fifield ...	
1767	Ashen Keynes, 70 A. F., 176 A. M., 490 A. P. ...	736	"	Berwick St. John ...	
1770	Endford ...	1,010	1788	Netherhaven ...	3,300
1772	Kemble and Pool ...	1,500	1789	Berwick St. James and Fisherton Anger ...	1,650
1774	Milton ...		"	Urchfont and Beechingstoke ...	
"	Titcombe, 450 A. F., 395 A. P. ...	845	1790	Great and Little Bedwin, Presbute ...	
1775	Southcott, Kepnell Down, Workdown and Pewsey ...		"	Deverill, Longbridge, Hussey and Monkton Deverill ...	
1776	Liddington and Medbourn, 639 A. F., 427 A. P. ...	1,066	1792	Avebury ...	
1777	Ashton Keynes ...		"	Knooke ...	
"	Earl Stoke ...	1,737	"	Ogbourne St. George ...	
"	Market Lavington ...		1793	Durnford ...	
1778	Ramsbury, Whitton, Eastridge and Baydon ...		"	Keevil, Idmaston, Fittleton and Chisenbury ...	
"	Coates ...		"	Roundway, Bedbow, Chiltote and Bishop's Cannings ...	
"	Highworth ...		1795	Poulton ...	
"	Ogbourn St. Andrews ...		"	Stratton St. Margaret ...	
"	Patney ...		"	Winterborne Earls and Allington ...	
1779	Chisledon, 1,230 A. F., 12 A. P. ...	1,242	"	Wroughton ...	
"	Milston and Brigmerston ...		1796	Wroughton and Uffcot ...	
"	Mildenhall ...	*800			
"	Wanborough ...				Carried forward .. 30,129
1780	Charlton ...				
"	Warminster and Corsley ...	4,000			
1781	Chicklade ...				
1782	Kingston Deverill ...	2,500			
	Carried forward ...	17,936			

WILTSHIRE—continued.

Date.	Enclosure.	Area enclosed.	Date.	Enclosure.	Area enclosed.
	Brought forward ...	30,129		Brought forward ...	22,103
1797	Allcannings and Allington		1810	Pitton and Farley ...	1,500
"	Great and Little Chiverhill		"	Winterbourn, Stoke, and Stapleford	
"	Easterton		1811	Bidderstone and Slaughtertford... ..	293
1798	Shrewton		"	Tileshead	
"	Sutton Veny		1812	Martin	350
"	Upton and Milton	820	"	Nettleton	981
1799	Oare		1813	Calne, Calstone, Wellington and Blackland	
"	Purton		"	Steeple Ashton	
"	Stratford under the Castle and Milford		"	Winterbourne Moncton	955
1800	Cherton		1814	Codford St. Peter	
"	Shalbourne		"	Broadchalk and Chilmarch	3,577
1801	Charlton... ..		"	Cricklade	
"	Manningford Bruce		"	Chirton	
"	Wilsford		"	Exford	
		30,949	"	Overton	
			"	Sutton Mandeville, A. F., 170 A. P.	545
1802	Coombe Bisset		1815	Bishop's Cannings	5,784
"	West Grinstead and White Parish... ..	3,350	"	Chitterne	1,500
"	Uphaven... ..	800	1816	Crudwell	
"	Wilsford		"	Downton and Britford... ..	
"	Westbury, 3,900 A. F., 1,200 A. P.	5,100	"	Everley	
1803	Upton Scudamore		"	Roads and Ashton	2,300
1805	Aldbourn		1818	Berwick St. Leonards	1,100
"	Exford, Fifield, Coombe, Longstreet and East Chisenbury		"	Damerham South	
"	Norton Bavant		"	Froxfield and Milton	
"	Somerford Keynes	500	"	Laverstock	1,211
1806	Great Somerford, A. F., 48 P.	948	1819	Durrington and Figheldeane	
1807	Mere	5,000	"	Malmesbury (St. Paul P.)	
1808	Bishopstrow and Warminster		"	Rodborne Cheney	
"	Codford St. Peter	600	1820	Cherhill, Calne, Calstone, Wellington and Compton Bassett	
1809	Bishopston		1821	Broad Hinton and Cliffe Pypard	*350
"	Chilton Foliat	400	1822	Dinton	
"	West Kington	950	1825	Wilton, Burcomb, Netherhampton, and Fugglestone	
"	Orcheston St. George and Elston, 400 A. F., 130 A. P.	530	1827	Ham	
"	Stockton... ..	1,500	1828	Boyton (with old enclosures)	2,300
"	Barford St. Martin, South Newton and Baverstock	2,425	1833	Steeple Langford	1,000
					45,849
	Carried forward ...	22,103			

WILTSHIRE—continued.

Enclosed under the General Enclosure Act, 1845.				Date of Act.	Date of Award.	Parish.	Area.
Date of Act.	Date of Award.	Parish.	Area.	Brought forward ...			2,407
1848	1851	Winterborne Dauntsey ...	440	1863	1866	Steeple Langford...	983
*	1853	Maddington ...	862	1865	1867	Donhead St. Mary	535
1852	"	Winterborne Gunner ...	551				<u>3,925</u>
"	1855	Maddington (Homananton Fields and Tenantry Down) ...	554				
Carried forward ...			2,407				
							Acres.
				Before 1802 ...			30,949
				1802-1845 ...			45,849
				After 1845 ...			3,925

WORCESTER.

Date.	Enclosure.	Area enclosed.	Date.	Enclosure.	Area enclosed.
1733	Aston Magna ...	...	Brought forward ...		26,533
1736	Aldminster, 1 great C. F., 2 C. pastures, several meadows ...	950	1779	Himbleton ...	2,000
1762	Holy Cross in Pershore...	950	"	Grafton Flyford ...	864
1763	Pirton ...	...	1781	Kington ...	1,000
1765	Bretfertton ...	...	1782	Church Bench, 20 yl.	*700
"	Emload, 28 yl. ...	980	1786	Harvington ...	*1,800
"	Linchwick and Norton...	...	1788	Fladbury ...	1,700
1771	Broadway, 90 yl. ...	*3,150	1790	Dormstone ...	...
"	Feckenham ...	220	1795	Bishampton, 67 yl.	*2,345
"	Hill Croome ...	...	"	Chattisley ...	...
"	Naunton Beauchamp, 13½ yl. ...	*472	"	Hanley Castle ...	...
1772	Blockley ...	2,300	1801	Ripple ...	...
"	Throckmorton ...	1,600			<u>36,942</u>
"	Nafford and Birlingham	*1,000	1802	Abbotts Morton ...	700
1774	Bricklehampton, 34 yl...	*1,190	"	Broughton ...	446
"	Defford, 600 A. F. ...	900	1803	Little Cemberton ...	...
"	Kidderminster ...	1,000	1805	Rushock ...	...
"	Upton Snodsbury, 800 A. F. ...	*1,000	1806	Crowle ...	...
1775	Bengworth, 39 yl. ...	*1,365	"	Wick juxta Pershore with Wick Burnel and West Waryn ...	...
"	Cleeve Prior, 27 yl. ...	*945	1807	Queenhill ...	...
"	Cutsden ...	800	"	Broughton Hachett ...	...
"	Pinvin, 14½ yl. ...	*507	"	Aldington ...	550
"	Wolverley ...	1,500	1808	Bredon ...	...
1776	Charlton, 53½ yl. ...	1,864	1809	Iccomb ...	...
"	Great and Little Hampton, 46 yl. ...	*1,610	1810	Eckington ...	...
"	Leigh ...	20	"	Pensham in Pershore ...	...
1778	Rouslench ...	1,300	"	Sedgeberrow ...	...
1779	Croptborne, 62 yl. ...	*1,860	"	Tibberton ...	...
Carried forward ...		26,533	1811	Churchill ...	...
			Carried forward ...		1,696

WORCESTER—continued.

Date.	Enclosure.	Area enclosed.	Enclosed under the General Enclosure Act, 1845.			
			Date of Act.	Date of Award.	Parish.	Area.
	Brought forward ...	1,696				
1811	North, South, and Middle Middleton ...		1847	1850	Newbold on Stour ...	957
"	Overbury ...		*	1852	Welland ...	55
"	Stoke Talmage ...	420		1854	Norton juxta Kempsey (East field) ...	70
1812	Badsey ...			1855	1860 Berrow ...	300
"	Holdfast ...			1856	1863 Upton on Severn and Ripple ...	880
"	Shipton upon Stower ...		1861	1865	Armscote (Tredington P.) ...	954
1813	Flyford Flavell ...		1864	1868	Blackwell (Tredington P.) ...	793
"	North Piddle ...	800				
1814	Bredon ...					
"	Inkberrow ...	2,200				
"	Strensham, 196 A. P. ...	*300				
"	Ombersley ...					
1818	Great Cemberton ...					
1819	Alvechurch ...	450				
1825	Whiteladies Aston ...					
1832	Fladbury ...					
1833	Yardley ...	200				
		<u>6,066</u>				<u>4,009</u>
					Acres.]	
				Before 1802	... 36,942	
				1802-1845	... 6,066	
				After 1845	... 4,009	

YORKSHIRE, WEST RIDING.

Date.	Enclosure.	Area enclosed.	Date.	Enclosure.	Area enclosed
1729	Thurnscoe ...	500		Brought forward ...	14,685
1757	Bishophthorpe, 200 A. F., 50 A. M., 400 A. P. ...	650	1770	Sherburn, Lennerton, Burkstone Ash, Church Fenton, Little Fenton and Biggin ...	3,013
1759	Bolton upon Dearne ...	1,000	"	Great Useburne, 480 A. F., 390 A. P. ...	870
1760	Adwicke in the Street ...	1,000	1772	Ackworth ...	
"	Calton ...		"	Clareton with Coneystrop and Allerton with Flaxby ...	480
1762	Rotherham, 750 A. M., 220 A. P. ...	*1,720	"	Follifoot, 165 A. F., 1,100 A. P. ...	1,265
1765	Kirkhammerton, 400 A. F. ...	*600	"	Snaith and Kellington, 1650 A. F., 922 A. P. ...	2,572
"	Kimberworth (Rotherham parish) ...	105	1773	Armthorpe ...	
"	Wadworth ...	2,000	"	Arkendale, 377 A. F., 250 A. P. ...	627
1766	Marston, 950 A. F., 750 A. P. ...	1,700	"	Drax, all F. ...	150
1767	North Auston and Todwick ...	1,100	"	Snaith and Cowick ...	1,160
"	Adlingfleet, Fockerby and Haldenby, 450 A. F., 700 P. ...	1,150	"	Skipton and Kildwick ...	2,329
1768	Hook ...	1,000	1774	Acombe and Holgate ...	2,000
1769	Laughton en Le Morthen, 1,100 A. F., 360 A. P. ...	1,460	"	Rawmarsh, 450 A. F., 800 A. P. ..	1,250
"	Sutton, 63 oxgangs ...	700			
	Carried forward ...	14,685		Carried forward ...	30,401

YORKSHIRE, WEST RIDING—*continued.*

Date.	Enclosure.	Area enclosed.	Date.	Enclosure.	Area enclosed.
	Brought forward ...	30,401		Brought forward ...	66,950
1775	Rigton (Kirkby Overblow P.) 2,000 A. F., 30 A. M. ...	2,030	1794	Hoyland ...	...
1776	Cawood and Wistow ...	2,000	„	Rufforth ...	770
1777	Barnsley, 280 A. F., 500 A. P. ...	780	1795	Checkheaton ...	210
„	Cantley, Brampton, Bassacar and High Ellers ...	2,700	1796	Berwick in Elmet ...	2,500
„	Monkbretton, 70 A. F., 300 A. P. ...	370	„	Hambleton ...	...
„	Thornton, 844 A. F., 307 A. P. ...	1,151	„	Kimberworth, 220 A. F., 250 A. P. ...	470
„	Thorner, 370 A. F., 500 A. P. ...	870	„	Mirfield, 60 A. F., 500 A. P. ...	560
1778	Dinnington, 610 A. F., 203 A. P. ...	813	1797	Bolton Percy ...	1,300
1780	Kighley, 80 A. F., 5,000 A. P. ...	5,080	„	Dalton, 300 A. F., 150 A. P. ...	450
„	Moseley and Kirk Bram- with, 220 A. F., 730 A. P. ...	950	„	Hillam ...	...
1783	North Deighton... ..	546	„	Pontefract ...	...
1784	Hextrope with Balby and Long Sandall ...	1,600	1798	Ulley, 220 A. F., 100 A. P. ...	320
1786	Moor Monkton, 390 A. F., 690 A. P. ...	1,080	1799	Brayton, Thorpe Willoughby, Burton and Gateforth ...	...
„	Methley, 500 A. F., 300 A. P. ...	800	„	Hirst Courtney ...	...
„	Little Smeaton and Stubbs Walden, 440 A. F., 718 P. ...	1,158	„	Long Preston, 15 F.'s, 150 A., 400 A. P. ...	550
1787	Spoofforth	500	„	Sandall Magna, Walton and Crigglestone ...	759
„	Cracoe, 77 A. F., 595 A. P. ...	662	„	Kirkheaton ...	400
1788	Featherstone, 230 A. F., 450 A. P. ...	680	1800	Carlton and Cambles- forth ...	...
„	Knapton, 5 F.'s... ..	230	„	Denby with Clayton West, M. I. ...	...
1789	Thorpe, 26 A. F., 700 A. P. ...	726	„	Kearley cum Netherby Martin with Graffton ...	400
1790	Burton Leonard	273	„	Womersley ...	...
1791	Sheffield, M. I. 30 A., 6,000 A. P. ...	6,030	„	High and Low Egborough, Sherwood, Hatgreen and Tranmere ...	500
„	Tadcaster	...	1801	Staveley ...	...
1792	Monk Fryston	650	„	Skellow ...	600
„	Tockwith	900	„	Little Useburn ...	...
1793	Brotherton, 286 A. P. ...	300	„	Whixley ...	...
„	South Milford and Lumby ...	1,370	„	Little Weeton, 1,200 A. F., 300 A. P. ...	1,500
„	Jakefield, Stanley, Wren- thorpe, Alvesthorpe and Thorns ...	2,300	„	Kettlewell and Conistree, 150 A. F. & M., 4,000 A. P. ...	4,150
	Carried forward ...	66,950			82,389
			1802	Crofton ...	473
			„	Hoyland Swaine ...	...
			1803	Barmby upon Dunn, 600 A. F., 604 A. P. ...	1,204
				Carried forward ...	1,677

YORKSHIRE, WEST RIDING—*continued.*

Date.	Enclosure.	Area enclosed.	Date.	Enclosure.	Area enclosed.
	Brought forward ...	1,677		Brought forward ...	21,518
1803	Hemsworth ...	800	1810	Rossington, 1,313 A. F.,	
"	Clifford, 300 A. F., 460			1,070 A. P. ...	1,383
"	A. P. ...	760	1811	Askham Bryan ...	660
"	Halifax (Elland cum		"	Hatfield, Thorne and	
	Greetland) 116 A. F.,			Fishlake (N.R.) ...	1,755
"	600 A. P. ...	716	"	Langside, 30 A. F., 4,000	
"	Kippax ...	890	"	A. waste ...	4,030
"	Shadwell, 80 A. F., 580		"	Ecclesfield (very little F.)	14,000
"	A. P. ...	660	1812	Darrington ...	
1804	Normanton and Wood-		1813	Fairburn... ..	820
	house, 330 A. F., 260		"	Askham Richard ...	220
"	A. P. ...	590	1814	Collingham, 200 A. F.,	
1805	Thresfield and Skire-			230 A. P. ...	430
	thorns, and Burnsal ...	1,690	"	Wath upon Dearne and	
1806	Kirk Sandall, 100 A. F.,			Rotherham, 180 A. F.,	
"	95 A. P. ...	195	"	80 A. P. ...	260
"	Skelton ...		"	Campsall, Norton and	
1807	Halifax ...	1,900	"	Askern ...	2,860
"	Bishop Monckton, 670		"	Frickley cum Clayton ...	440
"	A. F., 150 A. M., 300		"	Wickersley, 340 A. F.,	
"	A. P. ...	1,120	"	200 A. P. ...	540
"	South Kirby and South		1815	Brodsworth ...	
	Elmsall ...	600	"	Brampton and Swinton	1,370
"	Ossett (Dewsbury), 230		"	Burnsal, 9 A. F., 6,330	
"	A. F., 350 A. P. ...	580	"	A. P. ...	6,339
"	Low Dunsforth ...	630	1816	Arncliffe and Hawkes-	
"	Bramham, 680 A. F., 650			wick, 80 A. F. & M.,	
"	A. P. ...	1,330	"	1,800 A. P. ...	1,880
1808	Aldbrough, 580 A. F., 396		"	Arncliffe and Kettlewell	3,000
"	A. M. & P. ...	976	"	Thorpe Arch and Walton	
"	Kirk Smeaton ...	900	1817	Monkfryston ...	290
1809	Altofts, 290 A. F., 470		1818	Snaith ...	1,000
"	A. P. ...	760	1819	Barnbrough, 800 A. F.,	
"	Cudworth, 54 A. F. and			273 A. P. ...	1,073
"	M. I. 190 A. P. ...	244	"	Peniston, 50 A. F. & M. I.,	
"	Horbury, 260 A. F., 100		"	370 A. P. ...	420
"	A. P. ...	360	1827	Arksey ...	1,800
"	Purston Jackling, 100		1828	Kirburton and Almon-	
"	A. F., 70 A. P. ...	170		bury, 300 A. F., 18,000	
"	Rothwell with Royds		"	A. P. ...	18,300
	and Oulton with		"	Knaresborough and	
"	Woodlesford ...	450		Farnham, 78 A. F.,	
"	Cadeby, 500 A. F. & M.,		"	466 A. P. ...	544
"	180 A. P. ...	680	"	Moor Monkton ...	600
1810	Badsworth, M. I. ...		"	Whitgift ...	1,000
"	Garforth, 520 A. F., 280		1831	Ferry Fryston ...	830
"	A. P. ...	800	1835	Ulleskelf... ..	711
"	Gowthorpe (with old in-		1837	Rothwell, 300 A. F., 80	
	closures) ...	500	"	A. P. ...	380
"	Thorp Audlin ...	540			
"	Wath upon Dearne,				
"	M. I. ...				
					<u>88,453</u>
	Carried forward ...	21,518			

YORKSHIRE, WEST RIDING—*continued.**Enclosed under the General Enclosure Act, 1845.*

Date of Act.	Date of Award.	Parish.	Area.	Date of Act.	Date of Award.	Parish.	Area.
						Brought forward	... 1,737
				1859	1861	Mexborough	... 365
							<u>2,102</u>
						Acres.	
						Before 1842	... 82,389
						1802-1845	... 88,453
						After 1845	... 2,102

Date of Act.	Date of Award.	Parish.	Area.
*	1849	Clapham ...	592
1855	1858	Conisbrough ...	592
1854	"	Sutton (Campsall P.) ...	553
		Carried forward	... 1,737

YORKSHIRE, EAST RIDING.

Date.	Enclosure.	Area enclosed.	Date.	Enclosure.	Area enclosed.
1731	Catwicke, 2 C. F.'s and open pastures, 88 oxgangs ...	*1,760		Brought forward	... 32,950
1740	Bewholm, 2 fields, etc. ...	*1,600	1765	Everingham, 740 A. F., 850 A. M. and P. ...	1,590
1741	Great and Little Driffeld, 190 oxgangs ...	*3,800	"	Ellerker, 75 oxgangs ...	1,800
1746	Kelfield, 400 A. F. ...	*600	"	Flamborough ...	3,000
1755	Nunburnholme ...		"	Ulrome (or Ourram), (Holderness) ...	1,200
"	Stillingfleet, 40 oxgangs	*800	1766	Bessingby ...	1,080
1757	Fulford, 330 A. F., 450 A. P. ...	780	"	Beeford ...	3,000
"	Pocklington, 6 F.'s M. and P. ...		"	Brigham (Foston P.), 48½ oxgangs ...	*730
1758	Ottringham ...	*2,400	"	Cottingham ...	3,000
"	Skirpenbeck, 99 oxgangs	*1,980	"	Naburn, 350 A. F., 349 A. P. ...	699
1761	Burton Pidsea (Holderness) ...	1,800	"	Patrington (Holderness)	2,500
1762	Sproatley (Holderness) 119 oxgangs ...	*2,380	1767	South Burton (Burton Agnes) ...	2,800
"	Dringhoe, Upton and Brough (Holderness), 71 oxgangs ...	1,420	"	Huggate, 131 oxgangs ...	*2,620
1763	Marfleet (Holderness), 24 oxgangs ...	*480	1768	Bridlington ...	2,500
"	Sutton (Holderness), 740 A. F., 3,400 A. P. ...	4,140	"	Burton Fleming, 168 oxgangs ...	3,000
1764	Aldborough (Holderness), 80½ oxgangs ...	*1,610	"	Hotham, 120 A. F., 1,500 A. P. ...	2,700
"	North Cave ...	1,400	"	Welwich in Holderness...	
"	Sudcoates (Drypool), 94 nobles, 1½ gates, 1 foot F. ...		"	Willington ...	2,300
"	Skipsea, 88 oxgangs ...	*1,760	1769	Atterwick in Holderness	1,200
"	Skeffling (Holderness) ...	1,440	"	Aclome ...	1,060
1765	Benton (Bempton next Flamborough), 80 oxgangs ...	*1,600	"	Bishop Wilton ...	3,800
"	Brantingham and Thorpe, 900 A. F., 300 A. P. ...	1,200	"	Elvington ...	800
	Carried forward	... 32,950	"	Hutton Cranswick ...	3,000
			"	Lelley in Holderness, 22½ oxgangs ...	800
			"	Nafferton and Wansford, 3,000 A. F., 1,200 A. P. ...	4,200
			"	Poppleton (W. R.) and Scagglethorpe (E. R.), 920 A. F., 900 A. P. ...	1,820
			"	Sancton, 1,200 A. F., 80 A. M., 330 A. P. ...	1,610
				Carried forward	... 85,759

YORKSHIRE, EAST RIDING—*continued.*

Date.	Enclosure.	Area enclosed.	Date.	Enclosure.	Area enclosed.
	Brought forward ...	85,759		Brought forward ..	166,758
1769	Thwing ...	4,000	1777	Melbourne and Storthwaite, 300 A. F., 300 M., 1,800 P. ...	2,400
"	Wheldrake, 500 A. F., 180 A. M., 1,500 A. P. ...	2,180	1778	North Dalton ...	1,700
"	Youlthorpe ...	681	1780	Thornton, 800 A. F. ...	1,000
1770	Great Cowden (Holderness), 54½ oxgangs ...	1,100	1783	Roos in Holderness ...	1,521
"	Easington (Holderness)..	1,300	1785	South Cave ...	2,500
"	West Heslerton and Yedingham, 80 oxgangs ...	1,600	"	Kilnwick, 86 oxgangs, 650 A. F., 250 A. P. ...	900
"	East Heslerton ...	1,200	1788	Filey ...	620
"	East Newton (Holderness) ...	600	1789	Coniston in Holderness...	500
1771	Butterwick, 2 F.'s ...	7,000	1792	North Grimston, 75 oxgangs ...	660
"	Kilham on the Wolds ...	7,000	1793	Hollym and Withernsee	1,800
"	Lockington and Ayde, 1,800 A. F., 250 A. P. ...	2,050	"	Speeton ...	1,800
"	Lisset, 400 A. F., 600 A. P. ...	1,000	"	Skidby ...	600
"	Melton ...	1,000	"	Southam in Kirkburn ...	1,200
"	Long Reston and Arnold	1,600	1794	Elloughton, Brough and Walby ...	2,600
1772	Sigglesthorpe (Holderness), 65½ oxgangs ...	1,000	"	Lund ...	2,300
"	Welton ...	1,500	"	Tibthorpe ...	3,000
"	Would Newton ...	2,000	"	Warter ...	7,500
1773	East Cottonwith, 400 A. F., 560 A. F. ...	960	"	Walkington ...	3,000
"	Everthorpe, 42 oxgangs	500	1795	Holme upon the Wolds...	1,450
"	Harpham, 1,400 A. F., 600 A. P. ...	2,000	1796	West Ella, Kirk Ella, and Ellerby ...	1,600
"	Holme upon Spalding Moor, 1,472 A. F., 285 A. M. ...	7,000	1797	Settrington ...	1,100
"	Market Weighton, 4,200 A. F., 2,500 A. M. ...	6,700	1800	Holmpton and Hollym cum Withernsea ...	900
"	Preston in Holderness, 129 oxgangs ...	4,500	"	Hunmanby and Fordon	2,500
"	Sheckling cum Burstwick ...	850	1801	North Frodingham ...	2,500
1774	Bainton ...	2,700	"	Hornsea ...	2,500
"	Garton ...	4,050	"	Langtoft upon the Wolds	3,200
"	Rudstone...	4,000	"	Molcroft ...	700
1775	Goodmanham, 3,000 A. F., 100 A. P. ...	3,100	"	Ruston Parva ...	900
1776	Bilton ...	770	"	Weaverthorp ...	8,300
"	Foston ...	800	"	Willerby ...	1,500
"	Sutton upon Derwent ...	708			<u>227,009</u>
1777	Boynton ...	2,000	1802	Ellerton (Ellerton Priory) ...	1,040
"	Bugthorpe, 640 A. F., 310 A. P. ...	950	"	Folkton and East and West Flotmanby ...	1,800
"	Barmby upon the Moor...	2,800	"	Keyningham (Holderness)	1,350
"	North and South Newbald ...	6,000	"	Withernwick ...	1,500
"	Tunstall (Holderness) ...	800	"	Sewerby and Marten ...	2,000
	Carried forward ..	166,758	1803	Gaxton, Potter Brompton and Binnington ...	3,800
			"	Middleton, 2,000 A. F., 1,800 A. P. ...	3,800
			"	Wetwang and Fimber ...	2,820
				Carried forward ...	18,110

YORKSHIRE, EAST RIDING—*continued*.

Date.	Enclosure.	Area enclosed.	Date.	Enclosure.	Area enclosed.
	Brought forward ...	18,110		Brought forward ...	36,147
1805	Ryhill and Camerton ...	1,300	1823	Ferriby and Kirk Ella...	3,350
"	Huttons Ambo ...	2,500	1830	Blacktoft, Easttrington	
1806	Elsternwick ...	875		and South Cave, all F.	430
"	Owthorn ...	650	1832	Bubwith ...	1,700
1809	North Duffield ...		1833	Great Gwindale...	650
1810	West Cottingwith and Thorganby ...		1843	Hemingbrough ...	
"	Fridaythorpe ...	2,000	1844	Brandes Burton...	
1811	Paghill ...	402			<u>42,277</u>
"	Righton ...	1,600			
"	Osgodby ...	500			
1813	Easttrington ...				
1814	Hayton, 1,150 A. F., 450 A. P. ...	1,600			
1816	Londesborough ...				
1818	Etton, 2,000 A. F., 600 A. M. and P. ...	2,600			
1819	Barmston, 160 A. F., 130 A. P. ...	290			
1820	Hemingbrough (South Duffield township) ...				
1822	South Dalton (with old enclosures) ...	1,800			
1823	North Burton ...	1,920			
	Carried forward ...	36,147			

Enclosed under the General Enclosure Act, 1845.

Date of Act.	Date of Award.	Parish.	Area.
*	1849	Mappleton ...	1,060
*	1851	Cottam (Langtoft P.) ...	2,515
1878	1880	Riccall ...	1,297
1901		Skipworth ...	321
			<u>5,193</u>

	Acres.
Before 1802 ...	227,009
1802-1845 ...	42,277
After 1845 ...	5,193

YORKSHIRE, NORTH RIDING.

Date.	Enclosure.	Area enclosed.	Date.	Enclosure.	Area enclosed.
1748	Faceby in Cleveland, 700 A. F., 900 A. P. ...	1,600		Brought forward ...	15,447
1755	Marsk and Redcar ...	1,400	1771	Scalby and Throxenby or Newby, 2,000 A. F.	4,000
"	Slingsby ...		1773	Wilton (Ellerburn P.)	700
1756	Sutton upon the Forest, 1,300 A. F. ...	3,000	1774	Swinton (Appleton P.)	700
"	Warthill, 40 oxgangs ...	800	1776	Amotherby ...	
1758	Brompton and Sawden, 8 F.'s etc. ...		"	Lyth ...	
1759	East Cotham, 400 A. F., 400 A. P. ...	800	"	Stonegrave, Westness and Nunnington ...	1,110
1766	Stillington ...	1,400	1777	Bulmer ...	
1768	East Ayton ...	1,337	1784	Lockton ...	
1769	Ebberston ...	1,200	1785	Wykham and Ruston ...	2,000
"	Haxby ...	1,640	1787	Lastingham ...	
"	Sheriff Hutton and West Lilling, 833 A. F., 837 A. P. ...	1,670	1788	Kirkbymoorside, Fadmoor and Gillamoor	
1770	Upper Dunsforth and Braxton, 500 A. F., 100 A. P. ...	600	1789	Cold Kirkby ...	
	Carried forward ...	15,447	1790	Hutton Bushnell, 700 A. F., 170 A. M., 1250 A. P. ...	2,120
			"	Linton, 50 A. F., 480 A. P. ...	530
				Carried forward ...	26,607

YORKSHIRE, NORTH RIDING—*continued.*

Date.	Enclosure.	Area enclosed.
	Brought forward ...	26,607
1791	Norton in the Clay ...	800
1793	West Tanfield, 80 A. F., 500 A. P. ...	580
1794	Old Malton, 2 F.'s, one 416 A., other 14 A. ...	1,500
"	Skelton, 75 oxgangs, F., 200 A. P. ...	1,100
1798	Sowerby ...	1,100
1800	Tholthorpe and L. Fla- with ...	1,570
		33,257
1802	Flixton ...	2,600
"	Richmond, 344 A. F., 1,340 A. P. ...	1,684
1803	Wilton, Laxenby, Lack- enby and West Coat- ham ...	1,100
1806	Kirkdale and Hemsley...	950
1807	Alne ...	600
"	Hunton, about 40 A. F.	720
1808	Easingwold ...	500
1809	Helperby ...	
"	Skelton ...	
	Carried forward ...	8,154

Date.	Enclosure.	Area enclosed.
	Brought forward ...	8,154
1809	Allerston...	14,000
1810	Gilling in Richmond- shire ...	300
"	Tollerton...	
1811	Westerdale, all F. ...	190
"	Lune, Holwick and Romaldkirk, 302 A. F.	6,840
1812	Newton upon Ouze and Shipton ...	911
1815	Melsonby ...	600
1833	Bedale ...	176
		3,171

Enclosed under the General Enclosure Act, 1845.

Date of Act.	Date of Award.	Parish.	Area.
"	1853	Hinderwell	894
1864	1870	Leake	140
			1,034
			Acres.
	Before 1802	...	33,257
	1802-1845	...	31,171
	After 1845	...	1,034

APPENDIX C.



LELAND'S ITINERARY.

NORTHAMPTON, LEICESTER AND RUTLANDSHIRES.

LELAND entered Northamptonshire from Huntingdonshire, coming through Kimbolton and the village of Leighton. We have in Vol. I., folio 3 :—

“From Leighton to Barnewel Village” (in Northamptonshire) “a vi miles by exceeding faire Corne and pasture ground.”

“Thence to Oundle . . . the Medowes lying on every side on a great Leavel thereabouts.”

“Oundle to Foderingeye, a 2 miles by mervelous fair Corne ground and Pasture, but little wodde.”

“From Welingborow to Northampton 8 miles al be champaine Corne and Pasture Ground, but little wood or none, even as it is betwixt Oundle and Welingborow” (fol. 7).

“Wedon is a praty throughfare, sette on a playne ground” (fol. 11).

“Towcester is 7 miles from Wedon and as much from Northampton, al by playne Corne ground and pasture.”

“Northampton to Kingesthorpe a mile, and a little farther, by Multon Parke enclosed with Stone . . . thens by Champayne Ground, bering good grasse and Corne, a ix mile to Ketering” (fol. 12).

“Thens to Welledon, an uplandish Towne, 4 miles, where the Soile is sumwhat furnished about with wood, and plentee beside of Corne and Grasse . . . And thens 2 mile by Corne, Pasture and Wood to Deene.”

“From Dene to Rokingham, by summe Corne and Pasture but more Wood grounde a 3 miles” (fol. 13).

“There lyeth a greate valley under the Castle of Rokingham, very plentifull of Corne and Grasse . . . The Forest . . . about 20 mile

yn length, and in bradthe 5 or 4 Miles in sum places in sum less. And withyn the precinctes of it is good Corne and Plentie of Woodde."

"Rokingham to Pippewelle, the late Abbay, about a 3 Miles of by Wood and Pasture."

"Dene to Haringworth a 3 Miles be Corne, Grasse, and sum Woody Grounde" (fol. 14).

Then entering Leicestershire, he says:—

"The grounde bytwixt Dene and Staunton is plentiful of corne, and exceeding faire and large Medowis on both sides of the Weland. But from Rokingham to Staunton there was in sight little Wodde, as yn a Countrey al Chaumpain. From Staunton to Leycester al by Champaine Grounde an 8 or 9 Miles" (fol. 15).

"Leyrcester to Brodegate by grounde welle Wooddid 3 miles . . . Brodegate to Groby a Mile and a half much by Woodden lande" (fol. 19).

"Brodegate to Leighborow about a v Miles. 1st foreste of Charley communely called the Wast, xx miles or more in Cumpace, having plenty of woode" (fol. 20). The forest of Leyrcester, the other forest of the county, he says, is five miles in length.

"Brodegate to Bellegrave Village a 4 miles by Woddy and Pasture Grounde" . . . "Bellegrave to Ingresby a 4 Miles, partely by Corne, Pasture, and Woddy ground . . . Thens to Wiscombe a 4 Miles by Corne, Pasture and Wood . . . faire Orchardes and Gardenes" (fol. 22).

"Marke that such parte of Leyrcestershire as is lying South and Est is Champaine, and hath little Wood. And such parte of Leircestershire as lyith by West and North hath much woodde" (fol. 24).

Next he passes through Rutlandshire into Northamptonshire again:—

"From Wiscombe partely through Woddy ground of the Forest of Leefield, and so in Ruthelandshir by Woddy first, and then all champain Ground, but exceeding rich Corne and Pasture, to Uppingham . . . from Uppingham to Haringworth (Northamptonshire) 3 little miles, al by Champaine . . . Dene to Cliffe Parke 3 Miles; it is partely waullid with stone, and partely palid. From Dene to Coliweston a 5 or 6 Miles, partely by Champaine, partely by Woodde ground" (fol. 25).

"From Coly Weston to Grimesthorpe (in Lincolnshire) about an

8 or 9 most by playne Ground, good of Corne and Pasture, but little wood" (fol. 26).

His journey then took him northwards, but returning, he again passed through Leicestershire, Rutland and Northamptonshire, and notes :—

"Notingham to Bever (Belvoir) all by champaine ground, 12 miles" (fol. 113).

"Bever to Croxton, 2 miles" (fol. 115).

"Croxton to Castleford Bridge by champaine" (fol. 115).

"Castleford Bridge to Stamford 1 mile" (fol. 115).

"Stamford to Colyweston $2\frac{1}{2}$ miles, champayn" (fol. 115).

"Colyweston to Dene, moste by Chaumpaine" (fol. 115).

"Dene to Foderingeye, most by wood, 6 miles" (fol. 116).

"Foderingey to Undale, 2 miles, champaine" (fol. 116).

"Thens a 9 mile to Layton in Huntingdonshire, Champaine" (fol. 116).

"To Higham Ferrers in Northamptonshire, 8 miles" (fol. 116).

"To Bedford, 14 miles, champaine" (fol. 116).

WARWICK.

"From Charlecote to Stratford a 3 Miles by Champaine, good corn and grasse" (166 b).

"I roade from Stratford by champaine Ground, fruitfull of Corne and Grasse a 5 miles . . . thence 2 miles by Champaine to Coughton. From Coughton to Aulcester 2 miles by enclosed Ground (167 b). I roade from Aulcester towards Evvesham a 2 Miles by woody and inclosed Ground, and then a mile by Ground lesse inclosed, but havinge more Corne then wood. Thence a 4 miles by cleane Champion" (168 b).

Having thus entered Gloucestershire, he came through Worcester and Lichfield, and so re-entered Warwickshire from the north, and found—"Colishull to Meriden 4 m. by enclosed ground having some corne, wood and pasture. 3 miles by like ground to Coventry" (190 a). To Southam was "4 m. good corne and pasture in Champion," thence to Banbury in Oxfordshire "10 m. by champaine, noe wood but exceedinge good Pasture and corne."

BUCKINGHAM.

From Dunstable to "Mergate," as we have seen, was "al by Chaumpaine a vj miles" (vol. 1, fol. 120). But "thens by Chiltern

Hilles and woods and baren woody and ferne ground vij miles to Barkhanstede" (in Herts, near the Buckingham boundary, fol. 121). "Thens I passid by Hilly, Woody, and much baren ground to Cheynes (in Bucks) a v miles" . . . v miles good Pasture and Corne, v miles mory Ground, and 3 m. by sum enclosid and Woddy ground to Windelsore. From Windelsore by a 3 miles most be wood and enclosid, and 2 m. in faire open and levelle medow . . . to Tamise . . . Half a mile to Stanes Bridge" (fol. 122).

On a later journey he came from Oxford, and entered Bucks at Thame "by some Hilly and after great Pasture Groundes, fruitfull of beanes a 10 m. to Querendon in the Vale of Alesbury. Thens 5 m. to Alesbury all champaine" (Vol. IV. 191 b). But from Hagmondesham (Amersham) to Uxbridge was "9 miles by goodly enclosid grounds."

OXFORDSHIRE.

He came from Reading and crossed the river to Caushem (Caversham). "Thens I rode a v miles and more all by great Woddes. And thens by Chaumpaine hilly ground a 4 m. to Ewelme" (Vol. II. fol. 5). "From Ewelme to Haseley a v m. by Chaumpaine Ground somewhat plentiful of corn, but most layid to Pasturage" (fol. 7). "From Haseley to Chisilhampton by plaine ground fruteful of corne and Grasse, but baren of wood as al that Angle of Oxfordshire is, 3 miles. Thens to Drayton Village. Thens a mile to Dorchester" (fol. 10). "To Walingford $1\frac{1}{2}$ m. by mervelus fair Champain" (fol. 12). Here he again crossed the Thames into Berkshire; but later he entered the north west of the county, and found the district from Sutton to Banbury "all by champaine barren of wood" (Vol. IV., fol. 162 b), and the first 12 miles of the road from Banbury to Warwick "by Champaine Groundes, fruitful of Corne and Grasse" (163 a). Similarly from Southam (in Warwickshire) to Banbury was "10 m. by champaine, noe wood but exceedinge good Pasture and corne," and from Banbury to Bercester (Bicester) was 10 or 11 miles of "champaine."

LINCOLN.

"From Coly Weston to Grimesthorpe about an 8 Miles or 9, most by playn Ground, good of corne and pasture, but little wood" (Vol. I. fol. 26). "From Grimesthorpe to Corby about a 3 Miles by Champayne Ground. . . . Thens to Boutheby a 3 Miles, and

thereabouts is meately store of Wodde scaterid" (fol. 27). "From Boutheby to Hayder al by Champaine ground, fertile of corne and grasse, 4 Miles. From Hayder to Sleford a vj Miles al by Champaine ground (fol. 29). From Sleforde to Ancaster a 4 Miles by Chaumpaine (fol. 30). Ancaster to Temple Bruern al by Champaine of Ancaster Heth a 4 Miles. . . . From Temple Bruern to Lincoln 10 Miles by Champaine" (fol. 32). "Lincoln to Torkesey parte by Marsh Ground, and part by other, but very little wood, a 7 Miles. Torkesey to Marton Village about a mile by plaine sandy ground" (fol. 35).

YORKSHIRE, EAST RIDING.

"From York to Kexby Bridge by Champaine v miles" (Vol. I. fol. 49). Thence he went to Leckenfield, a village a little to the north of Beverley, "And al this way betwixt York and the Parke of Lekenfeld is meately fruteful of Corn and Grass, but it hath little wood" (fol. 49). He then went south to Hull and returned to Beverley: "From Kingeston to Beverle a vj Miles, a v by low pasture and Marsch Ground, and a Mile by enclosid and sumwhat woddy ground" (fol. 57). Starting from Beverley again towards Goole he has "Beverle to Walkington Village a 2 Mile, one by enclosid, and another by chaumpaine good corne land. Walkington to North Cave Village 5 Miles by fair champain corn ground. Northcave to Scalby a 3 Miles al by low Marsch and Medow Ground" (fol. 57).

"From Scalby to Hoveden (Howden) 4 M. scant one by enclosid Pasture and 3 by Morische and Fenny ground" (fol. 58). "From Hoveden to Wresehill (Wressel) a 3 Miles al by low Medow and Pastureground, whereof part is enclosed with Hegges" (fol. 59). "From Wresehill . . . Ferry about a Mile, most by Medow Ground, and so a xj Miles to York, whereof most parte was in sight Medow and Morisch Ground, and but meane corne, but toward York the soyle and corne were better" (fol. 69).

NORTH AND WEST RIDINGS.

He came on his first journey from Scrooby in Notts to Doncaster. He observes, "Bawtre to Doncaster an vij Miles by a great Plaine and Sandy ground caullid Blitherle" (Vol. I. fol. 37), Round Doncaster is "Medow, Corn and sum wood," but from "Tikhill to Cunesborow (Conisbrough) a 4 Miles by stony way and enclosid

ground" (fol. 39), and from "Dancaster to Heathfield (Hatfield) by champayn sandy ground a 5 Miles," and here comes Hatfield Chase, the scene of Vermuiden's labours later. He return to Doncaster and went north and found "The ground between Dancaster and Pontefract in sum places meately wooddid and enclosid ground" (fol. 42); from "pontefract to S. Oswaldes by much enclosid and meately woddy ground a 3 Miles or more" (fol. 44). From St. Oswalds to Sandon village (a mile from Wakefield), "a 3 Miles by enclosid Ground" (fol. 44). From Wakefield to Pontefract direct was "a vj miles parte by Enclosure, parte by Champaine" (fol. 46). Thence to Leeds, he found first three miles of enclosed ground, then five miles of low meadow, and "good high plaine corne ground" (fol. 46).

From Leeds to Tadcaster was apparently unenclosed, but from Tadcaster to York there was first 4 miles of enclosed ground, then four by "playn Champaine" (fol. 48). "From York to Stockton yn the Moore a 3 Miles by low Pasture and moreisch Ground. . . . Thens a 5 Miles by much lyke Ground . . . a little beyond that as about half a M. is Whitewelle Village. Thereabout the Fieldes for a Miles space were inclosid. . . . Thens a 2 M. by Fyrry. Thens to Malton a 3 Miles, and the ground is hilly there and daly and plentiful of Corne and Pasture (Vol. I. fol. 63). From Malton to Shirburne Village about an 8 miles by Champaine Ground. From Shirburne by Hilles to Semar. Thens a Mile by Meately plaine Ground, and so 2 Miles more in a vale enclosid with stepe Hilles on ech side to Scardeburg (fol. 66).

"Moste of the Ground from Scardeburg to Pykering was by Hille and Dale meate plentiful of Corn and Grasse but little wood in sight" (fol. 70). The vale of Pickering was open field land.

North-west of York itself was the great forest of Galtres, ten miles through (fol. 74). At Herperly Village beyond was "meately good corn ground, Pasture and Medow and sum Wooddes" (fol. 75).

Further south. "From Kirkeby Wisk to Northalverton a 4 Miles by Pasture and Corne Ground" (fol. 75).

Returning later from Durham we have from Greta Bridge to Richmond, "sum good corn and much More (fol. 95). Richmond to Middleham, al by mory Ground and little wood" but "Middleham to Gervallx Abbay a 2 Miles most by enclosed Pastures." His route lay through Ripon, West Tanfield, Boroughbridge, to Knaresborough; he notes pasture, corn, wood and moor. Then comes the great forest

of Knaresborough, 20 miles long and 8 broad. Then he went south through Pontefract and Doncaster, finding after Doncaster "3 Mile al by Champain ground" (fol. 105).

He came again into Yorkshire from Lancashire, and found by the Ouse near York "the ground was fair of Pasture, Corne and wood" (Vol. V. fol. 91), and from "Shirburne to Pontfract 6 m. soile in sight plaine, wel cornid, but little wood" (*ibid.*), and coming south, there is "woddy Grounds," and "soile riche of wood, Pasture, corne," but no mention of enclosure.

WESTERN COUNTIES.

Leland's observations are as follows. He saw, approaching Lechdale on crossing the Thames from Faringdon, "In ripa ulterori . . . greate Enclosures of stone walls" (Vol. II. fol. 22). He turned into Wiltshire, and came from Bradford into the neighbourhood of Bath and East Somerset. Burton to South Cadbury, and thence to Sherborne, just over the Dorset boundary, was "fair and fruteful Champain" (fol. 47), but by another route back from Sherborne to South Cadbury "the Pastures and Fieldes be much enclosid with Hegge Rowes of Elmes" (fol. 50), and a little later he says that "most part of al Somertsetshire is yn hegge rows enclosid" with elms (fol. 55).

Some details are given later. Southtown to Midsummer Norton was "hilly and enclosid," but Midsummer Norton to Wells "chaumpayne" (Vol. VIII. fol. 5), but thence south to Munney Delamere "hilly and enclosid" (fol. 7). Midsummer Norton to Mells (near Frome) was champayn (Vol. VIII. part 2, fol. 78 a). From Bath to Kelston (in Wilts) was champaine (fol. 67 b) and the triangular district between Bristol, Bath and Chipping Sodbury about half enclosed and half "champaine," and also the district on the other side of the Bristol Avon towards Frome in Somerset, the immediate neighbourhood of Frome being open (Vol. VII., part 2, fol. 68-77).

Aulcester (in Warwick), to Evesham was "2 Miles by woody and inclosed ground, and then a mile by Ground lesse inclosed. . . . Thence 4 miles by cleane Champion" (Vol. IV. fol. 168b), and the "champion Ground" continued for 6 or 7 miles to Stanwey, on the Cheltenham road.

North-west Worcester seems to have been generally enclosed. We have Bridgenorth (in Shropshire) to Kidderminster "mostly enclosed ground" (Vol. IV. fol. 182 b). "Bewdley to Milton, Milton to Hertlebury, and hence to Worcester is all described as enclosed Ground (183 b and 184 a), and so also the country between Worcester and Bromsgrove (185 a and 186 b).

APPENDIX D.

GENERAL LEGISLATION AFFECTING ENCLOSURE.

(Previous to the General Enclosure Act of 1845.)

STATUTE OF MERTON (1235), c. 4.

Enabled lords of manors, on leaving sufficient pasture for their tenants on the waste, to enclose the residue; but the lord must prove that the tenants have sufficient pasture, and means of ingress and egress.

STATUTE OF WESTMINSTER. (1285), c. 46.

Enabled lords of manors in which the waste was used as a common pasture by other manors, to enclose against their neighbours, when no specific grant of a right of common pasture had been made. It also provided against the creation of new common rights. "By occasion of a Windmill, Sheepcote, Dairy, enlarging of a court necessary, or Courtelage, from henceforth no man shall be grieved by Assize of Novel Disseisin for Common of Pasture." If after enclosure under this act the hedges are pulled down, the neighbouring townships may be distrained upon for damages.

ACTS FOR THE PROTECTION OF FORESTS.

21 EDWARD IV. (1482), c. 7.

In a forest subject to common rights after a wood has been felled the land may be enclosed for seven years to protect the young timber.

35 HENRY VIII. (1544), c. 17.

Where woods are subject to common rights, lords of manors may enclose one fourth of the wood for seven years, and fell the timber, leaving 12 young trees per acre standing. Meanwhile the lord of the

manor surrenders his common rights upon the remaining three fourths. Kent, Surrey and Sussex were excluded from the operation of the act.

13 ELIZABETH (1571), c. 25.

This makes the preceding Act perpetual.

DEPOPULATION ACTS.

The preamble of the first of this series of Acts, though well known, is here quoted in part.

4 HENRY VII. (1489), c. 19.

"Our King and Sovereign Lord . . . remembreth that . . . great inconveniences do daily increase by desolation and pulling downe, and wilfull waste of houses and townes within this realme and laying to Pasture Lands, which customably have been used in tillage, whereby idlenesse, which is the ground and beginning of all mischiefes, daily doth encrease. For where in some townes two hundred persons were occupied and lived by their lawfull labours, now there are occupied two or three heardmen, and the residue fall into idlenesse, the husbandrie, which is one of the greatest commodities of this Realme is greatly decayed, Churches destroyed, the service of God withdrawn, the bodies there buried, not prayed for. . . ."

To check these evils all occupiers of 20 acres and upwards of land that had been tilled in the previous three years, are required to maintain tillage, under pain of forfeiting to the lord of the manor one half of the profits of such land.

6 HENRY VIII. (1515), c. 5.

This was a temporary Act, in principle identical with the one passed in the following session.

7 HENRY VIII. (1516), c. 1.

This Act applied only to parishes "whereof the more part was or were used and occupied to tillage and husbandry." In such places "If any person shall decay a Town, a Hamlet, or House of

Husbandry, or convert tillage into Pasture” and have not “within j. yeere next after such wylfull decaye reedefyed and made ageyn mete and convenyent for people to dwell and inhabyte the same, and have use, and therein to exerceyse husbandry and tyllage” he forfeits one half of his land to the lord of the manor, until the offence is reformed. Land converted to pasture must again be tilled “after the maner and usage of the countrey where the seyd land lyeth.”

This Act was followed by the Inquisition of 1517.

ACT FOR RESTRAINING SHEEP FARMING.

25 HENRY VIII. (1534), c. 13.

This is an Act to deal with the economic cause of depopulating enclosures.

“Sundry persons have of late daily studied how to gather into few hands great multitude of Farms and great Plenty of Cattle, and in especial Sheep, putting such land as they can get to Pasture, and not to tillage, whereby they have not only pulled down Churches and Towns and inhanced the old Rates . . . so that poor men are not able to meddle with it . . . it is thought that the great occasions that moveth and provoketh those greedy and covetous people . . . is only the great Profit that cometh of Sheep.”

It is said that “some have 24,000, some 20,000, some 10,000, some 6,000, some 5,000 and some more, some less.”

It is enacted that with certain exceptions no one may keep more than 2,000 sheep under a penalty of 3s. 4d. per sheep per annum. half of the fine going to the crown, half to the informer. No man, further, may take more than two farms, and these must not be in the same parish.

DEPOPULATION ACTS.

27 HENRY VIII. (1536), c. 22.

This Act recites 4 Henry VII., c. 19, the first of the Depopulation Acts; and states that it had been enforced only in lands held immediately of the King. Now “the King shall have the Moiety of the Profits of those lands already converted for Tillage to Pasture sithence three years before Ann. 4 H. 7 until the Owner hath builded

up a convenient House to inhabit, and converted the same Pasture to Tillage again; and also take the Moiety of the issues of those lands hereafter to be converted, if the immediate Lord do it not within one year," until the owners have built a Tenement for every 50, 40 or 30 acres, and have reconverted the pasture to tillage. Again it is stipulated that the land shall be tilled "according to the nature of the soil and the course of Husbandry used in the country where any such lands do lie."

27 HENRY VIII. (1536), c. 28.

Persons to whom monastic lands had been granted by Henry VIII. are required to maintain yearly as much of the land in tillage and husbandry as had commonly been so used within the preceding 20 years, under a penalty of 6*l.* 13*s.* 4*d.* per month.

CONFIRMATION OF STATUTE OF MERTON.

3 & 4 EDWARD VI. (1550), c. 3.

This Act cites and confirms the Statutes of Merton and Westminster and facilitates the recovery of damages for breaking down the hedges erected to enclose wastes.

DEPOPULATION ACTS.

5 & 6 EDWARD VI. (1552), c. 5.

This Act requires that so much land be tilled yearly in any parish as had been tilled at any time since the accession of Henry VIII., under a penalty of 5*s.* per acre per annum.

Four Commissioners were to be appointed to enquire into the conversion of arable into pasture.

The Act did not apply to—

- (1) Land that had been pasture for 40 years.
- (2) Waste ground, common downs, fens, moors, marshes.
- (3) Lawful warren.
- (4) Woodland converted into pasture.
- (5) Land in deer parks.
- (6) Salt marshes and inundated land.
- (7) Land enclosed by licence of the King or his predecessor.

2 & 3 PHILIP AND MARY (1555-6), c. 2.

This cites and confirms the original Depopulation Act of 4 Henry VII. and makes it apply to all houses with 20 acres of land, whether the land is in tillage or not.

Commissioners to be appointed to enquire into all grounds converted into pasture since St. George's Day, in the 20th year of Henry VIII. to see to the re-edifying of houses, and the reconversion of pasture into tillage. The exceptions permitted are where lands have been enclosed by the King's licence, and by discretion of the Commissioners in cases where no public benefit, but individual hardship would ensue by the execution of the Act.

Rents increased on the conversion of tillage into pasture were to be abated; re-edified houses were to be let with 20 acres of land or 10 acres if the owner has no more.

The penalty of laying land down into pasture was again fixed at 5s. per acre per annum, half to be paid to the Crown, half to the informer.

5 ELIZABETH (1563), c. 2.

By this Act the more recent Depopulation Acts, 27 Henry VIII. c. 28, 5 & 6 Edward VI. c. 5, and 2 & 3 Philip and Mary, c. 2, were repealed as ineffectual; but the earlier ones, 4 Henry VII. c. 19, 7 Henry VIII. c. 22 and 27 Henry VIII. c. 22, ordered to be put into execution.

It was also enacted that "such lands or so much in quantity in any place as hath been put in Tillage and eared in any one year and so kept four years sithence the feast of St. George the Martyr, anno 20 Henry VIII. shall be eared and kept in Tillage, according to the Nature of the Soil and Custom of the Country by the Occupier thereof."

The penalty was raised to 10s. per acre per annum, and it could be recovered by the next heir in reversion if he sued for it within a year, if not, by the Remainderman, or in default by the lord of the manor, and if not so recovered, by the Crown.

This Act remained in force for thirty years, but was discontinued by 35 Elizabeth (1593), c. 5.

ACT FOR THE PROTECTION OF COTTAGERS' HOLDINGS
AND RIGHTS OF COMMON.

31 ELIZABETH (1589), c. 7.

This Act prohibited the letting of cottages to agricultural labourers with less than four acres of land under a penalty of 40s. per cottage per month, or the occupation of one cottage by more than one family, under a penalty of 10s. per cottage per month. The amount of land attached to cottages let to countrymen following other occupations was also regulated. These holdings were evidently intended to be acres in the arable fields, carrying with them the proportional common rights of pasturage, &c. This Act was repealed in 1775.

DEPOPULATION ACTS.

39 ELIZABETH (1597), c. 1.

In the preamble of this Act it is stated that in late years more than in times past, sundry towns, parishes and houses of husbandry have been destroyed and become desolate. All previous Acts for the re-edification of houses are repealed, and it is enacted that when houses of husbandry have been decayed for more than seven years, half the number must be rebuilt, and 40 acres of land allotted to them; unless the property had been sold meanwhile; in that case the purchaser need only rebuild one quarter of the decayed houses.

Where houses had decayed within the previous seven years, they are to be rebuilt; and if previously they had less than 40 acres of land, they must now at least have 20 acres; if previously they had 40 acres or more, they must now have at least 40 acres.

The penalty for not rebuilding the farmhouse, was £10 per house per annum; for not assigning the prescribed quantity of land, 10s. per acre per annum. One third of the penalty went to the Queen, one third to the parish, one third to the informer.

It is also enacted that it shall be lawful for any lord of the manor to make exchanges of lands, whether arable, pasture or meadow, with his tenants, and for the tenants, with the consent of the lord, to make exchanges with one another, for the sake of more convenient

occupation and husbandry. In other words the re-arrangement of the intermixed holdings in common arable fields and common meadows is expressly sanctioned.

39 ELIZABETH (1597), c. 2.

The preamble states that from the 7th year of Henry VII's reign to the 35th year of the current reign there had always been in force some Act for the maintenance of tillage, but in the latter year all such laws were discontinued ; and that in consequence in the period 1593-1597 "there have grown many more Depopulations by turning Tillage into Pasture than at any time for the like number of years heretofore."

It is enacted that lands converted from tillage to pasture shall be re-converted within three years, and that lands now in tillage shall remain so, under a penalty of 20s. per acre per annum. The Act applies to the counties of Bedford, Berkshire, Buckingham, Cambridge, Derby, Dorset, Durham, Gloucester, Hampshire, Hereford, Huntingdon, Leicester, Lincoln, Northampton, Northumberland, Nottingham, Oxford, Rutland, Somerset, Warwick, Wiltshire, Worcester, Yorkshire, with the Isle of Wight, and Pembroke in South Wales.

It did not apply to Cheshire, Cornwall, Cumberland, Devon, Essex, Hertford, Kent, Lancashire, Middlesex, Monmouth, Norfolk, Shropshire, Stafford, Suffolk, Surrey, Sussex and Westmoreland.

This Act remained on the Statute Book for 266 years. The earlier Depopulation Acts were repealed by 21 James I., c. 28, but this Act remained theoretically part of the law of the land until repealed by the Statute Law Revision Act of 1863. This was the last of the Depopulation Acts. ✓

AN ENCLOSURE ACT.

4 JAMES I. c. 11.

This is really a local Enclosure Act. The people of the parishes of Merden, Bodenham, Wellington, Sutton St. Michael, Sutton St. Nicholas, Murton-upon-Lug, and Pipe in Hereford, had all their lands, whether meadow, pasture or arable, open and intermixed, and commonable "after Sickle and Sithe." They themselves were

accustomed to house their sheep and cattle throughout the year, and the people of neighbouring villages took advantage of this custom to turn in cattle after harvest. The enclosure of one third of the land in each parish is authorised by the Act.

ACTS FOR IMPROVING THE CULTIVATION OF COMMON FIELDS.

13 GEORGE IV. (1773), c. 81.

This Act has been considered in the text.

41 GEORGE III. (1801), c. 20.

This was a temporary Act to encourage the cultivation of potatoes in common arable fields. The famine prices of 1800—1 caused a good deal of curious special legislation. Any occupier of land in common fields is authorised to plant potatoes, and to guard them from cattle grazing in the fields, on giving compensation for the loss of the common right to the other occupiers.

ACTS FOR FACILITATING ENCLOSURE.

41 GEORGE III. (1801), c. 109.

This is the General Enclosure Act promoted by the Board of Agriculture of 1793—1819. It is entitled "An Act for consolidating in one Act certain provisions usually inserted in Acts of inclosure, and for facilitating the mode of proving the several facts usually required in the passing of such Acts."

1 & 2 GEORGE IV. (1821), c. 23.

This amends the previous Act, so as to better regulate the cultivation of parishes during the progress of enclosure by Act.

1 & 2 WILLIAM IV. (1831), c. 42.

By this the churchwardens and overseers of a parish may enclose, up to 50 acres of waste, with the consent of the lord of the manor

and the majority of the owners of common rights, for the relief of the poor rates, or let the land so enclosed to poor and industrious persons. By another Act in the same session (c. 57) the principle is applied to Crown lands.

4 & 5 WILLIAM IV. (1834), c. 30.

An Act to facilitate the exchange of intermixed lands in common fields, by removing difficulties caused by some owners being minors, insane, &c.

6 & 7 WILLIAM IV. (1836), c. 115.

This is an important Act "for facilitating the enclosure of open and arable fields in England and Wales." Two-thirds in number and value of common arable fields may appoint commissioners for carrying out enclosure, as if enclosure had been authorised by a special Act. The awards were to be deposited in the parish churches.

If seven-eighths of the proprietors were agreed, enclosure could be carried out without the appointment of commissioners.

This Act is not to authorise the enclosure of common fields within 10 miles of the centre of London, within 1 mile from the centre of a town of 5,000 inhabitants, $1\frac{1}{2}$ miles from one of 15,000 inhabitants, 2 miles from one of 30,000 inhabitants, $2\frac{1}{2}$ miles from one of 70,000 inhabitants, or 3 miles from one of 100,000 inhabitants.

3 & 4 VICT. (1840), c. 31.

This was an Act amending the last, by extending its scope to lammas meadows; and providing that persons who were dissatisfied with awards under the preceding Act forfeited their right of appeal if they took possession of the lands allotted to them.

APPENDIX E.

A NORFOLK OPEN FIELD PARISH.

THE parish of Runton, adjoining Cromer, is unenclosed, and throws some light on Norfolk common field custom, and on the curious law with regard to "liberties of fold courses." There are in the parish two villages, East and West Runton. Most of the land in the parish is either common, or open field arable land. Of the open field arable, about 600 acres are "half year land" and between four and five hundred acres "whole year land." Both the whole year land and the half year land is intermixed, both in ownership and occupation, but the extent of intermixture has been steadily and continuously reduced. There is a tendency for adjoining strips of land to be let to one and the same farmer, and he is allowed to plough down the balks, in Runton called *lawns* or *loons*, which separate them. There are no common rights over the whole year land. There is an area of whole year land of 200 acres or more around each village, which is where one would expect to find it; and very curiously, a detached area of about 20 acres half way between the villages. There is no well marked boundary separating whole year from half year lands.

The half year lands are commonable from Michaelmas to Lady Day old style, that is from October 11th to April 11th. There is no prescribed rule of cultivation, but the customary course is:—first year, wheat; second, turnips; third, barley sown with clover, the land under this crop being "new ley land" after the barley is reaped; and in the fourth year the land remains under clover and is called "old ley land" or "ollay land."

The peculiar feature, characteristic of Norfolk common field agriculture, is that the owner of the Abbey Farm *in the next parish*, has the right to pasture sheep on the half year lands of Runton; in

the words of the old Act, he has the "liberty of fold courses" of Runton. Further, the Runton common right owners make up a flock called "The Collet Flock," and it is understood that wherever the Abbey flock goes, the Collet Flock can go too.

But the two flocks are kept distinct, grazing separately, each with its own shepherd.

INDEX.

ACREAGE of commons and common fields, 36

Acreage under wheat, 108

Acts for enclosing common fields, 7

Acts for enclosing waste, 7

Ackworth (Yorks.), 123

Adams, H. B.—“Germanic Origin of New England Towns,” 185; “Village Communities of Cape Ann and Salem,” 184

Agriculture, Board of (existing), 16

Agriculture, Board of, (1793—1819), *passim*.

Ailesworth (N. Hants.), 13

Ailesworth Heath, 17

Alconbury (Hunts.), 123

Amesbury (Wilts.), 235

Arden (Warwick), 205

Area of surviving common fields, 189

Area of recently enclosed common fields, 191

Ashby Magna, 208

Averham (Notts.), 137

Avon, the Wiltshire, 112

Avon, the Warwickshire, 205

Axholme, Isle of, 52

Aylesbury, Vale of, 221

BABRAHAM (Cambs.), 210

Baird and Foot, “Middlesex,” 218

“Balks,” 15, 63

“Bancroft Field,” 61

“Barley Field,” 14

Barnaby (Suffolk), 128

Barrowden (Rutland), 64

Bartlow (Cambs.), 82

Barton (Westmoreland), 177

Barton Turf (Norfolk), 127

Battersea common fields, 77

“Bean Field,” 12

Bear, W. E., Report to the Labour Commission on Agricultural Labour, 137

Beddington and Wallington (Surrey), 41

Bedfordshire, enclosure of, 192

Belton (Axholme), 52

Belvoir, Vale of, 97, 200

Bensington (Oxon.), 51

Bentham, J.—“Societie of the Saints,” 160; “Christian Conflict,” 202

Berkshire, enclosure of, 238

Berwick Salome (Oxon.), 51

Bestmoor (Oxon.), 35

Bishton, J., “Shropshire,” 252

“Black Corn Field,” 71

Blyth, W., “The English Improver,” 111, 201, 203, 219, 226, 253

Boldon book, the, 34

Bosworth (Leicester), 201

Boxworth (Cambs.), 210

Boys, “Kent,” 39, 230

Braunton Great Field, 159, 250

“Brecks,” 79

“Brewers’ Ash Field,” 20

Brightwell (Berks.), 68

Brixworth (N. Hants), 104

“Broad Mead,” 67

“Broad Oxgangs,” 31, 32

Buckinghamshire, enclosure of, 219

Burley estate small holdings, 138

Burnham (Suffolk), 180

“Buscall’s,” 78

Bygrave (Herts.), 45

CAMBRIDGESHIRE, enclosure of, 208

Carew, “Cornwall,” 18, 160, 247

Carlton in Lindrick, 127

Carmichael, A., on Runrig, 166

Carpenter of village community, 34

“Carrs,” 78, 79

Castle Camps (Cambs.), 75

Castor (N. Hants.), 13

Catthorpe (Leicester), 111, 208

Celery growing in Axholme, 57

“Champaine,” or “Champion,” 64, 70, 205

“Changeable Allotments,” 24

Charnwood Forest, 204

Cheshire, enclosure of, 252

Chilterns, the, 231

“Chimney Peepers,” 22

- Clark, J.—"Hereford," 125, 252;
 "Radnor," 244
 "Clipsatt Field," 61
 Clothall (Herts.), 43
 Cobbett, W., "Rural Rides," 112, 113, 237
 Colchester, 214
 "Comachadh," 168
 Constable of manor, 22, 34
 Cornwall, enclosure of, 247
 "Cotes," 21
 Cotswold Hills, 241
 Cottage holdings, 121, 137
 "Country Farmer, A," 98, 131
 "Country Gentleman, A," 95
 Court rolls, 20
 Cow dung as fuel, 201
 "Cowleaze," 30
 Cowper, John, "Inclosing Commons, etc.," 110, 154
 Crutchley, "Rutlandshire," 77
 Cumberland, enclosure of, 256
 Cunningham, W., "Growth of English Industry," 91, 115
 "Customary Cottages," 29

 "DALES," 257
 Dartmoor, 170, 248
 Davis, R., "Oxfordshire," 76, 222
 Davis, T., "Wiltshire," 76, 77, 113, 114, 115, 236
 Deddington (Oxon.), 103
 Derbyshire, enclosure of, 228
 Devonshire, enclosure of, 245
 "Discourse of the Commonweal," 39, 214, 246
 Disputes in open fields, 15, 16, 47
 "Doles," 21, 78, 79
 "Dolemeads," 79
 Donaldson, J., "Northamptonshire," 197
 Dorset, enclosure of, 240
 "Down Field," 61
 Downham (Cambs.), 210
 Durham, enclosure of, 229

 EAKING (Notts.), 12
 Earsham (Norfolk), 128
 "East Field," 20
 Eden, "Condition of the Poor," 102, 103, 104, 256
 Elmstone Hardwick (Glos.), 15, 47
 Eltham (Kent), 232
 Ely (Cambs.), 210
 Enclosure, meaning of, 1
 Enclosure, methods, 6
 Enclosure, typical act of, 3
 Engrossing of farms, 68
 Epping Forest, 2, 17
 Epworth (Axholme), 52
 Erchenfeld, 253
 Essex, enclosure of, 213
 Evenley (N. Hants), 127
 "Everington Field," 69
 "Every Year Lands," 80, 178
 Ewelme (Oxon.), 50

 "FARTHINGHOLDS," 30
 "Field Jury," 11
 Fiennes, Celia, "Tour," 201, 212, 214, 222, 224, 226, 228, 229, 231, 238, 252, 255
 Flax growing in Axholme, 54
 "Fold Courses," 83
 Fordington (Dorset), 30
 Fordington Field, 19, 30
 "Foreman of the Fields," 11, 14
 Forrest, W., "Princelye Poesie," 10
 Foston (Leicester), 100
 "Four Field Course," 48, 74
 Fox, J., "Glamorganshire," 244
 Frilsham Common, 69
 Frome R., 20
 Furze common (Ewelme), 51

 GATESHEAD (Durham), 177
 "Gathering and Splitting," 15
 Gavelkind, 245
 General Enclosure Acts, 17
 General report on enclosures, 95, 108, 123, 124, 129, 161
 Gloucestershire, enclosure of, 241
 Granger, J., "Durham," 154, 229
 "Great Horse Shoe," 27
 Great Sheepy (Leicester), 127
 Grimspound (Dartmoor), 170
 Grimston (Leicester), 138
 Grimstone (Dorset), 19
 Grimstone common rights, 31
 Gunnerton (Northumberland), 179

 HADLEY Wood, 2
 Hagbourne, West (Berks.), 68
 Hale, J., defence of, 150
 "Half-Livings," 22
 "Half-Plow," 172
 "Half-Year Lands," 78, 80
 Ham Field (Surrey), 65
 Hambleton cow pasture, 138
 Hampshire, enclosure of, 240
 Hampstead Heath, 2, 17
 Hasbach, W., "Die E. Landarbeiter," 61
 Hassell, C. — "Carmarthen," 244;
 "Pembroke," 244
 "Hatching Ground," 23

- Haxey (Axholme), 52
 "Haywards," 22, 34
 "Headlands," 15
 Hendred, East and West (Berks.), 68
 Henlow (Beds.), 3
 Herefordshire, enclosure of, 252
 Herringswell (Suffolk), 127, 188
 Hertfordshire, enclosure of, 218
 High Prices, Select Committee on, 108
 Hildersham (Cambs.), 82
 "Hitchland," 20, 76
 "Hole Rush," 25
 Holt, J. "Lancashire," 255
 "Hookland," 20, 76
 "Hook Mead," 67
 "Horse's Foot of Land," 173
 "Horse-gang," 172
 Houghton, J., "Collection," 155, 157
 Howlett, J., 91, 100
 "Hundred Acres," 24, 28
 Hunmanby (Yorks.), 88
 Huntingdon, enclosure of, 212

 ICKLINGHAM (Suffolk), 180
 Iken (Suffolk), 214
 Ilsley, East and West, 68
 "Infields," 80, 81, 187
 "Ings," 78, 79
 Insurrections and enclosure, 112, 150
 Intermixed lands, 243
 Isleham (Cambs.), 74
 Ivel, R., 4

 JAMES and Malcolm—"Buckinghamshire," 75, 219; "Surrey," 77, 233

 KAY, G.—"Flint," 244; "Carnarvon," 244
 Kent, enclosure of, 230
 Kent, "Norfolk," 85, 216, 217
 Kets' Rebellion, 150
 Kibworth Beauchamp (Leicester), 103

 LAMBARDE, W., "Perambulation of Kent," 231
 "Lacy's Bridge Man," 22
 Lancashire, enclosure of, 255
 "Lands," 9
 "Land spoilers," 67
 "Langford Field," 20
 "Launchers," 250
 Laurence, J., "New System of Agriculture," 153
 "Lawnds," or "Lawns," 20
 Lawrence, E., "Duty of Steward," 152, 155, 201, 207
 Laxton (Notts.), 8
 Laxton Heath, 9
 Leadam, W. S., "Domesday of Inclosures," 212, 225
 Leatham, I., "East Riding," 77, 89
 Lee, Joseph, 111, 161, 202
 Leland's Itinerary, 203, 205, 212, 219, 221, 222, 224, 228, 239, 253, 256
 Letcomb (Berks.), 123
 "Leyland," 77
 "Liberty of Fold Courses," 83
 Lincolnshire, enclosure of, 222
 Little Brandon (Norfolk), 127
 "Little Horse Shoe," 28
 Littleport (Cambs.), 210
 "Livings," 21
 Llanerfyl, 42
 Lloyd, T., "Cardiganshire," 244
 Lolworth (Cambs.), 210
 "Longlands," 26
 Long Sutton (Lincoln), 263
 "Loons," or "Lownts," 20
 "Lot Meadows," 35
 Lowe, R., "Nottinghamshire," 92, 227
 Luffenhall (Herts.), 45
 Luffenham, North and South (Rutland), 64
 Lynches, 70

 "MAAM" soil, 233
 Macdonald, J., "Hebrides," 173
 "Machair," 166
 Madingley (Cambs.), 210
 Maids Morton (Bucks.), 102
 Maitland, F. W., "Select Pleas," 156
 Manor bull, 23
 Marshall, W., "Central Highlands," 172, 180; "Rural economy of: Gloucestershire," 108, 153, 241; "Norfolk," 79; "Yorkshire," 156; "Midlands," 206; "Southern District," 232, 235; "West of England," 248
 Massachusetts, decrees for common fields, 185
 Massie, J., 91
 Matton (Lincoln), 177
 Maxwell, G., "Huntingdonshire," 74, 212
 Mercian type of village community, 8
 Mere (Wilts.), 236
 "Meres," 63
 Merrow (Surrey), 66
 Merton, statute of, 6
 "Mesne inclosures," 225
 "Middle Field," 20
 Middlesex, enclosure of, 218
 "Mill Bars Patch," 26
 "Mill Field," 8, 16
 "Mingle Mangle," 18

- Misterton (Leicester), 208
 Monk, R., "Leicestershire," 198
 Monmouthshire, enclosure of, 252
 Moore, John, 111, 201, 208
 More, Sir T., "Utopia," 116
 Moreton, North (Berks.), 70
 Morgan, G. B., "Cornwall," 249

 "NARROW Oxcgangs," 31
 Nen, R., 17
 "Nether Field," 16
 "New Closes," 21
 Newborough (N. Hants.), 197
 Newtontony (Wilts), 200
 "No Ditch Field," 61
 Norden, J., "Book of Surveying," 155,
 214, 238
 Norfolk, enclosure of, 217
 Norham, 179
 "Normangate Field," 16
 Northamptonshire, enclosure of, 197
 Northbourne (Kent), 42
 "North Field," 61
 Northumberland, enclosure of, 259
 Northwold (Norfolk), 128
 Nottinghamshire, enclosure of, 227

 ONE field system, 179
 Orford (Suffolk), 214
 Ossington (Notts.), 137
 Outer Hebrides, 166
 "Out Field," 77, 179
 Over (Cambs.), 210
 Owston (Axholme), 52
 Oxfordshire, enclosure of, 222
 "Oxcgangs," 31

 PALLING (Norfolk), 127
 Palmer, A. N.—"Ancient Tenures,"
 174, 245; "Wrexham," 20
 Pang, R., 69
 Parish Meeting, powers of, 50
 Passenham (N. Hants.), 123
 Pearce, W., "Berkshire," 76
 Pickering moor, 128
 Pickering, vale of, 157
 "Pindar," 56
 Pitt, W.—"Arable and Grassland,"
 95; "Leicestershire," 97, 200;
 "Staffordshire," 252
 "Places" (= Livings), 28
 "Plowgait," 172
 Poor rates and enclosure, 102
 Poppleton, 132
 Potato growing in Axholme, 57
 Potterne (Wilts.), 126
 Poultny (Leicester), 208
 Produce of common fields, 79, 111

 Produce of enclosed land, 100, 111
 Profit of enclosure, 98, 263

 QUILLETED fields, 42, 253
 Quillets, 83, 266

 "RANES," 257
 Rathbone, G., "Eltham Charities," 232
 Recreation grounds, 18, 65, 71, 118
 "Reeve," 34, 89
 Re-living copyholds, 19
 Re-living leaseholds, 48
 Renhold (Beds.), 44
 Rents before and after enclosure, 100,
 103, 111
 Richmond Hill, view from, 66
 "Rick Field," 20
 Rider Haggard, "Rural England," 57,
 138
 "Ridge and Furrow," 94
 Riots and enclosure, 112
 Robertson, J., "Perthshire," 165, 173
 "Robin Hood and Little John," 17
 Rockingham forest, 197, 204
 "Rotation Meadows," 35
 "Rounds," 88
 Royal burghs of Scotland, 164
 "Rundale," 6
 "Runrig," 6, 166, 244
 Rutland, enclosure of, 203

 SANDWICH Town Neck, 183
 Salem north and south fields, 185
 Salisbury, environs of, 235
 Seeborn, F., "English Village Com-
 munity," 179
 "Selions," 56
 "Shackage," 45, 78, 79
 "Shack Lands," 78
 "Shealing Feast," 170
 Sheepflock of village community, 22
 Sheepwalk, right of, 45
 Shilton (Berks.), 35
 Shropshire, enclosure of, 252
 "Sicks," 11
 Sinclair, Sir J., "Northern Counties
 of Scotland," 165, 172
 Six year course, 76
 Skene, "Celtic Scotland," 166, 173
 Small holdings, 58, 61, 119
 Small holdings, profit of, 121, 136, 139
 Smith, Adam, "Wealth of Nations,"
 94
 Soham (Cambs.), 61, 210
 Somerset, enclosure of, 242
 "Souming," 168
 "Square Patch," 27
 Staffordshire, enclosure of, 252

"Stake Weir," 27
 Stamford (Lincoln), 177
 Steeple Claydon, 75
 Stevenon (Berks.), 68, 71
 "Stint Book," 14
 Stone, T.—"Bedfordshire," 74; "Lincolnshire," 77, 223
 Stratton (Dorset), 19
 Stratton common rights, 31
 Stratton meadow, 24, 25
 Studham, 44
 Suffolk, enclosure of, 214
 Surrey, enclosure of, 233
 Sussex, enclosure of, 232
 Sutton (N. Hants.), 46
 Sutton Coldfield (Warwick), 254

 "TENANTRY," 113
 Tithe commutation and enclosure, 40, 188
 Tithe maps, 188
 "Thorn Field," 16
 Three field course, 8, 14, 74
 "Three Patches," 26
 Todenham (Gloucester), 123
 "Tofts," 10
 Totternhoe (Beds.), 63
 Tudor licences for enclosure, 6
 Tulvey (Beds.), 123
 Turnip culture, 81
 Tusser, "Champion and Several," 82,
 Tythingman, 22
 Two field course, 71, 76

 UPTON St. Leonards (Gloucester), 18, 63

 VALUE of land in Axholme, 60
 Vancouver — "Cambridgeshire," 75, 209; "Essex," 213
 Venteland (Gwent), 253
 "Viewers of the Fields," 22

Village community, types of, 6
 "Virgates," 30

 WALES, enclosure of, 243
 Wales, W., 91
 Walker, D., "Hertfordshire," 75, 125
 Wallingford (Berks.), 68
 Wallington (Herts.), 45
 "Walls," 21
 Water meadows, 116
 Weald, enclosure of the, 232
 Wedge—"Warwickshire," 204, "Cheshire," 101, 252
 Wessex type of village community, 19
 Westmoreland, enclosure of, 256
 Weston field, 62
 Weston Zoyland (Somerset), 61
 "Wheatfield," 14
 "Whitecorn field," 71
 White Horse, vale of, 238
 "Whole Livings," 21
 "Whole Year Lands," 80, 81
 Wilbraham (Cams.), 128
 Wimeswold (Leicester), 127
 Winslow (Bucks), 102
 Wistow (Leicester), 100, 101
 "Wood Field," 16
 Worcestershire, enclosure of, 242
 Wordsworth, H. W., "Lake District," 257
 Wytham-on-the-Hill (Lincoln), 179

 "YARDLANDS," 30, 113
 Yattenden (Berks.), 68, 69
 Yelden (Beds.), 44
 Yelling (Hunts.), 180
 Yorkshire, enclosure of, 224
 Yorkshire wolds, 77
 Young, A.—"Lincolnshire," 53, 177, 263; "Eastern Tour," 94, 107, 201, 217, 221; "Northern Tour," 94, 107, 195, 224, 226, 230; "Political Arithmetic," 105; "Wastes," 126, 128

THE LONDON SCHOOL OF ECONOMICS AND POLITICAL SCIENCE

(UNIVERSITY OF LONDON).

CLARE MARKET, KINGSWAY, LONDON, W.C.

THE special aim of the London School of Economics and Political Science is the study and investigation of Economic and Political Institutions.

The Classes and Lectures provide a complete course of study in the Faculty of Economics and Political Science (including Commerce and Industry) of the reorganized University of London. The course extends over three years and prepares candidates for the Degree of B.Sc. in Economics. A large proportion of the teaching required in the Faculty of Law is also provided by the courses at the School.

Some of the Classes and Courses of Lectures are designed to promote a wider knowledge of modern commercial conditions, and to meet the needs of those engaged in the Civil and Municipal Services, Journalism, Teaching and Public work. Training in methods of Investigation is also provided, especially in Historical Research, by the courses in Diplomatic and Palæography, and in Modern Economic Research by the courses in Statistics and others. The School also affords facilities for Original Work in Economics, History and Political Science.

A Library containing all the ordinary Standard Works of Reference and a very large amount of original and, in some cases, unique, material for Research, is attached to the School and is open gratuitously to all Students and to others on application to the Director.

The Fee for the full Course is £10 10s. per Session or £4 4s. per Term. Students are also admitted to single courses of Lectures at Special Fees, varying with the length of the course.

The Lectures and Classes are held in the daytime and also in the evening between 6 and 8 p.m.

The School is open to Men and Women.

The Academic Year begins in October and the Session of thirty weeks is divided into three terms, viz.:—Michaelmas Term, October to December; Lent Term, January to March; and Summer Term, April to June. Students may join the School at any time.

Scholarships varying in value from £15 to £100 are offered for competition from time to time.

Full particulars may be obtained on application to the Director.

NEW WORK BY SIDNEY AND BEATRICE WEBB.

English Local Government from the Revolution to the Municipal Corporations Act—The Parish and the County.

Published 1 Oct., 1906. Post 8vo, with Index, 650 pp. Price 16s. net.

ADVERTISEMENT.

More than that of any other Anglo-Saxon country, English Local Government is rooted in the past, and its contemporary problems can be neither fully understood nor adequately solved without a knowledge of how they have arisen. This work, the firstfruits of seven years' investigation into the development of English Local Government, combines a detailed history of local administration in parish and county throughout England and Wales from 1689 to 1835, with a descriptive analysis of the interesting constitutional evolution of this most fruitful period, when local authorities were practically free from supervision or control.

Avoiding discussions as to the origins of English local institutions, or even as to their growth during the Middle Ages, it describes in vivid detail the development of structure and function which led to the reforms of 1832-35, on which our present system is based. This description is framed on new lines and drawn almost entirely from materials hitherto unused. Instead of dealing principally with the law of local government, and the successive changes in the Statute-book, the institutions themselves, and the persons who worked them, are described as vital social tissue. The subject matter is, in fact, not law or politics, but the life-history of the various species of local governing bodies.

The manuscript records of county and parish from Northumberland to Cornwall, from Cardigan to Kent, elucidated by contemporary literature and biography, enable the authors to present an entirely new picture of the internal history of England in the eighteenth century, revealing what Justice of the Peace and Churchwarden really were, in their habits as they lived, the way in which the daily administration of the Parish and County was actually carried on, the manner in which the daily life of the people was affected by contemporary influences, and the result, both on the health and character of the nation, and in producing the difficulties that in the twentieth century confront us.

The present work is complete in itself. Subsequent volumes will deal similarly with Seignorial Franchises and Municipal Corporations, Statutory Bodies for Special Purposes, Local Administration in relation to Poverty and Crime and in relation to Public Health and Convenience, etc.

LONGMANS, GREEN & CO.,
LONDON, NEW YORK AND BOMBAY.

OTHER WORKS BY SIDNEY AND BEATRICE WEBB,

INDUSTRIAL DEMOCRACY. Post 8vo; Seventh Thousand; new edition in one vol., with new Introductory Chapter (1902); lxi. and 929 pp., with two diagrams. Price 12s. net.

A scientific description and critical analysis of all the forms of Trade Unionism and Factory Legislation in the United Kingdom. A storehouse of authenticated facts and philosophical criticism about every branch of the "Labour Question."

"A permanent and invaluable contribution to the sum of human knowledge We commend to the public a book which is a monument of research and full of candour. . . . Indispensable to every publicist and politician."—*Times* (on day of publication).

THE HISTORY OF TRADE UNIONISM. Post 8vo; Eighth Thousand; new edition, with new Introductory Chapter (1902); xxxiv. and 558 pp. Price 7s. 6d. net.

"A masterly piece of work"—*Times*.

"To the politician . . . an invaluable guide."—*Observer*.

PROBLEMS OF MODERN INDUSTRY. Post 8vo; Third Thousand; new edition, with new Introductory Chapter (1902); xx. and 286 pp. Price 5s. net.

THE HISTORY OF LIQUOR LICENSING IN ENGLAND. Small 8vo; Seventh Thousand; viii. and 162 pp. Price 2s. 6d. net.

LONDON EDUCATION. By SIDNEY WEBB. Small 8vo; viii. and 219 pp. Price 2s. 6d. net.

A description of the Educational organisation of London in 1903, with a survey of some of its administrative problems—avoiding both politics and religion.

LONGMANS, GREEN & Co., London, New York & Bombay.

Published by **SWAN, SONNENSCHN & Co.**

THE CO-OPERATIVE MOVEMENT IN GREAT BRITAIN. By BEATRICE POTTER (Mrs. Sidney Webb). Crown 8vo; Second edition (1893); Fifth Thousand; xii. and 260 pp.; with coloured map, appendices and index. Price 2s. 6d.

"Without doubt the ablest and most philosophical analysis of the co-operative movement which has yet been produced."—*Speaker*.

SOCIALISM IN ENGLAND. By SIDNEY WEBB. Crown 8vo; Second edition (1894); with new Introductory Chapter; xxii. and 136 pp. Price 2s. 6d.

THE LONDON PROGRAMME. By SIDNEY WEBB. Crown 8vo; Second edition (1894), with new Introductory Chapter; viii. and 214 pp. Price 2s. 6d.

STUDIES IN ECONOMICS

AND

POLITICAL SCIENCE.


A Series of Monographs by Lecturers and Students connected with the London School of Economics and Political Science.


EDITED BY THE

DIRECTOR OF THE LONDON SCHOOL OF ECONOMICS AND POLITICAL SCIENCE.

1. **THE HISTORY OF LOCAL RATES IN ENGLAND.** The substance of Five Lectures given at the School in November and December, 1895. By EDWIN CANNAN, M.A., LL.D. 1896. 140 pp., Crown 8vo, Cloth. 2s. 6d. P. S. KING & SON.
2. **SELECT DOCUMENTS ILLUSTRATING THE HISTORY OF TRADE UNIONISM.** I.—The Tailoring Trade. By F. W. GALTON. With a Preface by SIDNEY WEBB, LL.B. 1896. 242 pp., Crown 8vo, Cloth. 5s. P. S. KING & SON.
3. **GERMAN SOCIAL DEMOCRACY.** Six Lectures delivered at the School in February and March, 1896. By the Hon. BERTRAND RUSSELL, B.A., late Fellow of Trinity College, Cambridge. With an Appendix on Social Democracy and the Woman Question in Germany. By ALYS RUSSELL, B.A. 1896. 204 pp., Crown 8vo, Cloth. 3s. 6d. P. S. KING & SON.
4. **THE REFERENDUM IN SWITZERLAND.** By M. SIMON DEPLOIGE, University of Louvain. With a Letter on the Referendum in Belgium by M. J. VAN DEN HEUVEL, Professor of International Law in the University of Louvain. Translated by C. P. TREVELYAN, M.A., Trinity College, Cambridge, and edited with Notes, Introduction, Bibliography, and Appendices, by LILIAN TOMN, of Girton College, Cambridge, Research Student at the School. 1898. x. and 334 pp., Crown 8vo, Cloth. 7s. 6d. P. S. KING & SON.
5. **THE ECONOMIC POLICY OF COLBERT.** By A. J. SARGENT, M.A., Senior Hulme Exhibitioner, Brasenose College, Oxford; and Whately Prizeman, 1897, Trinity College, Dublin. 1899. viii. and 138 pp., Crown 8vo, Cloth. 2s. 6d. P. S. KING & SON.
6. **LOCAL VARIATIONS IN WAGES.** (The Adam Smith Prize, Cambridge University, 1898.) By F. W. LAWRENCE, M.A., Fellow of Trinity College, Cambridge. 1899. viii. and 90 pp., with Index and 18 Maps and Diagrams; Quarto, 11 in. by 8½ in., Cloth. 8s. 6d. LONGMANS, GREEN & Co.

7. **THE RECEIPT ROLL OF THE EXCHEQUER FOR MICHAELMAS TERM OF THE THIRTY-FIRST YEAR OF HENRY THE SECOND (1185).** A unique fragment transcribed and edited by the Class in Palæography and Diplomatic, under the supervision of the Lecturer, HUBERT HALL, F.S.A., of H.M. Public Record Office. With thirty-one Facsimile Plates in Collotype, and Parallel Readings from the contemporary Pipe Roll. 1899. vii. and 37 *pp.*; *Folio*, 15½ *in.* by 11½ *in.*, Green Cloth; two copies left. £2 15s. 0d. *net.* Apply to the Director, The School of Economics.
8. **ELEMENTS OF STATISTICS.** By ARTHUR L. BOWLEY, M.A., F.S.S., Cobden and Adam Smith Prizeman, Cambridge; Guy Silver Medallist of the Royal Statistical Society; Newmarch Lecturer, 1897-98. 500 *pp.*, *Demy 8vo*, Cloth. 40 Diagrams. 1901. Second Edition, 1902. viii. and 336 *pp.* 10s. 6d. *net.*
P. S. KING & SON.
9. **THE PLACE OF COMPENSATION IN TEMPERANCE REFORM.** By C. P. SANGER, M.A., late Fellow of Trinity College, Cambridge; Barrister-at-Law. 1901. viii. and 136 *pp.*, *Crown 8vo*, Cloth. 2s. 6d. *net.*
P. S. KING & SON.
10. **A HISTORY OF FACTORY LEGISLATION, 1802-1901.** By B. L. HUTCHINS and A. HARRISON, B.A., D.Sc. London. With a Preface by SIDNEY WEBB, LL.B. 1903, xviii. and 372 *pp.*, *Demy 8vo*, Cloth. 10s. 6d. *net.* Cheap Edition, 3s. 6d.
P. S. KING & SON.
11. **THE "PIPE ROLL" OF THE "EXCHEQUER" OF THE SEE OF WINCHESTER FOR THE FOURTH YEAR OF THE EPISCOPATE OF PETER DES ROCHES (1207).** Transcribed and edited from the original Roll in the possession of the Ecclesiastical Commissioners by the Class in Palæography and Diplomatic, under the supervision of the Lecturer, HUBERT HALL, F.S.A., of H.M. Public Record Office. With a Frontispiece giving a Facsimile of the Roll. 1903. xlviii. and 100 *pp.*, *Folio*, 13½ *in.* by 8½ *in.*, Green Cloth. 15s. *net.*
P. S. KING & SON.
12. **SELF-GOVERNMENT IN CANADA AND HOW IT WAS ACHIEVED: The Story of Lord Durham's Report.** By F. BRADSHAW, B.A., Senior Hulme Exhibitioner, Brasenose College, Oxford. 1903. 414 *pp.*, *Demy 8vo*, Cloth. 10s. 6d. *net.* Cheap Edition, 3s. 6d.
P. S. KING & SON.
13. **HISTORY OF THE COMMERCIAL AND FINANCIAL RELATIONS BETWEEN ENGLAND AND IRELAND FROM THE PERIOD OF THE RESTORATION.** By ALICE EFFIE MURRAY, D.Sc., former Student at Girton College, Cambridge; Research Student of the London School of Economics and Political Science. 1903. 486 *pp.* *Demy 8vo*, Cloth. 10s. 6d. *net.* Cheap Edition, 3s. 6d.
P. S. KING & SON.
14. **THE ENGLISH PEASANTRY AND THE ENCLOSURE OF COMMON FIELDS.** By GILBERT SLATER, M.A., St. John's College, Cambridge, D.Sc. (London). 1906. 337 *pp.*, *Demy 8vo*, Cloth. 10s. 6d. *net.*
A. CONSTABLE & Co.





84

PLEASE DO NOT REMOVE
CARDS OR SLIPS FROM THIS POCKET

UNIVERSITY OF TORONTO LIBRARY

Ec.H
36317s

Slater, Gilbert
The English peasantry and
the enclosure of common fields.

